

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

September 28, 2017

Responsible Party 1: Williams Nicolas 127 MITCHELLS LN MIDDLETOWN, RI 02842		
Location 24 SHERIDAN ST	CBL 017 G015001	Inspection Date 8/29/2017
Inspector Gene Cote	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 10/15/2017.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
NFPA 101- TABLE 8.3.4.2 UNRATED WINDOWS ARE NOT PERMITTED IN EXIT STAIRS; Fire window assemblies are not permitted in vertical shafts (including stairways, exits, and refuse chutes). Apt doors have non rated glass in door leading to stairs	___/___/___
NFPA 101-7.10.5.1 NORMAL ILLUMINATION FOR EXITS; Every sign required by 7.10.1.2, 7.10.1.5, or 7.10.8.1, other than where operations or processes require low lighting levels, shall be suitably illuminated by a reliable light source. Externally and internally illuminated signs shall be legible in both the normal and emergency lighting mode. Front entrance/exit has no illumination	___/___/___
NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements. 2nd floor apt smoke detector missing/not working check all	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.
NFPA 101- 9.1.2 CERTIFY ELECTRICAL SYSTEM; Electrical wiring and equipment shall be in accordance with NFPA 70, unless such installations are approved existing installations, which shall be permitted to be continued in service. Have your electrician label all breakers.	

Violation	Proposed Date of Completion
<p>NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS; Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating.</p> <p>various locations in basement, some may be old and not is use</p>	<p>___ / ___ / ___</p>
<p>NFPA 70- 590.6 EXTENSION CORDS; Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities.</p> <p>rear exit running through the door jam</p>	<p>___ / ___ / ___</p>
<p>NFPA 70- 4.10.8 DEFECTIVE LIGHT FIXTURE; Luminaries shall be installed such that the connections between the luminaire conductors and the circuit conductors can be inspected without requiring the disconnection of any part of the wiring unless the luminaries are connected by attachment plugs and receptacles.</p> <p>above the panels in basement</p>	<p>___ / ___ / ___</p>
<p>NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers)</p> <p>Need domestic sprinkler head protection above the new gas furnace.</p>	<p>___ / ___ / ___</p>
<p>NFPA 1, CHAPTER 10 - 10.11.6 HIBACHI OR GRILL ON BALCONY; NO HIBACHI, GAS-FIRED GRILL, CHARCOAL GRILL, OR OTHER SIMILAR DEVICES USED FOR COOKING, HEATING, OR OTHER PURPOSE, SHALL BE USED OR KINDLED ON ANY BALCONY OR UNDER ANY OVERHANG PORTION OR WITHIN 10 FTOF ANY STRUCTURE</p> <p>Grills on 3rd floor</p>	<p>___ / ___ / ___</p>
<p>NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour.</p> <p>All 3 Apts all doors, basement door in rear stairwell</p>	<p>___ / ___ / ___</p>
<p>NFPA 1- 10.1.1 STRUCTURE NEEDS REPAIR; Every new and existing building or structure shall be constructed, arranged, equipped, maintained, and operated in accordance with this code so as to provide a reasonable level of life safety, property protection, and public welfare from the actual and potential hazards created by fire, explosion, and other hazardous conditions.</p> <p>Rear deck on the first floor needs repair. Consult with City of Portland Code Enforcement on the permit procedure.</p>	
<p>NFPA 720- 5.5.6.1 CO ALARMS REQUIRED; The performance, location, and mounting of notification appliances used to initiate or direct action, evacuation or relocation of the occupants, or for providing information to occupants or staff, shall comply with the requirements of Chapter 6.</p> <p>Required in all units and the basement.</p>	
<p>FINAL DATE OF COMPLETED VIOLATION(S)</p>	<p>___ / ___ / ___</p>
<p>FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)</p>	<p>___ / ___ / ___</p>

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date

Responsible Party

Date

Responsible Party

SEEN AND AGREED

Date

Fire Prevention Bureau