

NOTES:
1. USE ACI REQUIREMENTS FOR THE MINIMUM COVER OF REINF.
2. PROVIDE 2-#6 T&B HORIZ MIN., UNLESS NOTED OTHERWISE.
3. "L" SHALL BE THE LARGER OF "L1" OR "L2".

1 CONCRETE GRADE BEAM DETAIL
3/4" = 1'-0"

GRADE BEAM SCHEDULE

MARK	WIDTH x DEPTH WxD	BOT. REINF. CONTINUOUS	TOP REINF. CONTINUOUS	STIRRUPS			REMARKS
				TYPE	SIZE	SPACING	
GB1	2'-4"x3'-3"	4-#9	4-#9		#4	18"	1 ADD'L. #9 EA. SIDE
GB2	1'-2"x4'-6"	3-#9	3-#9		#4	12"	6 ADD'L. #9 EA. SIDE
GB3	1'-2"x3'-11"	3-#9	3-#9		#4	12"	HORIZ. SIDE BARS #4@ 12" O.C. EF
GB4	1'-2"x3'-2"	3-#9	3-#9		#4	12"	HORIZ. SIDE BARS #4@ 12" O.C. EF

STATE OF MAINE
RIMANTAS M. VEITAS
No. 9477
LICENSED PROFESSIONAL ENGINEER
Date: 10/27/17

Reviewed for Code Compliance
Inspection Division
Portland, Maine

Prepared For: 0 Hancock Street LLC

Consulting Engineer: VEITAS pue VEITAS engineers
890 Granite Street Suite 101
Braintree, Massachusetts 02184
TEL:(781)842-2868 FAX:(781)849-2065

Architect: ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project: 0 HANCOCK STREET
0 HANCOCK STREET
PORTLAND, MAINE

Revisions:
08-11-17 Issued for Foundation Permit
08-31-17 Permit Set
09-15-17 Steel Bid Set
09-22-17 Pile Bid Set
09-29-17 Concrete Bid Set
10-06-17 Issued for Permit

Date: 08/11/17
Scale:
Grade Schedule & Details

S306