



**1 LEAF TYPES**

1/4" = 1'-0"

**PUBLIC AREA DOOR SCHEDULE**

DOOR No.	LOCATION	SIZE			TYPE	DOOR LEAF		DOOR FRAME		THRESHOLD	LABEL	OPERATION	SWEEP	CLOSER	REMARKS
		WIDTH	HEIGHT	THICKNESS		MATERIAL	FINISH	MATERIAL	FINISH						
<b>1ST FLOOR</b>															
101	STAIR A	3'-6"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
102	STAIR B	3'-6"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
103	STAIR B	3'-6"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	INSULATED
104	STAIR C	3'-6"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
105	STAIR C	3'-6"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	INSULATED
106	ENTRY	6'-0"	8'-0"	1 3/4"	9	ALUM	-	ALUM	-	ALUM	-	ENTRY	Yes	Yes	
108	ELEC. ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	STOR.	Yes	Yes	
109	ELEC. ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	STOR.	Yes	Yes	
110	ELEC. ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	ENTRY	Yes	Yes	INSULATED
111	SERVICE AREA	8'-0"	9'-0"	1 1/2"	12	MTL	PTD.	MTL	PTD	-	-	O.H. DOOR			OVER HEAD DOOR FOR SERVICE ENTRY, INSULATED
112	SERVICE AREA	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	-	ENTRY	Yes	Yes	INSULATED
113	UTILITY ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	STOR.	Yes	Yes	
114	UTILITY ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	ENTRY	Yes	Yes	INSULATED
115	ENTRY	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	-	ENTRY	Yes	Yes	INSULATED
116	ENTRY	6'-0"	8'-0"	1 3/4"	9	ALUM	-	ALUM	-	ALUM	-	ENTRY	Yes	Yes	FUTURE TENANT DOOR, TO BE LOCATED
117	ENTRY	3'-0"	8'-0"	1 3/4"	8	ALUM	-	ALUM	-	ALUM	-	ENTRY	Yes	Yes	FUTURE TENANT DOOR, TO BE LOCATED
118	ENTRY	3'-0"	8'-0"	1 3/4"	8	ALUM	-	ALUM	-	ALUM	-	ENTRY	Yes	Yes	FUTURE TENANT DOOR, TO BE LOCATED
119	ENRTY	3'-0"	8'-0"	1 3/4"	8	ALUM	-	ALUM	-	ALUM	-	ENTRY	Yes	Yes	FUTURE TENANT DOOR, TO BE LOCATED
<b>2ND FLOOR</b>															
201	STAIR A	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
202	STAIR B	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
203	STAIR C	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
204	ELEC. ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	STOR.	Yes	Yes	
205	ELEC. ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	STOR.	Yes	Yes	
<b>3RD FLOOR</b>															
301	STAIR A	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
302	STAIR B	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
303	STAIR C	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
304	ELEC. ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	STOR.	Yes	Yes	
305	ELEC. ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	STOR.	Yes	Yes	
<b>4TH FLOOR</b>															
401	STAIR A	3'-6"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
402	STAIR B	3'-6"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
403	STAIR C	3'-6"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
404	ELEC. ROOM	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	45 MIN	STOR.	Yes	Yes	
405	ROOF TOP	6'-0"	7'-0"	1 3/4"	9	ALUM	-	ALUM	-	ALUM	-	ENTRY	Yes	Yes	
407	ROOF TOP	6'-0"	6'-11 13/16"	1 3/4"	9	ALUM	-	ALUM	-	ALUM	-	ENTRY	Yes	Yes	
408	STORAGE	6'-0"	7'-0"	1 3/4"	2	HM	PTD	HM	PTD	ALUM	-	STOR.	Yes	Yes	
409	MECH. PENTHOUSE	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	-	STOR.	Yes	Yes	
<b>ROOF - T.O.S.</b>															
501	STAIR B	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	90 MIN	PASS	Yes	Yes	
502	MECH. PENTHOUSE	3'-0"	7'-0"	1 3/4"	3	HM	PTD	HM	PTD	ALUM	-	STOR.	Yes	Yes	
503		3'-0"	7'-0"	1 3/4"	3										

**NOTES**

- ALL RATED DOORS TO HAVE CLOSERS, SMOKE SEALS, AND DOOR SWEEPS
- ALL EXTERIOR DOORS TO HAVE CLOSERS, WEATHERSTRIPPING, AND DOOR SWEEPS
- ALL DOORS ARE TO BE PAINT-GRADE, U.N.O.



Prepared For:  
**0 Hancock Street**  
 LLC  
 P.O. Box 7486  
 Portland, ME 04112

Consultant:



Architect:

Project:  
**0 Hancock Street**  
 1 Hancock Street  
 Portland, Maine

Revisions:  
 Issued For Permit - 10/23/2017

Date:  
 August 2017

Scale:  
 1/4" = 1'-0"

Door Schedule

**A8.01**