ROOM FINISH SCHEDULE - LEVEL THREE AND LEVEL FOUR

ROOM NUMBER	NAME	FLOOR MAT'L	FLOOR BASE	WALLS NORTH MAT'L	WALLS SOUTH MAT'L	WALLS EAST MAT'L	WALLS WEST MAT'L	CEILING MAT'L	CEILING HT	ROOM NUMBER	COMMENTS
301	STAIR	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	301	
302	COPY	CPT-1	RB-1	PTD	PTD	PTD	-	ACT-1	RE: RCP	302	
303	STORAGE	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	303	
304	ELEC	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	304	
305	OFFICE	CPT-2	RB-1	PTD	PTD	PTD/GL	PTD	ACT-2	RE: RCP	305	
306	OFFICE	CPT-2	RB-1	PTD	PTD	PTD	PTD/GL	ACT-2	RE: RCP	306	
307	OFFICE	CPT-2	RB-1	PTD	PTD	PTD	PTD/GL	ACT-2	RE: RCP	307	
308	OFFICE	CPT-2	RB-1	PTD	PTD	PTD	PTD/GL	ACT-2	RE: RCP	308	
309	OFFICE	CPT-2	RB-1	PTD	PTD	PTD/GL	PTD	ACT-2	RE: RCP	309	
310	OFFICE	CPT-2	RB-1	PTD	PTD	PTD/GL	PTD	ACT-2	RE: RCP	310	
312	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	312	
313	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	313	
314	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	314	
315	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	315	
316	MEETING	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD/GL	ACT-2	RE: RCP	316	
317	CORRIDOR	CPT-1+2	RB-1	PTD/GL	PTD/GL	PTD/GL	-	ACT-1	RE: RCP	317	
318	PARALEGAL	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	318	
319	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	319	
320	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	320	
321	KITCHEN	LVT-1	RB-1	PTD	PTD	PTD/CT-1	PTD	ACT-1/GWB	RE: RCP	321	
322	ELT OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	322	
323	CORRIDOR	CPT-2	RB-1+3	PTD	-	WD-1	PTD	ACT-1	RE: RCP	323	
325	COATS	CPT-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	325	
326	EXECUTIVE SUITE	CPT-1+2	RB-1+3	PTD	PTD	PTD/WD-1	PTD	ACT-1	RE: RCP	326	
327	CEO	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD/GL	ACT-2	RE: RCP	327	
328	MEETING	CPT-2	RB-1	WD-1	PTD/GL	PTD/GL	PTD	ACT-2/GWB	RE: RCP	328	
329	BREAK-OUT	CPT-1+2	RB-1	PTD/GL	PTD	PTD/GL	PTD	ACT-1	RE: RCP	329	
330	ELT VISIT OFFICE	CPT-2	RB-1	PTD	PTD	PTD	PTD/GL	ACT-2	RE: RCP	330	
331	FOCUS	CPT-2	RB-1	PTD/GL	AWP-3	PTD	PTD	ACT-2	RE: RCP	331	
332	FOCUS	CPT-2	RB-1	PTD/GL	AWP-3	PTD	PTD	ACT-2	RE: RCP	332	
333	COPY	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	333	
334	ELEV LOBBY	CPT-2	RB-1+3	-	-	PTD	WD-1	WD-2	RE: RCP	334	
335	STAIR A	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	335	
336	CORRIDOR	CPT-2	RB-1+3	PTD/GL	PTD/WD-1	-	PTD/GL	ACT-1	RE: RCP	336	*SEE WALL FINISH PLANS; ID111 SERIES
337	T / D	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	337	
338	TOILET	PFT-1-3	PTB-1	PTD	PTD	PTD	PTD	ACT-2	RE: RCP	338	
339	BREAK OUT	CPT-1	RB-1	PTD	-	PTD	PTD	ACT-1	RE: RCP	339	
340	CORRIDOR	CPT-2	RB-1	-	-	PTD	PTD	ACT-1/GWB	RE: RCP	340	
341	WELL	LVT-1	RB-1	PTD	PTD	PTD	PTD	ACT-2	RE: RCP	341	
342	WELL	LVT-1	RB-1	PTD	PTD	PTD	PTD	ACT-2	RE: RCP	342	
343	JANITOR	SC	RB-2	PTD/FRP	PTD/FRP	PTD/FRP	PTD/FRP	EXP-PTD	RE: RCP	343	FRP TO 4'-0" AFF
344	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	344	*PROVIDE STAINLESS COVE STRIP
345	ALCOVE	CPT-2	RB-1	PTD	PTD	-	GT-1	GWB	RE: RCP	345	
346	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	346	*PROVIDE STAINLESS COVE STRIP
347	OPEN OFFICE	CPT-1+2	RB-1	-	PTD	PTD	PTD	ACT-1	RE: RCP	347	
348	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	348	
349	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	349	
350	MEETING	CPT-2	RB-1	PTD	PTD/GL	PTD/GL	PTD	ACT-2	RE: RCP	350	
351	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD/GL	PTD	ACT-2	RE: RCP	351	
352	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	352	
353	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	353	
354	MEETING	CPT-1	RB-1	PTD	PTD	PTD/GL	PTD	ACT-2	RE: RCP	354	
355	MEETING	CPT-1	RB-1	PTD	PTD	PTD/GL	PTD	ACT-2	RE: RCP	355	
356	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	356	
357	STAIR	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	357	
358	CORRIDOR	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	358	
359	STORAGE	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	359	
360	MEETING	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD/GL	ACT-2	RE: RCP	360	
361	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	361	
362	CORRIDOR	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	362	
363	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD/GL	ACT-2	RE: RCP	363	
364	CFO	CPT-2	RB-1	PTD	PTD	PTD	PTD/GL	ACT-2	RE: RCP	364	
365	OPEN OFFICE	CPT-1+2	RB-1	-	PTD	PTD	PTD	ACT-1	RE: RCP	365	
366	KITCHEN / MEET	LVT-1	RB-1	PTD/CT-1	-	PTD	PTD/AWP-3	ACT-1/GWB	RE: RCP	366	
367	CORRIDOR	CPT-1	RB-1	-	-	PTD/GL	PTD	ACT-1/GWB	RE: RCP	367	
368	FOCUS	CPT-2	RB-1	PTD	PTD	AWP-3	PTD/GL	ACT-2	RE: RCP	368	
369	FOCUS	CPT-2	RB-1	PTD	PTD	AWP-3	PTD/GL	ACT-2	RE: RCP	369	
370	FOCUS	CPT-2	RB-1	PTD	PTD	AWP-3	PTD/GL	ACT-2	RE: RCP	370	
371	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	371	*PROVIDE STAINLESS COVE STRIP
372	ALCOVE	LVT-1	RB-1	PTD	PTD	-	GT-1	GWB	RE: RCP	372	
373	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	373	*PROVIDE STAINLESS COVE STRIP
374	STORAGE	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	374	
375	ELEC.	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	375	
376	BREAK OUT	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	376	
377	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD/GL	PTD	ACT-1	RE: RCP	377	
378	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	378	
379	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	379	
380	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	380	
381	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	381	
382	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	382	
383	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	383	
384	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD/GL	PTD	ACT-2	RE: RCP	384	
385	ELT OFFICE	CPT-2	RB-1	PTD	PTD	PTD/GL	PTD	ACT-2	RE: RCP	385	
386	OPEN OFFICE	CPT-1+2	RB-1	-	PTD	PTD	PTD/GL	ACT-1	RE: RCP	386	
387	OPEN OFFICE	CPT-1+2	RB-1	-	PTD	PTD	PTD	ACT-1	RE: RCP	387	
388	BREAK OUT	CPT-1+2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-1	RE: RCP	388	
389	MEETING	CPT-1	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	389	
390	WORK ROOM	CPT-1	RB-1	PTD	PTD	PTD	PTD/GL	ACT-2	RE: RCP	390	
401	STAIR	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	401	
402	COPY	CPT-1	RB-1	PTD	PTD	PTD/AWP-3	-	ACT-1	RE: RCP	402	
403	T / D	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	403	
404	ELEC.	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	404	
405	ELT OFFICE	CPT-1	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	405	
406	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	406	
407	COFFEE ALCOVE	LVT-1	RB-1	PTD	PTD	PTD/CT-1	PTD	ACT-1/GWB	RE: RCP	407	
408	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	408	
409	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	409	
410	CORRIDOR	CPT-2	RB-1	-	PTD	PTD/GL	PTD/GL	ACT-1	RE: RCP	410	
411	OFFICE	CPT-2	RB-1	PTD	PTD	PTD	PTD/GL	ACT-2	RE: RCP	411	
412	STOR.	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	412	
413	CORRIDOR	EST-1	RB-1	PTD	PTD/WD-1	PTD	GT-1	WD-2	RE: RCP	413	
414	TOILET	PFT-1-3	PTB-1	PTD	PTD	PTD	PTD	ACT-2	RE: RCP	414	*PROVIDE STAINLESS COVE STRIP
415	JAN	SC	RB-2	PTD/FRP	PTD/FRP	PTD/FRP	PTD/FRP	EXP-PTD	-	415	FRP TO 4'-0" AFF
416	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	416	*PROVIDE STAINLESS COVE STRIP
417	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	417	*PROVIDE STAINLESS COVE STRIP
418	STAIR A	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	418	
419	ELEV LOBBY	EST-1	RB-1+3	-	-	PTD	WD-1	WD-2	RE: RCP	419	
420	WAITING	EST-1	RB-1	PTD	PTD/GL	PTD	PTD	RE: RCP	RE: RCP	420	
421	COFFEE ALCOVE	LVT-1	RB-1	PTD	PTD	PTD/CT-1	PTD	ACT-1/GWB	RE: RCP	421	
422	PRODUCT SHOWCASE	CPT-1	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	422	
423	BOARD ROOM	CPT-2	RB-1	PTD/GL	PTD	PTD	WD-1	ACT-1	RE: RCP	423	

FINISHES LEGEND:

ACOUSTIC CEILING TILE

ACT-1: ROCKFON, ALASKA SQUARE TEGULAR NARROW 9/16-INCH (10203), 24x72-INCH CEILING TILE, COLOR: WHITE. REFER TO SPECIFICATIONS FOR INFORMATION REGARDING SUSPENSION SYSTEM AND TRIM.

ACT-2: ARMSTRONG COMMERCIAL CEILINGS, ULTIMA BEVELED TEGULAR 9/16-INCH (1942), 24x24-INCH CEILING TILE, COLOR: WHITE. REFER TO SPECIFICATIONS FOR INFORMATION REGARDING SUSPENSION SYSTEM AND TRIM.

ACT-3: ARMSTRONG COMMERCIAL CEILINGS, CANYON BEVELED TEGULAR 15/16-INCH (1492), 24x24-INCH CEILING TILE, COLOR: WHITE. COMPATIBLE SUSPENSION GRID SYSTEM WITH PERIMETER TRIM, MOULDINGS AND ACCESSORIES REQUIRED FOR A COMPLETE INSTALLATION.

ACT-4: ARMSTRONG COMMERCIAL CEILINGS, METALWORKS MESH, EXPANDED METAL TEGULAR IN LATTICE PATTERN; 15/16-INCH GRID, 24x24-INCH MESH PANELS WITH BLACK ACOUSTIC INFILL BACKING; GRID AND MESH COLOR: WHITE. COMPATIBLE SUSPENSION GRID SYSTEM WITH PERIMETER TRIM, MOULDINGS AND ACCESSORIES REQUIRED FOR A COMPLETE INSTALLATION.

ACRYLIC PANELS

AP-1: (LOGO SIGNAGE) 3FORM, CHROMA, 1/2-INCH GAUGE, RENEWABLE MATTE FINISH ON FACE, VELLUM FINISH ON BACK, COLOR: CLEAR WITH AVALANCHE D01, SAMPLE REFERENCE SO-446409.1.

AP-2: (BACKLIT PANELS) 3FORM, CHROMA, 1/2-INCH GAUGE, RENEWABLE MATTE FINISH ON FACE, VELLUM FINISH ON BACK, COLOR: CLEAR WITH POWDER D03.

ACOUSTIC WALL PANELS:

AWP-1: MDC, ZINTRA, LOUVERS - STANDARD SQUARE, 48x108-INCHES; BLACK POWDERCOAT FRAME, LOUVER COLOR: TBD.

AWP-2: DL COUCH, NUFELT, 63-INCH ROLL WIDTH, 0.12-INCH THICKNESS, COLOR: TBD.

AWP-3: DL COUCH, NUFELT, 63-INCH ROLL WIDTH, 0.12-INCH THICKNESS WITH CORK SUBSTRATE, COLOR: TBD.

CERAMIC TILE

CT-1: CROSSVILLE TILE, SYMPATICO, BOTANIC LT02, 12x24-INCH TILE, GLOSS FINISH.

CT-2: (FIELD) CREATIVE MATERIALS CORPORATION, MULTIDIMENSIONAL TILE, 16x32-INCH TILE, WHITE IN MATTE FINISH.

CT-3: (ACCENT) CREATIVE MATERIALS CORPORATION, MULTIDIMENSIONAL TILE, 16x32-INCH TILE, WHITE HEXAGON IN MATTE FINISH.

CARPET TILE

CPT-1: BENTLEY MILLS, TRESPASS (8TE20), 18x36-INCH TILE, AFIRMA HARDBACK, BRICK INSTALLATION, COLOR: MURPHY RANCH (806304).

CPT-2: BENTLEY MILLS, REPOSE (8RJ26), 18x36-INCH TILE, AFIRMA HARDBACK, COLOR: AWAKENING (800220).

ENGINEERED STONE TILE
****FLOOR PREP TO INCLUDE FULL SPREAD LEVELER****

EST-1: STONE SOURCE, TREND Q, 6.6MM THICKNESS, 24x48-INCH TILE, HONED SURFACE FINISH, COLOR: PIETRA SERENA.

EST-2: STONE SOURCE, TREND Q, 6.6MM THICKNESS, 24x48-INCH TILE, POLISHED FINISH, COLOR: 460.

FIBER-REINFORCED PLASTIC

FRP-1: MARLITE, STANDARD FRP, PEBBLED SURFACE, PROVIDE CORNER AND EDGE TRIM, COLOR: WHITE P100.

LUXURY VINYL TILE

LVT-1: PATCRAFT, MIXED MATERIALS CONVERGE, WOOD PLANX (1336V), 9x36-INCH TILE, 40 MIL WEAR LAYER, COLOR: TBD.

MARMOLEUM COMPOSITION TILE

MCT-1: FORBO, MARMOLEUM COMPOSITION TILE, 13x13-INCH TILE, COLOR: TBD.

PAINT

PTD-1: CEILINGS & SOFFITS, TYPICAL; TBD
PTD-2: WALLS, TYPICAL; TBD
PTD-3: ACCENT - TBD
PTD-4: ACCENT - TBD
PTD-5: ACCENT - TBD
PTD-6: ACCENT - PMS 186
PTD-7: DRY ERASE PAINT; CLEAR TOP COAT OVER FINISH COATS; REQUIRES LEVEL 5 GWB
PTD-8: CHALKBOARD PAINT

PLASTIC LAMINATE

PLAM-1: (CASEWORK VERTICAL SURFACES, TYPICAL) TBD.
PLAM-2: (BACK OF HOUSE SHELVING) TBD.

PORCELAIN FLOOR TILE

PFT-1: CREATIVE MATERIALS CORPORATION, ROUNDABOUT, 8x8-INCH HEXAGON, COLOR : WHITE.
PFT-2: CREATIVE MATERIALS CORPORATION, ROUNDABOUT, 8x8-INCH HEXAGON, COLOR : LIGHT GREY.
PFT-3: CREATIVE MATERIALS CORPORATION, ROUNDABOUT, 8x8-INCH HEXAGON, COLOR : GREY.

PORCELAIN TILE BASE

PTB-1: CREATIVE MATERIALS CORPORATION, ROUNDABOUT, 3x24-INCH BULL NOSE TILE, COLOR: LIGHT GREY.

RESILIENT WALL BASE

RB-1: JOHNSONITE, MILLWORK PROFILE, EQUINOX, 4.5-INCHES HIGH, COLOR: TBD.
RB-2: JOHNSONITE, COVED TOE WALL BASE, 4-INCHES HIGH, COLOR: TBD.
RB-3: JOHNSONITE, MILLWORK PROFILE, MANDALAY, 3-INCHES HIGH, COLOR: BLACK #40.
RB-4: JOHNSONITE, MILLWORK PROFILE, EQUINOX, 4.5-INCHES HIGH, COLOR: TBD - ACCENT.
RB-5: JOHNSONITE, MILLWORK PROFILE, EQUINOX, 4.5-INCHES HIGH, COLOR: TBD - ACCENT.

RESILIENT STAIR ASSEMBLY

RSA-1: JOHNSONITE, RUBBER STAIR TREADS WITH INTEGRATED RISER AND VISUALLY IMPAIRED COLOR INSERT STRIP; COLOR: SMOKEY PEARL HAMMERED (WGD) WITH SMOOTH INSERT STRIP IN BIG TOP (294). 24x24-INCH METALLURGY TILE AT LANDINGS, COLOR: SMOKEY PEARL HAMMERED (WGD).

SEALED CONCRETE

SC: SHERWIN WILLIAMS/GENERAL POLYMERS, EPOXY WATER EMULSION PRIMER/SEALER (GP 3477); CLEAR.

SOLID SURFACE MATERIAL

SSM-1: (BREAK ROOM COUNTERTOPS) HANSTONE QUARTZ, COLOR TBD.
SSM-2: (RESTROOM COUNTERTOPS) WILSONART QUARTZ, COLOR TBD.
SSM-3: (COUNTERTOPS, TYPICAL) CORIAN, PRICE GROUP D

WALK-OFF MAT

WOM-1: BENTLEY MILLS, ROUGH IDEA (8RU260220T), 24x24-INCH TILE, COLOR: DRAFT (800655).
WOM-2: MATS INC., DUAL TRACK RECESSED FOOT GRILLE SYSTEM

WOOD

WD-1: DEADHEAD LUMBER, RESAWN TIMBER CO., CUSTOM STAINED WHITE OAK, TONGUE AND GROOVE PLANKS WITH MITRED CORNERS.
WD-2: DEADHEAD LUMBER, RESAWN TIMBER CO., CUSTOM STAINED WHITE OAK MOUNTED TO CEILING HUNG SUSPENSION SYSTEM.
WD-3: WOOD CASEWORK;

ROOM FINISH NOTES:

1. SEE GI001 FOR PROJECT GENERAL NOTES.
2. SEE GI002 FOR PARTITION LEGEND AND TYPE OF GWB COMPOSITION REQUIRED.
3. REFER TO FLOOR FINISH PLANS (ID101 - ID107) FOR ADDITIONAL INFORMATION REGARDING LOCATIONS OF FINISH MATERIALS, AND FLOOR FINISH PATTERNS.
4. REFER TO WALL FINISH PLANS (ID111 - ID117) FOR ADDITIONAL INFORMATION REGARDING TYPES AND LOCATIONS OF WALL APPLIED MATERIALS AND FINISHES.
5. REFER TO RCPS FOR ADDITIONAL INFORMATION REGARDING CEILING HEIGHTS AND TYPES.
6. ALL EXPOSED STRUCTURE, DUCTWORK AND SPRINKLER PIPING TO BE PAINTED, UNLESS NOTED OTHERWISE.

FINISH MATERIAL ABBREVIATIONS:

ACT	ACOUSTIC CEILING TILE
AP	ACRYLIC PANELS
AWP	ACOUSTIC WALL PANELS
CPT	CARPET
CT	CERAMIC TILE
EST	ENGINEERED STONE TILE
EXP	EXPOSED TO STRUCTURE
FRP	FIBER-REINFORCED PLASTIC
GL	GLASS
GT	GLASS TILE
GWB	GYPSUM WALL BOARD
LVT	LUXURY VINYL TILE
MCT	MARMOLEUM COMPOSITION TILE
MTL	METAL
PFT	PORCELAIN FLOOR TILE
PLAM	PLASTIC LAMINATE
PTB	PORCELAIN TILE BASE
PTD	PAINT(ED)
RB	RESILIENT BASE
RCP	REFLECTED CEILING PLAN
RSA	RESILIENT STAIR ASSEMBLY
SC	SEALED CONCRETE
SF	STOREFRONT
SSM	SOLID SURFACE MATERIAL
WD	WOOD
WOM	WALK-OFF MAT

Date: 06/15/18

REV.	DESCRIPTION	DATE
1	ADDENDUM NO. 1	12-11-17

ADDENDUM NO. 1
12-11-17

CURRENT ISSUE STATUS:

PROJECT NORTH:

SMRT Architects and Engineers
144 Fore Street/P.O. Box 618
Portland, Maine 04104
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY

WEX
CORPORATE HEADQUARTERS

PORTLAND, ME

LEVEL THREE & LEVEL FOUR
ROOM FINISH SCHEDULES

SHEET TITLE:

0" 1/4" 1/2" 1" 2" 3"

SCALE: AS NOTED

PROJECT MANAGER:	GWV	PROJECT NO:	17120-01
A/E OF RECORD:	GWV		
JOB CAPTAIN:	CBM		
DRAWN BY:	CBM		
SMRT FILE:	AE602-17120-01	SHEET No.	AE602

© COPYRIGHT 2017 SMRT INC.

NOT FOR CONSTRUCTION

30x42