AREA A - LEVEL FOUR REFLECTED CEILING PLAN (B2)
1/8" = 1'-0"

CEILING LEGEND:

- 2x2 CEILING TILE AND GRID
- 2x6 CEILING TILE AND GRID
- GWB CEILING
- WOOD SLAT CEILING (WD-2)
- WOOD PANEL (WD-3)
- DOWN LIGHT
- 2x2 LIGHT FIXTURE
- 1x4 LIGHT FIXTURE
- SUPPLY DIFFUSER
- RETURN DIFFUSER
- EXHAUST DIFFUSER
- LINEAR DIFFUSER
- LINEAR PENDANT - DIRECT/INDIRECT
- LINEAR RECESSED
- DECORATIVE PENDANT
- DECORATIVE PENDANT
- DECORATIVE PENDANT
- NOT IN SCOPE

CEILING NOTES:

1. SEE GI001 FOR GENERAL PROJECT NOTES.
2. SEE FINISH SCHEDULE FOR CEILING AND CEILING GRID TYPES.
3. EXCEPT WHERE INDICATED, CENTER CEILING GRIDS IN ROOMS. USE HALF TILES OF GREATER @ PERIMETERS WHEN POSSIBLE.
4. ALIGN CEILING ITEMS AS SHOWN, WITH COMMON CENTERLINES TYPICALLY. CENTER ITEMS IN CEILING, OR IN AREAS UNLESS INDICATED OTHERWISE.
5. WHERE TEGULAR OR BEVELED TILE IS USED, PAINT ALL CUT EDGES TO MATCH.
6. CAULK JOINT BETWEEN CEILING GRID (WALL ANGLE) AND WALL WHERE GAPS ARE LARGER THAN 1/8" OR GREATER.
7. PROVIDE ACCESS PANELS AS REQUIRED IN GWB CEILINGS FOR ACCESS AS REQUIRED BY ALL TRADES.
8. FIRE SPRINKLERS SHALL BE CENTERED IN CEILING TILE OR HALF TILE AS SHOWN. FIRE SPRINKLERS SHALL BE LOCATED IN ALIGNMENT WITH OTHER CEILING ITEMS AND SHALL BE PLACED IN COORDINATION WITH LIGHT FIXTURE POSITIONS INDICATED, TYPICAL.
9. FIRE SPRINKLERS ARE SHOWN FOR COORDINATION PURPOSES ONLY. ADDITIONAL SPRINKLER HEADS MAY BE REQUIRED FOR CODE COMPLIANCE, AS DETERMINED BY THE FIRE PROTECTION DESIGNER. SPRINKLERS ARE NOT SHOWN IN ALL AREAS WHERE REQUIRED. FIRE PROTECTION CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A COMPLETE AND FULLY CODE COMPLIANTE SYSTEM, INCLUDING HEADS NOT INDICATED IN THIS DRAWING. SIDEWALL MOUNT SPRINKLER HEADS UNDER BALCONIES ARE NOT SHOWN IN THE CEILING PLANS.
10. MECHANICAL AND ELECTRICAL SCOPE SHOWN FOR REFERENCE AND COORDINATION ONLY. REFER TO MECHANICAL DOCCUMENTS.
11. WHERE ARCHITECTURAL DRAWINGS DEPICT MECHANICAL OR ELECTRICAL ITEMS OR EQUIPMENT (LIGHTS, DIFFUSERS, ETC.) INSTALLATION OF SUCH ITEMS SHALL BE COORDINATED WITH EACH RESPECTIVE TRADE SUB-CONTRACTOR.
12. WHERE DRAWINGS DO NOT ACCESS INSTALLATION METHODOLOGY, THE CONTRACTOR SHALL BE BOUND TO PERFORM IN STRICT COMPLIANCE WITH THE MANUFACTURER'S SPECIFICATIONS, AND STANDARD INDUSTRY STANDARDS
13. ALL ACT CEILINGS TO BE OFFSET FROM INSIDE FACE OF EXTERIOR MULLIONS BY 3'-8" UNLESS OTHERWISE NOTED.
14. CEILING DIMENSIONS ARE TO FINISH FACE OF WALL.
15. PROVIDE 4-INCH METAL PERIMETER TRIM AT ALL EXPOSED EDGES OF ACT EXCEPT AS INDICATED BY CEILING HEIGHT TRANSITION DETAILS A15 ON AE509.
16. ALL EXPOSED STRUCTURE AND SPRINKLER PIPING TO BE PAINTED [PTD-9]; TO INCLUDE AREAS VISIBLE ABOVE WOOD SLAT [WD-2] CEILINGS.

Date: 06/15/18

REV	DESCRIPTION	DATE
2	SI - 4	05/31/18
1	SI - 1	05/09/18
0	ISSUED FOR CONSTRUCTION	04/16/18

SI - 4
05/31/18
CURRENT ISSUE STATUS:

PROJECT NORTH:

SMRT Architects and Engineers
144 Fore Street/P.O. Box 618
Portland, Maine 04104
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY
SMRT

WEX
CORPORATE HEADQUARTERS

PORTLAND, ME

AREA A - LEVEL FOUR
REFLECTED CEILING PLAN

SHEET TITLE:

0" 1/4" 1/2" 1" 2" 3"

SCALE: AS NOTED

PROJECT MANAGER:	GWV	PROJECT NO:	17120-01
A/E OF RECORD:	GWV		
JOB CAPTAIN:	CBM		
DRAWN BY:	CBM		
SMRT FILE:	AE127-17120-01	SHEET No.	AE127

COPYRIGHT 2017 SMRT INC

30x42