ROOM FINISH SCHEDULE - LEVEL ONE AND LEVEL TWO

ROOM NUMBER	NAME	FLOOR MAT'L	FLOOR BASE	WALLS NORTH MAT'L	WALLS SOUTH MAT'L	WALLS EAST MAT'L	WALLS WEST MAT'L	CEILING MAT'L	CEILING HT	ROOM NUMBER	COMMENTS
101	STAIR	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	101	
102	STOR	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	102	
103	ELEC	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	103	
104	CORY	CPT-1	RB-1	PTD	PTD	PTD/AWP-3	PTD	ACT-1	RE: RCP	104	
105	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	105	
106	OFFICE / MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	106	
107	OFFICE / MEETING	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	107	
108	ELT OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	108	
110	HR OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	110	
111	EMP. ENTRANCE	WOM-1+2	RB-1	SF	PTD/GL	PTD/GL	PTD	WD-2	RE: RCP	111	
112	COFFEE LOUNGE	EST-1/WOM-1	RB-1	PTD/GL	VARIES*	PTD/GL	PTD/GL	ACT-1/GWB/WD-1	RE: RCP	112	*SEE WALL FINISH PLANS; ID111 SERIES
113	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD/GL	PTD	ACT-2/GWB	RE: RCP	113	
114	VESTIBULE	WOM-1+2	RB-1	PTD	PTD/GL	SCREEN*	SF	WD-2	RE: RCP	114	*RE: A/V
115	LOBBY	EST-1/WOM-1	RB-1+3	VARIES*	VARIES*	VARIES*	VARIES*	RE: RCP	RE: RCP	115	*SEE WALL FINISH PLANS; ID111 SERIES
117	COAT / LUGGAGE	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	117	
118	ELEV LOBBY	EST-1	RB-3	-	-	EST-2	WD-1	WD-2	RE: RCP	118	
119	STAIR A	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	119	
120	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD/GL	PTD	ACT-1	RE: RCP	120	
121	CORRIDOR	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	121	
122	CORRIDOR	EST-1	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	122	
123	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	123	*PROVIDE STAINLESS COVE STRIP
124	ALCOVE	EST-1	RB-1	PTD	PTD	-	GT-1	GWB	RE: RCP	124	
125	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	125	*PROVIDE STAINLESS COVE STRIP
126	T / D	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	126	
127	JAN	SC	RB-2	PTD/FRP	PTD/FRP	PTD/FRP	PTD/FRP	EXP-PTD	RE: RCP	127	FRP TO 4'-0" AFF
128	TOILET	PFT-1-3	PTB-1	PTD	PTD	PTD	PTD	ACT-2	RE: RCP	128	*PROVIDE STAINLESS COVE STRIP
129	BIKE STORAGE	SC	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	129	
130	SHOWER ALCOVE	EST-1	RB-1	PTD	PTD	PTD	PTD	ACT-2	RE: RCP	130	
131	SHOWER	PFT-1-3	CT*	CT-2	CT-2	CT-2+3	CT-2	GWB	RE: RCP	131	
132	SHOWER	PFT-1-3	CT*	CT-2	CT-2	CT-2+3	CT-2	GWB	RE: RCP	132	
133	SHOWER	PFT-1-3	CT*	CT-2	CT-2	CT-2+3	CT-2	GWB	RE: RCP	133	
134	SHOWER	PFT-1-3	CT*	CT-2	CT-2	CT-2+3	CT-2	GWB	RE: RCP	134	
135	SHOWER	PFT-1-3	CT*	CT-2	CT-2	CT-2+3	CT-2	GWB	RE: RCP	135	
136	SHOWER	PFT-1-3	CT*	CT-2	CT-2	CT-2+3	CT-2	GWB	RE: RCP	136	
137	SHOWER	PFT-1-3	CT*	CT-2	CT-2	CT-2+3	CT-2	GWB	RE: RCP	137	
138	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	138	
139	CORRIDOR	CPT-2	RB-1	-	-	PTD/GL	PTD	ACT-1	RE: RCP	139	
140	MEETING	CPT-2	RB-1	PTD/GL	PTD/GL	PTD	PTD/GL	ACT-2	RE: RCP	140	
141	MEETING	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	141	
142	FOCUS	CPT-2	RB-1	PTD	PTD	PTD/GL	AWP-3	ACT-2	RE: RCP	142	
143	FOCUS	CPT-2	RB-1	PTD	PTD	PTD/GL	AWP-3	ACT-2	RE: RCP	143	
144	FOCUS	CPT-2	RB-1	PTD	PTD	PTD/GL	AWP-3	ACT-2	RE: RCP	144	
145	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	145	
146	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	146	
147	STOR.	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	147	
148	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD/GL	ACT-1	RE: RCP	148	
149	COFFEE	LVT-1	RB-1	PTD/CT-1	-	PTD	PTD	GWB	RE: RCP	149	
150	COPY / CORRIDOR	LVT-1	RB-1	PTD	PTD	PTD/AWP-3	PTD/GT-1	ACT-1/GWB	RE: RCP	150	
151	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	151	*PROVIDE STAINLESS COVE STRIP
152	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	152	*PROVIDE STAINLESS COVE STRIP
153	LOADING DOCK	SC	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	-	153	EPOXY PAINT ALL WALLS
154	STORAGE	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	-	154	
155	ELEC	SC	-	PTD	PTD	PTD	PTD	EXP-PTD	-	155	
156	MECH	SC	-	PTD	PTD	PTD	PTD	EXP-PTD	-	156	
157	MAIL ROOM	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	157	
201	STAIR	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	201	
202	COPY	CPT-1	RB-1	PTD	PTD	PTD/AWP-3	-	ACT-1	RE: RCP	202	
203	STORAGE	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	203	
204	ELEC	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	204	
205	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	205	
206	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	206	
207	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	207	
208	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	208	
209	MEETING	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	209	
210	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	210	
211	BREAK OUT	CPT-1+2	RB-3	AWP-1	WD-1	-	AWP-1	ACT-1	RE: RCP	211	
212	MEETING	CPT-1	RB-1	PTD	PTD/GL	PTD	PTD/GL	ACT-2	RE: RCP	212	
213	CORRIDOR	CPT-1+2	RB-1	PTD	PTD	PTD	-	ACT-1	RE: RCP	213	
215	STAIR	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	215	
216	ELEV LOBBY	EST-1	RB-1+3	-	-	PTD	WD-1	WD-2	RE: RCP	216	
217	TOILET	PFT-1-3	PTB-1	PTD	PTD	PTD	PTD	ACT-2	RE: RCP	217	
218	RECYCLE	EST-1	RB-1	PTD	-	PTD	PTD	GWB	RE: RCP	218	
219	STORAGE	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	219	
220	BREAK ROOM	EST-1	RB-1	PTD/CT-1/WD-1	PTD	PTD/WD-1/GL	PTD	ACT-1/GWB	RE: RCP	220	
222	PHONE	CPT-2	RB-1	PTD	PTD	AWP-3	PTD	GWB/AWP-2	RE: RCP	222	
223	BREAK OUT	CPT-2	RB-1	AWP-2	PTD	PTD/AWP-2	-	ACT-1/GWB/AWP-2	RE: RCP	223	
224	CORRIDOR	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	224	
225	CORRIDOR	CPT-1+2	RB-1	-	-	PTD	PTD	ACT-1/GWB	RE: RCP	225	
226	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	226	*PROVIDE STAINLESS COVE STRIP
227	ALCOVE	CPT-2	RB-1	PTD	PTD	-	GT-1	GWB	RE: RCP	227	
228	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	228	*PROVIDE STAINLESS COVE STRIP
229	JANITOR	SC	RB-2	PTD/FRP	PTD/FRP	PTD/FRP	PTD/FRP	EXP-PTD	RE: RCP	229	FRP TO 4'-0" AFF
230	T / D	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	230	*PROVIDE STAINLESS COVE STRIP
231	BREAK OUT	CPT-1+2	RB-1	PTD	-	PTD	PTD	ACT-1	RE: RCP	231	
232	WELL	LVT-1	RB-1	PTD	PTD	PTD	PTD	ACT-2	RE: RCP	232	
233	WELL	LVT-1	RB-1	PTD	PTD	PTD	PTD	ACT-2	RE: RCP	233	
234	MEETING	CPT-1	RB-1	PTD	PTD	PTD/GL	PTD	ACT-2	RE: RCP	234	
235	MEETING	CPT-1	RB-1	PTD	PTD	PTD/GL	PTD	ACT-2	RE: RCP	235	
236	CORRIDOR	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	236	
237	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	237	
238	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	238	
239	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	239	
240	FOCUS	CPT-2	RB-2	PTD	PTD	PTD/GL	AWP-3	ACT-2	RE: RCP	240	
241	FOCUS	CPT-2	RB-2	PTD	PTD	PTD/GL	AWP-3	ACT-2	RE: RCP	241	
242	FOCUS	CPT-2	RB-2	PTD	PTD	PTD/GL	AWP-3	ACT-2	RE: RCP	242	
243	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	243	
244	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	244	
245	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	245	
246	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	246	
247	MEETING	CPT-1	RB-1	PTD/GL	PTD	PTD/GL	PTD/GL	ACT-2	RE: RCP	247	
248	MEETING	CPT-1	RB-1	PTD	PTD	PTD/GL	PTD/GL	ACT-2	RE: RCP	248	
249	OPEN OFFICE	CPT-1+2	RB-1	-	PTD	PTD	PTD	ACT-1	RE: RCP	249	
250	OPEN OFFICE	CPT-1+2	RB-1	-	PTD	PTD	PTD	ACT-1	RE: RCP	250	
251	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	251	
252	STAIR	RSA-1	RB-1	PTD	PTD	PTD	PTD	GWB	RE: RCP	252	
253	STORAGE	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	253	
254	COPY	CPT-2	RB-1	PTD	PTD	PTD	-	GWB	RE: RCP	254	
255	MEETING	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD/GL	ACT-2	RE: RCP	255	
256	KITCHEN / MEETING	LVT-1	RB-1	PTD/CT-1	-	PTD	PTD/AWP-3	ACT-1/GWB	RE: RCP	256	
257	MEETING	CPT-1	RB-1	PTD/GL	PTD	PTD/GL	PTD/GL	ACT-2	RE: RCP	257	
258	MEETING	CPT-1	RB-1	PTD	PTD	PTD/GL	PTD/GL	ACT-2	RE: RCP	258	
259	OPEN OFFICE	CPT-1+2	RB-1	-	PTD	PTD	PTD	ACT-1	RE: RCP	259	
260	CORRIDOR	LVT-1/CPT-2	RB-1	-	-	PTD	PTD	ACT-1/GWB	RE: RCP	260	
261	FOCUS	CPT-2	RB-1	PTD	PTD	AWP-3	PTD/GL	ACT-2	RE: RCP	261	
262	FOCUS	CPT-2	RB-1	PTD	PTD	AWP-3	PTD/GL	ACT-2	RE: RCP	262	
263	FOCUS	CPT-2	RB-1	PTD	PTD	AWP-3	PTD/GL	ACT-2	RE: RCP	263	
264	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	264	*PROVIDE STAINLESS COVE STRIP
265	ALCOVE	LVT-1	RB-1	PTD	PTD	-	GT-1	GWB	RE: RCP	265	
266	TOILET	PFT-1-3	PTB-1/CT*	CT-2+3	CT-2+3	CT-2+3	CT-2+3	ACT-2/GWB	RE: RCP	266	*PROVIDE STAINLESS COVE STRIP
267	STORAGE	MCT-1	RB-2	PTD	PTD	PTD	PTD	ACT-3	RE: RCP	267	
268	BREAK OUT	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	268	
269	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	269	
270	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	270	
271	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	271	
272	OFFICE	CPT-2	RB-1	PTD/GL	PTD	PTD	PTD	ACT-2	RE: RCP	272	
273	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	273	
274	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	274	
275	OFFICE	CPT-2	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	275	
276	OPEN OFFICE	CPT-1+2	RB-1	PTD	PTD	PTD	PTD	ACT-1	RE: RCP	276	
277	MEETING	CPT-1	RB-1	PTD	PTD	PTD	PTD/GL	ACT-2	RE: RCP	277	
278	MEETING	CPT-1	RB-1	PTD	PTD/GL	PTD	PTD	ACT-2	RE: RCP	278	
279	ELEC.	MCT-1	RB-2	PTD	PTD	PTD	PTD	EXP-PTD	RE: RCP	279	

FINISHES LEGEND:

ACOUSTIC CEILING TILE

ACT-1: ROCKFON, ALASKA SQUARE TEGULAR NARROW 9/16-INCH (10203), 24x72-INCH CEILING TILE, COLOR: WHITE. REFER TO SPECIFICATIONS FOR INFORMATION REGARDING SUSPENSION SYSTEM AND TRIM.

ACT-2: ARMSTRONG COMMERCIAL CEILINGS, ULTIMA BEVELED TEGULAR 9/16-INCH (1942), 24x24-INCH CEILING TILE, COLOR: WHITE. REFER TO SPECIFICATIONS FOR INFORMATION REGARDING SUSPENSION SYSTEM AND TRIM.

ACT-3: ARMSTRONG COMMERCIAL CEILINGS, CANYON BEVELED TEGULAR 15/16-INCH (1492), 24x24-INCH CEILING TILE. COLOR: WHITE. COMPATIBLE SUSPENSION GRID SYSTEM WITH PERIMETER TRIM, MOULDINGS AND ACCESSORIES REQUIRED FOR A COMPLETE INSTALLATION.

ACT-4: ARMSTRONG COMMERCIAL CEILINGS, METALWORKS MESH, EXPANDED METAL TEGULAR IN LATTICE PATTERN; 15/16-INCH GRID, 24x24-INCH MESH PANELS WITH BLACK ACOUSTIC INFILL BACKING; GRID AND MESH COLOR: WHITE. COMPATIBLE SUSPENSION GRID SYSTEM WITH PERIMETER TRIM, MOULDINGS AND ACCESSORIES REQUIRED FOR A COMPLETE INSTALLATION.

ACRYLIC PANELS

AP-1: (LOGO SIGNAGE) 3FORM, CHROMA, 1/2-INCH GAUGE, RENEWABLE MATTE FINISH ON FACE, VELLUM FINISH ON BACK, COLOR: CLEAR WITH AVALANCHE D01, SAMPLE REFERENCE SO-446409.1.

AP-2: (BACKLIT PANELS) 3FORM, CHROMA, 1/2-INCH GAUGE, RENEWABLE MATTE FINISH ON FACE, VELLUM FINISH ON BACK, COLOR: CLEAR WITH POWDER D03.

ACOUSTIC WALL PANELS:

AWP-1: MDC, ZINTRA, LOUVERS - STANDARD SQUARE, 48x108-INCHES; BLACK POWDERCOAT FRAME, LOUVER COLOR: TBD.

AWP-2: DL COUCH, NUFELT, 63-INCH ROLL WIDTH, 0.12-INCH THICKNESS, COLOR: TBD.

AWP-3: DL COUCH, NUFELT, 63-INCH ROLL WIDTH, 0.12-INCH THICKNESS WITH CORK SUBSTRATE, COLOR: TBD.

CERAMIC TILE

CT-1: CROSSVILLE TILE, SYMPATICO, BOTANIC LT02, 12x24-INCH TILE, GLOSS FINISH.

CT-2: (FIELD) CREATIVE MATERIALS CORPORATION, MULTIDIMENSIONAL TILE, 16x32-INCH TILE, WHITE IN MATTE FINISH.

CT-3: (ACCENT) CREATIVE MATERIALS CORPORATION, MULTIDIMENSIONAL TILE, 16x32-INCH TILE, WHITE HEXAGON IN MATTE FINISH.

CARPET TILE

CPT-1: BENTLEY MILLS, TRESPASS (8TE20), 18x36-INCH TILE, AFIRMA HARDBACK, BRICK INSTALLATION, COLOR: MURPHY RANCH (806304).

CPT-2: BENTLEY MILLS, REPOSE (8RJ26), 18x36-INCH TILE, AFIRMA HARDBACK, COLOR: AWAKENING (800220).

ENGINEERED STONE TILE
****FLOOR PREP TO INCLUDE FULL SPREAD LEVELER****

EST-1: STONE SOURCE, TREND Q, 6.6MM THICKNESS, 24x48-INCH TILE, HONED SURFACE FINISH, COLOR: PIETRA SERENA.

EST-2: STONE SOURCE, TREND Q, 6.6MM THICKNESS, 24x48-INCH TILE, POLISHED FINISH, COLOR: 460.

FIBER-REINFORCED PLASTIC

FRP-1: MARLITE, STANDARD FRP, PEBBLED SURFACE, PROVIDE CORNER AND EDGE TRIM, COLOR: WHITE P100.

LUXURY VINYL TILE

LVT-1: PATCRAFT, MIXED MATERIALS CONVERGE, WOOD PLANX (1336V), 9x36-INCH TILE, 40 MIL WEAR LAYER, COLOR: TBD.

MARMOLEUM COMPOSITION TILE

MCT-1: FORBO, MARMOLEUM COMPOSITION TILE, 13x13-INCH TILE, COLOR: TBD.

PAINT

PTD-1: CEILINGS & SOFFITS, TYPICAL; TBD
PTD-2: WALLS, TYPICAL; TBD
PTD-3: ACCENT - TBD
PTD-4: ACCENT - TBD
PTD-5: ACCENT - TBD
PTD-6: ACCENT - PMS 186
PTD-7: DRY ERASE PAINT; CLEAR TOP COAT OVER FINISH COATS; REQUIRES LEVEL 5 GWB
PTD-8: CHALKBOARD PAINT

PLASTIC LAMINATE

PLAM-1: (CASEWORK VERTICAL SURFACES, TYPICAL) TBD.
PLAM-2: (BACK OF HOUSE SHELVING) TBD.

PORCELAIN FLOOR TILE

PFT-1: CREATIVE MATERIALS CORPORATION, ROUNDABOUT, 8x8-INCH HEXAGON, COLOR : WHITE.
PFT-2: CREATIVE MATERIALS CORPORATION, ROUNDABOUT, 8x8-INCH HEXAGON, COLOR : LIGHT GREY.
PFT-3: CREATIVE MATERIALS CORPORATION, ROUNDABOUT, 8x8-INCH HEXAGON, COLOR : GREY.

PORCELAIN TILE BASE

PTB-1: CREATIVE MATERIALS CORPORATION, ROUNDABOUT, 3x24-INCH BULL NOSE TILE, COLOR: LIGHT GREY.

RESILIENT WALL BASE

RB-1: JOHNSONITE, MILLWORK PROFILE, EQUINOX, 4.5-INCHES HIGH, COLOR: TBD.
RB-2: JOHNSONITE, COVED TOE WALL BASE, 4-INCHES HIGH, COLOR: TBD.
RB-3: JOHNSONITE, MILLWORK PROFILE, MANDALAY, 3-INCHES HIGH, COLOR: BLACK #40.
RB-4: JOHNSONITE, MILLWORK PROFILE, EQUINOX, 4.5-INCHES HIGH, COLOR: TBD - ACCENT.
RB-5: JOHNSONITE, MILLWORK PROFILE, EQUINOX, 4.5-INCHES HIGH, COLOR: TBD - ACCENT.

RESILIENT STAIR ASSEMBLY

RSA-1: JOHNSONITE, RUBBER STAIR TREADS WITH INTEGRATED RISER AND VISUALLY IMPAIRED COLOR INSERT STRIP; COLOR: SMOKEY PEARL HAMMERED (WGD) WITH SMOOTH INSERT STRIP IN BIG TOP (294). 24x24-INCH METALLURGY TILE AT LANDINGS, COLOR: SMOKEY PEARL HAMMERED (WGD).

SEALED CONCRETE

SC: SHERWIN WILLIAMS/GENERAL POLYMERS, EPOXY WATER EMULSION PRIMER/SEALER (GP 3477); CLEAR.

SOLID SURFACE MATERIAL

SSM-1: (BREAK ROOM COUNTERTOPS) HANSTONE QUARTZ, COLOR TBD.
SSM-2: (RESTROOM COUNTERTOPS) WILSONART QUARTZ, COLOR TBD.
SSM-3: (COUNTERTOPS, TYPICAL) CORIAN, PRICE GROUP D

WALK-OFF MAT

WOM-1: BENTLEY MILLS, ROUGH IDEA (8RU260220T), 24x24-INCH TILE, COLOR: DRAFT (800655).
WOM-2: MATS INC., DUAL TRACK RECESSED FOOT GRILLE SYSTEM

WOOD

WD-1: DEADHEAD LUMBER, RESAWN TIMBER CO., CUSTOM STAINED WHITE OAK, TONGUE AND GROOVE PLANKS WITH MITRED CORNERS.
WD-2: DEADHEAD LUMBER, RESAWN TIMBER CO., CUSTOM STAINED WHITE OAK MOUNTED TO CEILING HUNG SUSPENSION SYSTEM.
WD-3: WOOD CASEWORK;

ROOM FINISH NOTES:

1. SEE GI001 FOR PROJECT GENERAL NOTES.
2. SEE GI002 FOR PARTITION LEGEND AND TYPE OF GWB COMPOSITION REQUIRED.
3. REFER TO FLOOR FINISH PLANS (ID101 - ID107) FOR ADDITIONAL INFORMATION REGARDING LOCATIONS OF FINISH MATERIALS, AND FLOOR FINISH PATTERNS.
4. REFER TO WALL FINISH PLANS (ID111 - ID117) FOR ADDITIONAL INFORMATION REGARDING TYPES AND LOCATIONS OF WALL APPLIED MATERIALS AND FINISHES.
5. REFER TO RCPS FOR ADDITIONAL INFORMATION REGARDING CEILING HEIGHTS AND TYPES.
6. ALL EXPOSED STRUCTURE, DUCTWORK AND SPRINKLER PIPING TO BE PAINTED, UNLESS NOTED OTHERWISE.

FINISH MATERIAL ABBREVIATIONS:

ACT	ACOUSTIC CEILING TILE
AP	ACRYLIC PANELS
AWP	ACOUSTIC WALL PANELS
CPT	CARPET
CT	CERAMIC TILE
EST	ENGINEERED STONE TILE
EXP	EXPOSED TO STRUCTURE
FRP	FIBER-REINFORCED PLASTIC
GL	GLASS
GT	GLASS TILE
GWB	GYPSUM WALL BOARD
LVT	LUXURY VINYL TILE
MCT	MARMOLEUM COMPOSITION TILE
MTL	METAL
PFT	PORCELAIN FLOOR TILE
PLAM	PLASTIC LAMINATE
PTB	PORCELAIN TILE BASE
PTD	PAINT(ED)
RB	RESILIENT BASE
RCP	REFLECTED CEILING PLAN
RSA	RESILIENT STAIR ASSEMBLY
SC	SEALED CONCRETE
SF	STOREFRONT
SSM	SOLID SURFACE MATERIAL
WD	WOOD
WOM	WALK-OFF MAT

REV	DESCRIPTION	DATE
1	ADDENDUM NO. 1	12-11-17

ADDENDUM NO. 1
12-11-17

CURRENT ISSUE STATUS:

SMRT Architects and Engineers
144 Fore Street/P.O. Box 618
Portland, Maine 04104
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY

WEX
CORPORATE HEADQUARTERS

PORTLAND, ME

LEVEL ONE & LEVEL TWO ROOM FINISH SCHEDULES

SHEET TITLE:

SCALE: AS NOTED

PROJECT MANAGER:	GWV	PROJECT NO:	17120-01
A/E OF RECORD:	GWV		
JOB CAPTAIN:	CBM		
DRAWN BY:	CBM		
SMRT FILE:	AE601-17120-01	SHEET No.	AE601

© COPYRIGHT 2017 SMRT INC.

NOT FOR CONSTRUCTION

Date: 06/15/18