Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/09/16

SECTION 1
1 1/2"=1'-0" S1.04

SHORE EXIST CEILING FRAMING.
CUT CEILING FRAMING BACK AND REMOVE LEDGERS.
INSTALL C12 AND THREADED RODS.
INSTALL BLOCKING AND CEILING FRAMING HANGERS.
REMOVE EXISTING TIMBER COLUMN.

SECTION 2
1 1/2"=1'-0" S1.04

SECTION 3
1"=1'-0" S1.03
S1.04

STATE OF MAINE
DAVID TERRAULT
4840
PROFESSIONAL ENGINEER

Prepared For:
GORHAM SAVINGS BANK
10 WENTWORTH DRIVE
GORHAM, ME 04038

Consulting Engineer:
STRUCTURAL DESIGN CONSULTING
2696 Lake Shore Road
Unit 1-330
Gilford, NH
03249
Tel 603.293.8038

Architect:
ARCHETYPE Architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
GRAND TRUNK BUILDING
1 India Street
Portland, Maine

Revisions:
Issued for Permit 03/15/16

Scale: As Noted

Date: 15 Mar 2016

STRUCTURAL
SECTIONS AND DETAILS

S2.01