Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/09/16

CRAWL SPACE SLAB PLAN

1/4"=1'-0"

REFER TO SUB-SLAB VAPOR MITIGATION SYSTEM LAYOUT PLAN PREPARED BY RANSOM CONSULTING, INC FOR VAPOR BARRIER AND ALL BELOW SLAB FILL AND PREPARATION WORK.

CONCRETE SLAB MIX PROPORTIONS:

28 DAY COMPRESSIVE STRENGTH	3,000 PSI
MAX. LARGE AGGREGATE SIZE	3/8"
MAX. W/C RATIO	0.48
SLUMP	3"±1"
WATER-REDUCING ADMIXTURE	ASTM C494, TYPE A
FIBER REINFORCING	ASTM C1116, TYPE III VIRGIN POLYPROPYLENE FIBERS 1 1/2 LBS. PER CU. YD.

Project North
W E
S

STATE OF MAINE
DAVID TERRAULT
4840
PROFESSIONAL ENGINEER

Prepared For:
GORHAM SAVINGS BANK
10 WENTWORTH DRIVE
GORHAM, ME 04038

Consulting Engineer:
STRUCTURAL DESIGN CONSULTING
2696 Lake Shore Road
Unit 130
Gilford, NH
03249
Tel 603.293.8038

Architect:
ARCHETYPE Architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
GRAD TRUNK BUILDING
1 India Street
Portland, Maine

Revisions:
Issued for Permit 03/15/16

Scale: 1/4"=1'-0"

Date: 15 Mar 2016

CRAWL SPACE SLAB PLAN

S1.00