FIRST FLOOR FIRE ALARM PLAN

SCALE: 1/4"=1'-0"

## SHEET NOTES:

1. ADDRESSABLE MONITOR MODULE(S) PROVIDED TO MONITOR ALL WATER FLOW, PRESSURE SWITCHES, TAMPER SWITCHES AND POST INDICATING VALVES ASSOCIATED WITH THE FIRE SPRINKLER SYSTEM. INSTALLING CONTRACTOR SHALL FIELD VERIFY EXACT MOUNTING, CIRCUITING AND PROGRAMMING REQUIREMENTS. FIELD VERIFY EXACT QUANTITY AND LOCATION(S).

2. PROVIDE HEAT DETECTOR(S) WITHIN 24" OF EACH SPRINKLER HEAD IN THE ELEVATOR CONTROL ROOM AND HOISTWAY(S). HEAT DETECTORS SHALL HAVE A LOWER TEMPERATURE RATING THAN THE SPRINKLERS IN THE AREA AND BE MONITORED FOR INTEGRITY.

3. ADDRESSABLE RELAY MODULES (4) PROVIDED FOR THE ELEVATOR RECALL AND SHUT DOWN. TIE TO ELEVATOR EQUIPMENT ROOM DETECTOR(S), HOISTWAY DETECTOR(S) AND LOBBY DETECTOR(S) TO INITIATE RECALL AND SHUT DOWN. ADDRESSABLE MONITOR MODULE PROVIDED TO MONITOR THE CONTROL CIRCUIT TO THE ELEVATOR SHUNT TRIP BREAKER FOR THE PRESENCE OF OPERATING VOLTAGE. LOSS OF VOLTAGE SHALL CAUSE A SUPERVISORY SIGNAL AT THE CONTROL PANEL. FIELD VERIFY EXACT MOUNTING, CIRCUITING AND PROGRAMMING REQUIREMENTS.

RESERVED FOR CITY STAMP

| REVISION | DESCRIPTION | DATE |
|---|---|---|
| 0 | ISSUED FOR REVIEW & APPROVAL | 8/19/2016 |

CUNNINGHAM
Security Systems
10 Princes Point Road, Yarmouth, Maine 04096
Office: 207.846.3350 • Fax: 207.846.6080

**GRAND TRUCK BUILDING**
**1 INDIA STREET**
**PORTLAND, MAINE 04101**
**FIRST FLOOR FIRE ALARM PLAN**

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 12/29/16

CITY OF PORTLAND, MAINE RESURGAM

shop drawings
created by:
5794 W. 4600 So.
Hooper, UT 84315
Office: 801.985.0410
UNI
www.unicpd.net
Fire Alarm Des