



NOTES:

DUE TO:
 VARIATIONS IN LAMPS,
 BALLASTS,
 MANUFACTURING,
 LINE VOLTAGE, AND
 SITE CONDITIONS,
 A GUARANTEED LEVEL OF
 PERFORMANCE IS NOT
 POSSIBLE AND IS NOT
 REPRESENTED BY THIS
 ANALYSIS.

1. THE RESULTS OF THIS
 STUDY ARE TO BE VIEWED
 ONLY AS AN INDICATION
 OF POSSIBLE
 PERFORMANCE.

2. LIGHT LOSS FACTORS
 (LLF) ARE AS NOTED
 IN SCHEDULE.

Luminaire Schedule

Symbol	Qty	Label	Arrangement	Total Lamp Lumens	LLF	Description	Mounting Height
□	6	MTRQL-3L35	GROUP	N.A.	0.850	MTRQL-12-4-3L35-30-120	14'
□	25	BSMFL-3L35	GROUP	N.A.	0.850	BSMFL-3-3L35-30-120	4'
●	8	LALC	SINGLE	N.A.	0.850	LALC-DB-FL-X-5G150-30-XX-120	10'

Calculation Summary

Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Walkway CalcPts	Illuminance	Fc	1.45	4.0	0.2	7.25	20.00

selux

5 LUMEN LANE
 P.O. BOX 1060
 HIGHLAND, NY 12528
 PH. (845) 691-7723

JOB NAME:
 Marriot AC Hotel

LOCATION:
 Portland ME

PREPARED FOR:
 selux Lighting Design

SELUX REPRESENT.
 CT

DRAWN BY:
 LLS

Page 1 of 1

Rev A

Date:4/7/2017