Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 04/12/16

1 WINDOW TYPES
1/4" = 1'-0"

ALL WINDOWS:
(EXTERIOR COLOR = BLACK)
(INTERIOR COLOR = WHITE)

2 TYPICAL WINDOW TRIM WITHIN DWELLING UNIT
NOT TO SCALE

LEGEND:
T = TEMPERED GLASS
FG = FIBERGLASS
AL = ALUMINUM
DH = DOUBLE HUNG
AW = AWNING
LV = LOUVER
F = FIXED
CL = GLIDER
C = CASEMENT
VL = VINYL
H = HOPPER
SL = SKY LIGHT

WINDOW SCHEDULE

KEY	ACTION	ROUGH * OPENING (WxH) VIF	R.O.HEAD HEIGHT FROM SUBFLOOR	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	MATERIAL	FINISH	REMARKS (FOR TEMPERED GLASS LOCATIONS SEE WINDOW ELEVATION TYPES; FOR MASONRY OPENING DIMENSIONS COORDINATE COURSING WITH EXTERIOR ELEVATION SHEETS AND PLAN AND SECTION DETAIL SHEETS)
A	DH	2'-8" X 6'-2"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING, 5/8" SIMULATED DIVIDED LIGHT
A'	DH	2'-8" X 6'-2"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING, 5/8" SIMULATED DIVIDED LIGHT, TEMPERED GLASS
B	DH	1'-7" X 6'-2"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING
C	DH	2'-8" X 6'-0"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING, 5/8" SIMULATED DIVIDED LIGHT
C'	DH	2'-8" X 6'-0"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING, 5/8" SIMULATED DIVIDED LIGHT, TEMPERED GLASS
D	DH	1'-7" X 6'-2"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING
E	DH	2'-8" X 5'-10"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING, 5/8" SIMULATED DIVIDED LIGHT
E'	DH	2'-8" X 5'-10"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING, 5/8" SIMULATED DIVIDED LIGHT, TEMPERED GLASS
F	F	———	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING
G	C	———	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING, TEMPERED GLASS
H	SL	2'-0" X 4'-0"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING
J	F	3'-2" X 3'-6"	-	-	-	-	AL	-	G.C. TO VERIFY WINDOW SIZE WITHIN EXISTING MASONRY OPENING, 5/8" SIMULATED DIVIDED LIGHT

NOTES:

1.) PROVIDE WINDOW SHADES AT ALL BEDROOM WINDOWS

WINDOW NOTES:

*1.) COORDINATE AND ADJUST ROUGH OPENING DIMENSIONS TO ACCOMMODATE SILL PAN FLASHING SYSTEM

2.) CONTRACTOR TO FIELD VERIFY SIZE OF WINDOWS IN EXISTING OPENINGS BEFORE WINDOWS ARE ORDERED FROM THE FACTORY

3.) HALF SCREENS ALL OPENINGS

4.) PROVIDE BRICKMOULD CASING AT ALL WINDOWS, PROVIDE ARCH TOP BRICK MOULD AND PANEL INFILL AT ALL ARCHED MASONRY HEADERS

5.) PROVIDE WINDOW OPENING CONTROL DEVICES FOR ALL WINDOWS TO LIMIT OPENINGS TO 4" MAXIMUM

6.) CONTRACTOR TO VERIFY THAT ALL EGRESS OPENINGS MEET EGRESS REQUIREMENTS

7.) ALL GLAZING LOCATED WITHIN 18" OF FINISHED FLOOR TO BE TEMPERED GLASS

8.) ALL EXTERIOR GLAZING TO BE INSULATED

9.) FRAME ALL OPENINGS WITH ELEVATIONS

10.) SEAL WINDOW TO ROUGH OPENING WITH LOW EXPANDING FOAMINSULATION - SEE DETAILS

REGISTERED ARCHITECT
RYAN J. SENATORE
No. 3322
STATE OF MAINE

© 2016 RYAN SENATORE ARCHITECTURE

RESIDENCES
107 INDIA STREET
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS STREET
PORTLAND, MAINE 04101
207-747-5159
senatorearchitecture.com

CONSULTANTS:

STRUCTURAL:
Structural Integrity
77 Oak Street
Portland, ME 04101
207-774-4614

REVISIONS:

DATE: FEBRUARY 5, 2016
PROJECT No.
DRAWN BY: RRT
CHECKED BY: RJS
SCALE: AS NOTED

SHEET TITLE:
WINDOW SCHEDULE

A7-1