- 2. EXISTING DIMENSIONS AND CONDITIONS ARE FOR REFERENCE ONLY. CONTRACTOR SHALL VERIFY ALL EXISTING CONSTRUCTION AND DIMENSIONS IN THE FIELD PRIOR TO CONSTRUCTION OR FABRICATION. ALL DISCREPANCIES SHALL BE REPORTED TO THE ENGINEER PRIOR TO COMMENCING WORK.
- 3. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IF DEVIATIONS OR CHANGES ARE REQUIRED TO THE CONTRACT DOCUMENTS OR APPROVED SHOP DRAWINGS DUE TO INTERFERENCES, FABRICATION ERRORS, OR OTHER CAUSES.
- 4. THE STRUCTURE IS SELF—SUPPORTING AND STABLE AFTER THE ENTIRE BUILDING IS COMPLETELY CONSTRUCTED. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR ERECTION PROCEDURES AND SEQUENCING DURING CONSTRUCTION AND ERECTION TO PROVIDE AND ENSURE LOCAL AND OVERALL STABILITY OF THE BUILDING AND ITS COMPONENTS DURING CONSTRUCTION AND ERECTION. THE CONTRACTOR SHALL RETAIN A LICENSED STRUCTURAL ENGINEER TO DESIGN TEMPORARY BRACING/SHORING AND DETERMINE WHERE THE TEMPORARY BRACING/SHORING IS NEEDED.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ERECTION PROCEDURES, SEQUENCING AND FOR COMPLYING WITH ALL APPLICABLE SAFETY REGULATIONS DURING THE WORK.
- 6. ONE ELECTRONIC COPY OR TWO SETS OF HARD COPIES OF SHOP DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER. ONE HARD COPY WILL BE RETURNED TO THE CONTRACTOR AND ONE HARD COPY WILL BE RETAINED BY THE ENGINEER.
- 7. REFERENCE THE PROJECT SPECIFICATIONS FOR MATERIAL, WORKMANSHIP AND ADDITIONAL INFORMATION NOT COVERED IN THESE NOTES (WHERE APPLICABLE)

<u>DESIGN CRITERIA:</u>

. BUILDING CODES:
INTERNATIONAL BUILDING CODE (IBC), 2009 EDITION
ASCE 7-05 MINIMUM DESIGN LOADS FOR BUILDING AND OTHER STRUCTURES
MAINE UNIFORM BUILDING AND ENERGY CODE

2. LIVE LOADS: UTILITY AREAS = 40 PSF STORAGE AREAS = 125 PSF

3. SNOW LOADS:

GROUND SNOW LOAD (Pg) = 60 PSF

SNOW EXPOSURE FACTOR (Ce) = 1.0

SNOW LOAD IMPORTANCE FACTOR (Is) = 1.0

THERMAL FACTOR (Ct) = 1.1

FLAT ROOF SNOW LOAD (Pf) = 46 PSF + DRIFT

COMPONENTS & CLADDING - PER ASCE 7-05

SEISMIC RESPONSE COEFFIENT (Cs) = 0.057

H. WIND LOADS:

BASIC WIND SPEED = 100 MPH

IMPORTANCE FACTOR (Iw) = 1.0

WIND EXPOSURE B

MAIN WINDFORCE-RESISTING SYSTEM (INCLUDES WINDWARD + LEEWARD) = 26 PSF (AT ROOF)

5. SEISMIC CRITERIA:

BASED ON EQUIVALENT LATERAL FORCE PROCEDURE

OCCUPANCY CATEGORY II

SOIL SITE CLASSIFICATION = D

SEISMIC IMPORTANCE FACTOR (Ie) = 1.0

DESIGN SPECTRAL RESPONSE ACCELERATION PARAMETER:

Sds = .371

Sd1 = .160

SEISMIC DESIGN CATEGORY B

RESPONSE MODIFICATION COEFFICIENT (R) = 6.5 (WOOD FRAMED SHEAR WALLS)

FOUNDATION NOTES:

- 1. FOUNDATIONS HAVE BEEN DESIGNED USING A PRESUMED ALLOWABLE BEARING PRESSURE PER TABLE 1806.2 OF THE INTERNATIONAL BUILDING CODE BASED ON TYPICAL SOILS FOUND IN THIS AREA. IF CLAY, MUD, ORGANIC SILT, PEAT OR UNPREPARED FILL IS FOUND DURING CONSTRUCTION, NOTIFY ENGINEER IMMEDIATELY, AS THE ALLOWABLE LOADS USED IN DESIGN WILL NEED TO BE VERIFIED BY A GEOTECHNICAL ENGINEER.
- 2. ALLOWABLE SOIL BEARING CAPACITY USED IN DESIGN = 2,000 PSF
- 3. MINIMUM FROST DEPTH COVER = 4'-6" FOR EXTERIOR FOOTINGS BELOW FINAL EXTERIOR GRADE.
- 4. EXCAVATION, BACKFILL, COMPACTION, GRADATION REQUIREMENTS, FOUNDATION DRAINAGE AND PERMANENT DEWATERING REQUIREMENTS SHALL BE PROVIDED BY A GEOTECHNICAL ENGINEER.
- 5. CONCRETE SLABS ON GRADE SHALL BE CONSTRUCTED ON A MINIMUM 12" THICK LAYER OF PROPERLY COMPACTED STRUCTURAL FILL.
- FOUNDATIONS SHALL BEAR ON UNDISTURBED NATIVE SOIL, UNLESS NOTED OTHERWISE. THE CONTRACTOR SHALL NOTIFY THE GEOTECHNICAL AND STRUCTURAL ENGINEER IF ANY UNSUITABLE SOILS ARE ENCOUNTERED PRIOR TO PLACING FOUNDATIONS.
- 7. FOUNDATION WALLS AND SLAB-ON-GRADES SHALL REACH THEIR FULL 28 DAY COMPRESSIVE STRENGTH PRIOR TO BACKFILLING. THE CONTRACTOR SHALL PROVIDE TEMPORARY SHORING/BRACING FOR WALLS WHEN BACKFILL IS PLACED PRIOR TO CONCRETE ACHIEVING ITS FULL 28 DAY STRENGTH.
- 8. PROTECT FOUNDATIONS FROM FROST AND KEEP BOTTOM OF TRENCH DRY DURING CONSTRUCTION. IF GROUNDWATER IS ENCOUNTERED NEAR OR ABOVE THE BASE OF THE FOOTINGS, EXCAVATIONS SHALL BE DEWATERED DURING CONSTRUCTION. SURFACE WATER SHALL BE DIVERTED AWAY FROM EXCAVATIONS.
- 9. DO NOT UNDERMINE EXISTING FOUNDATIONS OF ADJACENT STRUCTURES. CONTRACTOR SHALL BE RESPONSIBLE FOR THE SHORING AND BRACING OF EXISTING STRUCTURES DURING EXCAVATION, BACKFILLING, AND CONSTRUCTION. CONTRACTOR SHALL SLOPE EXCAVATIONS TO ACHIEVE SOIL STABILITY.

CONCRETE NOTES:

- 1. ALL WORK SHALL CONFORM TO THE LATEST EDITIONS OF "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE" (ACI 318) AND "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS" (ACI 301)
- 2. REQUIRED CONCRETE PARAMETERS ARE AS FOLLOWS:

 LOCATION	MAX W/C RATIO	f'c	AIR-ENTRAINMEN
INT. WALLS/ELEV. SLABS	.52	3,000 PSI	2% ± 1½%
FOUNDATIONS, FOOTINGS, & FOUNDATION WALLS	.45	4,500 PSI	6% ± 1½%
INT. SLAB-ON-GRADE	.45	4,500 PSI	2% ± 1½%
EXT. SLAB-ON-GRADE	.45	4,500 PSI	6% ± 1½%

WHERE: W/C = WATER TO CEMENT RATIO AND f'c = COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS

USE PORTLAND CEMENT TYPE II, IN CONFORMANCE WITH ASTM 150 AIR ENTRAINING ADMIXTURES SHALL CONFORM TO ASTM C 260 ADMIXTURES SHALL CONFORM TO ASTM C 494 FLY ASH USED AS ADMIXTURES SHALL CONFORM TO ASTM C 618

- 3. MAXIMUM AGGREGATE SIZE SHALL BE 3/4", IN CONFORMANCE WITH ASTM C33.
- 4. CALCIUM CHLORIDE OR ADMIXTURES CONTAINING CALCIUM CHLORIDE IS NOT PERMITTED.
- 5. MAXIMUM SLUMP AFTER THE ADDITION OF A WATER-REDUCING ADMIXTURE IS 6 INCHES.
- 6. CONTRACTOR SHALL NOT PLACE CONCRETE ON FROZEN GROUND OR IN WATER. ADEQUATE EQUIPMENT SHALL BE PROVIDED FOR HEATING CONCRETE MATERIALS AND PROTECTING CONCRETE DURING NEAR-FREEZING OR FREEZING WEATHER. REFERENCE ACI 306, AS NOTED ABOVE, FOR RECOMMENDATIONS FOR COLD WEATHER CONCRETING.
- 7. VERTICAL CONSTRUCTION JOINTS IN WALLS SHALL NOT EXCEED A SPACING OF 40 FEET, U.N.O.
- . ANCHOR BOLTS SHALL BE HEADED RODS AND CONFORM TO ASTM F1554, GRADE 36 KSI WELDABLE STEEL, U.N.O. ON DRAWINGS. PROVIDE GALVANIZED ANCHOR BOLTS WHERE IN CONTACT WITH PRESSURE TREATED LUMBER.
- 9. REINFORCING BARS SHALL CONFORM TO ASTM A615, GRADE 60, DEFORMED BARS.
- 10. WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185 AND BE PROVIDED IN FLAT SHEETS.
- 11. MINIMUM CONCRETE COVER FOR REINFORCEMENT SHALL BE AS FOLLOWS:

 A. CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH

 B. FORMED CONCRETE IN CONTACT WITH EARTH OR EXPOSED TO WEATHER

 C. CONCRETE NOT EXPOSED TO EARTH OR WEATHER IN SLABS & WALLS

 1½ INCHES
- 12. WELDING OF REINFORCEMENT IS NOT PERMITTED.
- 13. PROVIDE NON-SHRINK GROUT BENEATH LEVELING PLATES & BEARING PLATES w/ MINIMUM COMPRESSIVE STRENGTH OF 5,000 PSI AT 28 DAYS.
- 14. PROVIDE CONTINUOUS REINFORCEMENT AT ALL CORNERS AND INTERSECTIONS, SEE TYPICAL FOUNDATION WALL DETAILS ON FOUNDATION DETAILS SHEET.
- 15. REINFORCING BARS AND ALL EMBEDDED ITEMS, INCLUDING ANCHOR BOLTS, MUST BE ACCURATELY PLACED AND ADEQUATELY SECURED <u>BEFORE</u> CONCRETE IS PLACED. "WET SETTING" OF EMBEDDED ITEMS INTO CONCRETE IS STRICTLY PROHIBITED.
- 16. UNLESS NOTED ON DRAWINGS, FOLLOW ACI STANDARDS FOR LAP SPLICE LENGTHS OF REINFORCING BARS.

WOOD NOTES:

- 1. ALL TIMBER FRAMING SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AITC TIMBER CONSTRUCTION MANUAL AND AF&PA NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION (NDS).
- 2. ALL FRAMING SHALL BE SPRUCE-PINE-FIR, No.2 OR BETTER U.N.O. AND HAVE A MAXIMUM MOISTURE CONTENT OF 19%.
- 3. ALL WOOD IN CONTACT WITH MASONRY OR CONCRETE OR EXPOSED TO WEATHER SHALL BE PRESSURE TREATED (PT) SOUTHERN YELLOW PINE.
- 4. WHERE "LVL" IS NOTED ON DRAWINGS, PROVIDE VERSA LAM 3100 BY BOISE CASCADE, OR APPROVED EQUIVALENT, WHICH HAS THE FOLLOWING MINIMUM ALLOWABLE STRESSES:
 - Fb = 3100 PSI Fc = 2510 PSI (PARALLEL TO GRAIN)
 Fv = 285 PSI Fc = 750 PSI (PERPENDICULAR TO GRAIN)
 Ft = 1555 PSI E = 2,000,000 PSI
- 5. ALL ENGINEERED LUMBER THAT IS EXPOSED TO WEATHER SHALL BE WOLMANIZED.
- 6. ALL FLOOR SHEATHING SHALL BE 3/4" TONGUE AND GROOVE, GLUED AND NAILED TO FLOOR FRAMING WITH 8d RINK SHANK NAILS AT 6" o.c. AT SUPPORTED PANEL EDGES, 12" o.c. AT INTERMEDIATE SUPPORTS.
- 7. ALL ROOF SHEATHING (5/8") AND WALL SHEATHING (1/2") SHALL BE APA PERFORMANCE—RATED. ATTACH TO SUPPORTED PANEL EDGES WITH 8d NAILS AT 6" o.c. AND AT INTERMEDIATE SUPPORTS WITH 8d NAILS AT 12" o.c. U.N.O. SEE DRAWINGS FOR MORE STRINGENT NAILING REQUIREMENTS AT WOOD SHEAR WALLS.
- 8. SHEATHING SHALL BE ORIENTED WITH LONG DIMENSION PERPENDICULAR TO THE SUPPORTS AND BE CONTINUOUS OVER TWO OR MORE SUPPORTS. STAGGER ALL JOINTS & PROVIDE ADEQUATE JOINT SPACING (1/8" TYP) AS RECOMMENDED BY MANUFACTURER.
- 9. PROVIDE FULL DEPTH BLOCKING AT ENDS AND INTERIOR SUPPORTS OF ALL JOISTS AND RAFTERS WHERE JOISTS AND RAFTERS FRAME OVER SUPPORTS. PROVIDE 1x3 DIAGONAL BRIDGING OR FULL DEPTH SOLID BLOCKING FOR EACH 8'-0" OF SPAN FOR ALL JOISTS AND RAFTERS.
- 10. WHERE BEAMS ARE LABELED ON PLAN, DO NOT SPLICE BEAM NOR ANY PLY OF BEAM BETWEEN SUPPORTS.
- 11. ALL CONNECTION HARDWARE SHALL BE BY SIMPSON STONG—TIE (OR APPROVED EQUIVALENT) AND SHALL BE HOP—DIPPED GALVANIZED. HARDWARE IN CONTACT WITH PRESSURE TREATED (PT) LUMBER SHALL BE GALVANIZED G185 (ZMAX). REFER TO MANUFACTURERS LITERATURE FOR PROPER INSTALLATION GUIDELINES.
- 12. FASTENERS USED IN CONTACT WITH PRESSURE TREATED (PT) LUMBER SHALL BE HOT-DIPPED GALVANIZED, STAINLESS STEEL, OR OTHER FINISH APPROVED BY ENGINEER.
- 13. ALIGN COLUMNS SUCH THAT COLUMNS BEAR CONTINUOUSLY TO FOUNDATION SUPPORT. INSTALL ADDITIONAL SOLID BLOCKING WITHIN FLOOR PACKAGE TO PROVIDE CONTINUITY OF LOAD PATH.
- 14. PROVIDE HORIZONTAL BLOCKING FOR ALL LOAD BEARING WALLS AT 4'-0" O.C. VERTICAL, MAXIMUM.
- 15. SUBMIT SHOP DRAWINGS FOR ALL PREFABRICATED WOOD JOISTS AND WALL PANELS TO ENGINEER FOR REVIEW PRIOR TO CONSTRUCTION.

Phone 207.842.2800 Fax 207.842.2828 www.cascobayengineering.com
CLIENT:
SUNNY TIME SOLAR, LLC PO BOX 15372 PORTLAND, ME 04102
ANTHONY DUMAIS No. 12851
MAINE

CASCO BAY

ENGINEERING

424 Fore Street Portland, ME 04101

51 HANCOCK STREET
PORTLAND
NEW BUILDING

ABBREVIATIONS:

ADDL

BTWN

CIP

CJ

CLR

CMU

CNJ

COL

CONC

CONN

CONT

DIA

DWG

DISCONT

EL, ELEV

EQUIP

FDN

FLR

FTG

GALV

HSS

INFO

HOR, HORIZ

(E), EX, EXIST

CONTR

ARCH

ANCHOR BOLT

BOTTOM OF FOOTING

STRUCTURAL STEEL CHANNEL

CAST-IN-PLACE CONCRETE

CONCRETE MASONRY UNIT

COMPLETE PENETRATION WELD

CONSTRUCTION JOINT

DOUBLE ANGLE

LONG LEG HORIZONTAL

LONG LEG VERTICAL

LINEAR FOOT

POUND

MAXIMUM

MINIMUM

NUMBER

MECHANICAL

NEAR FACE

NEAR SIDE

ON CENTER

OPPOSITE

NOT TO SCALE

OUTSIDE FACE

PIER DESIGNATION

PREFABRICATED

REINFORCING STEEL

REQUIRED

ROOF DRAIN

SLIP CRITICAL

SLAB-ON-GRADE

SPECIFICATIONS

STAINLESS STEEL

SECTION

SHEATHING

SIMILAR

SPACING

STANDARD

STIFFENER

STEEL

TOP

STRAIGHT

STRUCTURAL

TOP AND BOTTOM

TOP OF CONCRETE

TOP OF FOOTING TEMPERATURE

TOP OF SHELF

TOP OF SLAB

TOP OF STEEL

TOP OF WALL

VERTICAL

WITH

WITHOUT

WORK POINT WEIGHT

WELDED WIRE FABRIC

VERIFY IN FIELD

STRUCTURAL TUBING

UNLESS NOTED OTHERWISE

STRUCTURAL STEEL WIDE FLANGE

PARTIAL PENETRATION WELD

POUNDS PER SQUARE FOOT

POUNDS PER SQUARE INCH

MANUFACTURER

MISCELLANEOUS

MECH

NTS

PREFAB

REINF

SECT

SOG

SPAC

STD

STIFF

STL

STR

T&B

TOC, T/CONC

T/FTG, TOF

T/SHELF

T/SLAB

T/STL

T/WALL

UNO

VER, VERT

STRUCT

SPECS

SHEATH

REQ, REQD

ADDITIONAL

ARCHITECT

BUILDING

BEAM

BOTTOM

BEARING

BETWEEN

CANTILEVER

CENTERLINE

COLUMN

CONCRETE

CONNECTION

CONTINUOUS

CONTRACTOR

CUBIC YARD

DIAMETER

DIMENSION

DRAWING

EXISTING

EACH FACE

ELEVATION

EQUIPMENT

EACH SIDE

EACH WAY

EXPANSION

EXTERIOR

FOUNDATION

FLANGE

FLOOR

FOOTING

FIELD VERIFY

GALVANIZED

HORIZONTAL

INSIDE FACE

INFORMATION

HEIGHT

INCH

HOLLOW STRUCTURAL SHAPE

KIP (1 KIP = 1,000 LBS)

KIPS PER SQUARE INCH

F00T

GAGE

FINISH FLOOR

FOOTING DESIGNATION

EQUAL

FACH

DISCONTINUOUS

CONTROL JOINT

	DATE	1-7-15				
	CKD. BY	TD				
	DR. BY	TD				
ISSUED	DESCRIPTION	ISSUED FOR PERMIT - NOT FOR CONSTRUCTION				
	No.	4				

SHEET TITLE:

STRUCTURAL NOTES

DESIGNED:	TD
DRAWN:	TD
DATE:	1-6-15
PROJECT NUMBER:	15-004

S0.0