SECOND FLOOR FRAMING PLAN

Scale: ¼" = 1'-0"

FLOOR FRAMING NOTES:

1. See structural notes sheet S1.
2. Built-up beams shall be spiked together w/ 3 rows of 16d nails @ 12" o.c.
3. Provide metal hangers at all joist connections..
4. Provide double joists below all upper parallel walls.
5. Provide solid blocking at mid-span of all joists.
6. See architectural drawings for all dimensions and openings.
7. Add solid blocking between floor joists below all posts.
8. Provide (2) 2 x 10 headers with 2" rigid insulation at all exterior window and door openings unless noted otherwise on plans.
9. Leave ⅛" gap between top of floor beams and bottom for plywood sheathing.
10. Field verify existing member size matches as shown. Notify engineer if member does not match.

THIRD FLOOR FRAMING PLAN

Scale: ¼" = 1'-0"

FLOOR FRAMING NOTES:

1. See structural notes sheet S1.
2. Built-up beams shall be spiked together w/ 3 rows of 16d nails @ 12" o.c.
3. Provide metal hangers at all joist connections..
4. Provide double joists below all upper parallel walls.
5. Provide solid blocking at mid-span of all joists.
6. See architectural drawings for all dimensions and openings.
7. Add solid blocking between floor joists below all posts.
8. Provide (2) 2 x 10 headers with 2" rigid insulation at all exterior window and door openings unless noted otherwise on plans.
9. Leave ⅛" gap between top of floor beams and bottom for plywood sheathing.

ENGINEERING DESIGN PROFESSIONALS
Consulting Engineers
P.O. BOX 575, FREEPORT, MAINE 04032 • (207) 865-9505

Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 03/13/15

PROJECT:
Fournier Apartment
16 Federal Street, Portland, ME

DRAWING:
2nd & 3rd FLOOR FRAMING PLANS

STATE OF MAINE
LARRY A. WICHROSKI
No. 5080
LICENSED
PROFESSIONAL ENGINEER

DESIGNED BY:	Larry A. Wichroski, P.E.
DRAWN BY:	LAW
JOB #:	06614
DATE:	12-18-2014

REVISIONS

SHEET:
S3
of 4