


Quality Assurance Labs Inc.

NON-DESTRUCTIVE TESTING AND INSPECTION SERVICES

80 PLEASANT AVENUE • SOUTH PORTLAND, MAINE 04106 • TEL: (207) 799-8911 • FAX: (207) 799-7251

ULTRASONIC INSPECTION REPORT

CUSTOMER: SW COLE GRAY OFFICE		DATE OF INSPECTION		M	D	Y
				07	21	08
ATTENTION:		REPORT No.		QAL-08-1418		
PROJECT: MARRIOTT HOTEL		PAGE		1	OF	1
COMPONENT INSPECTED: 3RD FLOOR FRAMING		JOB No.		06-0726		
AREA OF INTEREST: MOMMENT CONNECTIONS		P.O. No.		VERBAL		
COMPONENT LOCATION: PORTLAND, ME		INSTRUMENT				
CUSTOMER WORK ORDER No: N/A		PART No.: N/A		MAKE: PANAMETRICS		
MATERIAL: CARBON STEEL		HEAT No.: N/A		MODEL: LTC		
COMPONENT SURFACE CONDITION: AS WELDED		EQUIPMENT No.:				
EXAMINATION DATA		MATERIAL THICKNESS: 12.7 mm (0.500 in.)				
Project Code/Spec: AWS D1.1		SCREEN RANGE: 10"				
U.T. Procedure No.		U.T. Technique No.		COUPLANT: SONO CLEAR		
RESULTS: AS NOTED		INDICATIONS: NONE		TRANSDUCERS		
REMARKS: PERFORMED ULTRASONIC INSPECTIONS ON 3RD FLOOR FRAMMING MOMMENT CONNECTIONS IAW AWS.D1.1. GRID LINES: A-2 WEST & EAST T/B A-3 WEST & EAST T/B A-4 WEST & EAST T/B CIV EAST T/B C-4 WEST & EAST T/B C-5 WEST T/B T/B = TOP & BOTTOM NOTE: ACCEPT,NO CRACKS, CRACKLIKE, OR RELIVANT INDICATIONS NOTED AT TIME OF INSPECTION. ////LAST ITEM <p style="text-align: center;">FAA REPAIR STATION NUMBER RX5R187N METHOD(S),PROCESS(ES),PROCEDURE(S) MERCURY FREE</p>		MAKE: PANAMETRICS				
		FREQ.: 2.25 MHz		ANGLE: 70°		
		SIZE: 12.7 mm (0.500 in.)				
		STYLE: SINGLE		SHAPE: SQUARE		
		EQUIPMENT No.:				
		MAKE: PANAMETRICS				
		FREQ.: 2.25 MHz		ANGLE: 0°		
		SIZE: 25.4 mm (1.000 in.)				
		STYLE: SINGLE		SHAPE: ROUND		
		EQUIPMENT No.:				
MAKE:						
FREQ.:		ANGLE:				
SIZE:						
STYLE:		SHAPE:				
EQUIPMENT No.:						
REFERENCE BLOCKS						
MAKE: PANAMETRICS						
TYPE: IIW						
MATERIAL: CARBON STEEL						
EQUIPMENT No.:						
SENSITIVITY: 64.3db + 6db						
TRANSFER VALUE:						
ADDITIONAL INFORMATION - SEE ATTACHED: <input type="checkbox"/> SKETCH(ES) <input checked="" type="checkbox"/> SUPPLEMENTARY SHEET(S) <input type="checkbox"/> VIDEO		CERTIFICATION		DATE		
SIGNATURES		LEVEL		M	D	Y
INSPECTOR S. DYER 		ASNT II		07	21	08
SUPERVISOR						
AUTHORIZED INSPECTOR						
CUSTOMER REPRESENTATIVE						