



ISSUED FOR CONSTRUCTION - 11/05/07

NO.	REVISION	DATE

SCALE: As Noted
DATE:
DRAWN BY: JR
CHECKED BY: JR

PERMIT REVIEW CORRECTIONS 1-16-08

KEY PLAN (Occupant Load Table (1004.1.2))

AS - ASSEMBLY	Unconcentrated 15 sq. ft. / person net
RI - HOTEL	Concentrated 7 sq. ft. / person net
BUSINESS	200 sq. ft. / person - gross
KITCHEN	200 sq. ft. / person gross
EXERCISE ROOM, AND POOL	50 sq. ft. / person gross
POOL DECK	15 sq. ft. / person gross
STORAGE/MECHANICAL	300 sq. ft. / person gross
MERCANTILE	60 sq. ft. / person gross

EGRESS ANALYSIS

- Lobby and egress access corridors: First floor - three exists required and provided. 2nd, 3rd, 4th and 5th floors - two exists required and provided.
- Exit signs, as shown on plans to be approved by local fire marshalls office.
- Length of exit access travel 200' per Table 1015.1.170' provided

Accessible entrances and exists

GROUP ONE
21 W. THIRD STREET, BOSTON, MA 02127
TEL: (617)288-7000 FAX: (617)288-0209

RESIDENCE INN BY MARRIOTT
PORTLAND, ME
JOB# 802

CODE REVIEW- OCCUPANCY AND EGRESS

DRAWING NO. **A0.2**