

Quality Assurance Labs Inc.

NON-DESTRUCTIVE TESTING AND INSPECTION SERVICES

80 PLEASANT AVENUE • SOUTH PORTLAND, MAINE 04106 • TEL: (207) 799-8911 • FAX: (207) 799-7251

INSPECTION REPORT

CUSTOMER: S. W. COLE ENG.		PAGE 1 OF 1	
ADDRESS: GRAY, ME.			
ATTENTION: ROGER DOMINGO			
COPIES:			
PROJECT: MARIOTT AT OCEAN GATEWAY			
OWNER: MARIOTT			
CONTRACTOR: LEDGEWOOD CONSTRUCTION			
JOB No.: 06-0726.2	REPORT No.: QAL-08-1290	P. O. NUMBER:	DATES INSPECTED: 07-01-08

REMARKS

>>>> SITE VISIT TO PERFORM VISUAL INSPECTION OF STRUCTURAL STEEL CONNECTIONS: GRID LINES 20-26, N-X TO INCLUDE ALL LEVELS.

> ANCHOR BOLTED CONNECTIONS COMPLETE. HOWEVER, LOCATION LINE 23 SHOWS (2) COLUMNS WITH SHORT ANCHOR BOLTS. BY USING JUST THE SQUARE BASE WASHERS AND FIELD WELD BOLT TO WASHER AND BASE PLATE WOULD BE A SIMPLE FIX. REQUEST RFI FOR FINAL DISPOSITION.

> LOWER LEVEL PLANK TO GIRDER CONNECTIONS APPROX. 80% COMPLETE. ROOF LEVEL FRAMING PLAN IN-PROGRESS.


> DIAGONAL LOWER BOLTED CONNECTIONS IN-PROCESS FOR FINAL TORQUE.

COMPLETED ITEMS COMPLY WITH SITE DOCUMENTS AND AWS D1.1 REQUIREMENTS FOR VISUAL ACCEPTANCE.

END ITEMS ////

FAA REPAIR STATION NUMBER RX5R187N
METHOD(S), PROCESS(ES), PROCEDURE(S) MERCURY FREE

ADDITIONAL INFORMATION - SEE ATTACHED: SKETCH(ES) SUPPLEMENTARY SHEET(S) NDT REPORTS VIDEO

SIGNATURES		CERTIFICATION		DATE			
		LEVEL		M	D	Y	
INSPECTOR	MICHAEL DREW CWI # 99050211 				07	03	08
SUPERVISOR							