


Quality Assurance Labs Inc.

NON-DESTRUCTIVE TESTING AND INSPECTION SERVICES

80 PLEASANT AVENUE • SOUTH PORTLAND, MAINE 04106 • TEL: (207) 799-8911 • FAX: (207) 799-7251

ULTRASONIC INSPECTION REPORT

CUSTOMER: SW COLE GRAY OFFICE		DATE OF INSPECTION	M	D	Y
ATTENTION: CRAIG		REPORT No.	10	03	08
PROJECT: MARRIOTT HOTEL		PAGE	1	OF	1
COMPONENT INSPECTED: 5th FLOOR FRAMING		JOB No.	06-0726		
AREA OF INTEREST: MOMENT CONNECTIONS		P.O. No.	06-0726.2		
COMPONENT LOCATION: PORTLAND ME		INSTRUMENT			
CUSTOMER WORK ORDER No: 06-0726.2	PART No.: N/A	MAKE: PANAMETRICS			
MATERIAL: CARBON STEEL	HEAT No.: N/A	MODEL: LTC			
COMPONENT SURFACE CONDITION: AS WELDED		EQUIPMENT No.: 35403			
EXAMINATION DATA		MATERIAL THICKNESS: 15.875 mm (0.625 in.)			
Project Code/Spec AWS D1.1		SCREEN RANGE: 10"			
U.T. Procedure No.		U.T. Technique No.			
RESULTS: AS NOTED	INDICATIONS: AS NOTED	COUPLANT: SONO-CLEAR			
REMARKS: PERFORMED ULTRASONIC INSPECTION ON THE FOLLOWING MOMENT CONNECTIONS IAW AWS D1.1. GRID LINES: C-10 WEST T/B ACCEPTED C-11 EAST & WEST T/B ACCEPTED A-10 EAST & WEST T/B ACCEPTED A-11 EAST & WEST T/B ACCEPTED A-12 EAST & WEST T/B ACCEPTED A-13 EAST & WEST T/B ACCEPTED ACCEPT: ALL REMAINING WELDS UNLESS NOTED NO CRACKS, CRACKLIKE, OR RELEVANT INDICATIONS NOTED. T/B = TOP & BOTTOM. /// LAST ITEM///		TRANSDUCERS			
		MAKE: PANAMETRICS			
		FREQ.: 2.25 MHz		ANGLE: 0°	
		SIZE: 25.4 mm (1.000 in.)			
		STYLE: SINGLE		SHAPE: ROUND	
		EQUIPMENT No.:			
		MAKE: PANAMETRICS			
		FREQ.: 2.25 MHz		ANGLE: 70°	
		SIZE: 12.7 mm (0.500 in.)			
		STYLE: SINGLE		SHAPE: SQUARE	
EQUIPMENT No.:					
MAKE:					
FREQ.:		ANGLE:			
SIZE:					
STYLE:		SHAPE:			
EQUIPMENT No.:					
REFERENCE BLOCKS					
MAKE: PANAMETRICS					
TYPE: IIW					
MATERIAL: CARBON STEEL					
EQUIPMENT No.:					
SENSITIVITY: 58db					
ADDITIONAL INFORMATION - SEE ATTACHED: <input type="checkbox"/> SKETCH(ES) <input type="checkbox"/> SUPPLEMENTARY SHEET(S) <input type="checkbox"/> VIDEO					
SIGNATURES		CERTIFICATION		DATE	
		LEVEL		M D Y	
INSPECTOR S. Dyer 	ASNT	II	10	03	08
SUPERVISOR					
AUTHORIZED INSPECTOR					
CUSTOMER REPRESENTATIVE					
		TRANSFER VALUE:			