



May 23, 2016

Jubilacion Llc

1090 North Rd

North Yarmouth, ME 04097

CBL: 020 D009001

Located at 0058 FEDERAL ST

NOTICE OF INTENT TO PROSECUTE

Dear Owner/Manager/Occupant,

An inspection of the property located at the address referenced above revealed that the structure and premises fail to comply with NFPA 2009 Fire Code and/or NFPA Life Safety Codes. Attached is a list of those violations.

The above-referenced property is in violation of the Chapter 10, Fire Prevention and Protection, Article 1 of the Portland City Code (the "Code") and National Fire Protection Association (NFPA) 101 Life Safety Code. Please note that the Code is available online at www.portlandmaine.gov.

This is a notice of intent to prosecute. As such, the matter is being referred to the City of Portland Corporation Council for legal action and possible civil penalties as provided for in Chapter 10, Fire Prevention and Protection, 10-25 of the Code and in Title 30- A.M.R.S.A. 4452.

Please be advised that you will need to contact the Fire Prevention Bureau at 207-874-8400 before the court date on the attached Reference to Court letter to either schedule a re-inspection or to submit a plan of action to correct these violations.

Sincerely,

A handwritten signature in cursive script that reads "Capt. Petrucci".

Portland Fire Department

Fire Prevention Bureau

**CITY OF PORTLAND
PORTLAND FIRE DEPARTMENT**

380 Congress Street
Portland, Maine 04101

354518

Inspection Violations

Owner/Manager Jubilacion Llc		Inspector Daniel Small	Inspection Date 5/21/2016
Location 0058 FEDERAL ST	CBL 020 D009001	Status Failed	Inspection Type Fire Company-FP Routine Inspec

Code	Int/Ext	Floor	Unit No.	Area	Compliance Date
------	---------	-------	----------	------	-----------------

1) 73.10

Violation: NFPA 101-7.2.4.3.1 FIRE BARRIER REQUIRES MAINTENANCE; Fire barriers separating buildings or areas between which there are horizontal exits shall have a minimum 2-hour fire resistance rating, unless otherwise provided in 7.2.4.4.1, and shall provide a separation that is continuous to the finished grounded level.

Notes: PANELING LOCATED IN FRONT HALLWAY OF #56

2) 73.15

Violation: NFPA 101- 31.3.1.1.1 VERTICAL OPENINGS NOT FIRE RATED; VERTICAL OPENINGS SHALL BE ENCLOSED OR PROTECTED IN ACCORDANCE WITH SECTION 8.6.

Notes: STAIRWAY WALLS AND CEILINGS HAVE BREACHES IN PLASTER

3) 80.28

Violation: NFPA 101- 7.5.1.1 EXIT OBSTRUCTED; Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to not less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4.

Notes: ALL AREAS---3RD FLOOR REAR STAIRWAY IS COMPLETELY BLOCKED

4) 80.88

Violation: NPFA 101- 7.2.2.1.1 STAIRS REQUIRE REPAIR; Stairs shall meet the following criteria:
 (1) New stairs shall be in accordance with Table 7.2.2.2.1.1(a)
 (2) Existing stairs shall be permitted to remain in use, provided that they meet the requirements for existing stairs shown in Table 7.2.2.2.1.1(b)
 (3) Approved existing stairs shall be permitted to be rebuilt in accordance with the following: (a) dimensional criteria of table 7.2.2.2.1.1(b) and other stair requirements of 7.2.2
 (4) The requirements for new and existing stairs shall not apply to stairs located in industrial equipment access areas where otherwise provided in 40.2.5.2.

Notes: MISSING BALUSTERS IN STAIRWAYS

5) 91.15

Violation: NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS; Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating.

Notes: BASEMENT

CITY OF PORTLAND
PORTLAND FIRE DEPARTMENT

380 Congress Street
Portland, Maine 04101

Inspection Violations

Owner/Manager Jubilacion Lic		Inspector Daniel Small	Inspection Date 5/21/2016
Location 0058 FEDERAL ST	CBL 020 D009001	Status Failed	Inspection Type Fire Company-FP Routine Inspec

6) 91.20

Violation: NFPA 70- 590.6 EXTENSION CORDS; Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities.

Notes: SEVERAL CORDS USED AS A PERMANENT WIRING-BASEMENT

7) 91.25

Violation: NFPA 70 MISSING BOX COVERS; REFER TO NFPA 70, NATIONAL ELECTRICAL CODE, ON STANDARDS FOR MISSING BOX COVERS.

Notes: BASEMENT

8) 91.30

Violation: NFPA 70 MISSING BREAKER IN PANEL; REFER TO NFPA 70, NATIONAL ELECTRICAL CODE, FOR INFORMATION ON MISSING BREAKERS IN AN ELECTRICAL PANEL.

Notes:

9) 3.011

Violation: NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; THE AREAS DESCRIBED IN TABLE 31.3.2.1.1 SHALL BE PROTECTED AS INDICATED:
BOILER AND FUEL-FIRED HEATER ROOMS SERVING MORE THAN A SINGLE DWELLING UNIT
(MINIMUM SEPARATION/PROTECTION IS 1 HOUR OR SPRINKLERS)

Notes: HOT WATER HEATERS IN BASEMENT

Comments: Inspections from Naviline Fire Inspections. 3 were listed.

STATE OF MAINE

DISTRICT COURT
Location: Portland
Docket No.

CITY OF PORTLAND and body politic and
Corporate, located in the County of
Cumberland and State of Maine,

Plaintiff,

**FIRE PREVENTION AND PROTECTION
CODE VIOLATION**

(M.R. CIV. P. 80H AND 80k)

v.

Jubilacion LLC
Defendant

SUMMONS NUMBER: 354518

This matter has been referred to the Corporation Counsel's Office for immediate legal action with respect to the code violations detailed in the attached letter. It has been assigned the above summons number and will be filed with the Portland District Court and will be assigned for an initial appearance at the Portland District Court 205 Newbury Street Portland, Maine 04101 at 8:30 A.M. on 08/08/2016. Please contact Tori Ross in Fire Prevention at (207)-874-8400 or via e-mail at meservev@portlandmaine.gov to set up an in-person meeting to meet with somebody in the Fire Prevention Bureau to resolve these issues or make alternative arrangements to relieve you of the requirement to appear in Court on 08/08/2016.

Dated:



Corporation Counsel
City of Portland
389 Congress St
Portland, ME 04101
207-874-8480

Danielle P. West-Chubita
Bar #9532