

CITY OF PORTLAND  
 FIRE PREVENTION BUREAU  
 380 Congress Street, Portland, Maine 04101  
 fireprevention@portlandmaine.gov  
 (207) 874-8400

**NOTICE OF VIOLATION AND ORDER TO CORRECT**

November 8, 2017

<b>Responsible Party 1:</b> Bogner Colleen 1090 North Rd North Yarmouth, ME 04097		
<b>Location</b> 56 FEDERAL ST	<b>CBL</b> 020 D009001	<b>Inspection Date</b> 10/4/2017
<b>Inspector</b> Sean Donaghue	<b>Inspection Type</b> FP Routine Inspection	<b>Status</b> Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

**You must send this form to the Fire Prevention Bureau no later than 11/30/2017.**

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
<b>PORTLAND FIRE DEPARTMENT CHAPTER 10 4.6.1, 4.6.2 UNIT/SUITE NUMBERS NOT MARKED;</b> 4.6.1 Residential units shall be designated using numerals. 4.6.2 The first numeral of each residential unit shall be the floor designation. All unit doors require identification numbering	___/___/___
<b>NFPA 101- 31.3.1.1.1 VERTICAL OPENINGS NOT FIRE RATED;</b> Vertical openings shall be enclosed or protected in accordance with Section 8.6. 58 third floor hallway wall needs proper fire rated divider, currently plastic window in wall	___/___/___
<b>NFPA 101- 7.2.1.8.1 FIRE DOORS MUST BE SELF- OR AUTO-CLOSING;</b> A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3. Please ensure all fire doors self close properly, 56 Unit 2 and Basement doors don't close properly	___/___/___
<b>NFPA 101- 7.2.8.5.1 HANDRAILS REQUIRED ON STAIRS;</b> All fire escape stairs shall have walls or guards and handrails on both sides in accordance with 7.2.8.4.1 (b). 56 side basement handrail requires shoring/support, missing balusters interior handrails and exterior deck	___/___/___
<b>NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED;</b> In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements. 58 Unit 1 inoperable smoke detector in sleeping area requires replacement	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.

Violation	Proposed Date of Completion
<p><b>NFPA 1 EXCESSIVE/DISORDERLY STORAGE;</b> Reference NFPA 1 for excessive fuel-load.</p> <p>No storage permitted in egress hallways, debris found in both front and back stairwells on both 56 and 58 sides</p>	<p>___/___/___</p>
<p><b>NFPA 70- 590.6 EXTENSION CORDS;</b> Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities.</p> <p>No permanent use of extension cords, noted in 58 Unit 2</p>	<p>___/___/___</p>
<p><b>NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED;</b> The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers)</p> <p>On demand hot water heater requires sprinkler protection, 56 side basement</p>	<p>___/___/___</p>
<p><b>NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED;</b> Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour.</p> <p>58 Basement door is not fire rated</p>	<p>___/___/___</p>
<p><b>FINAL DATE OF COMPLETED VIOLATION(S)</b></p>	<p>___/___/___</p>
<p><b>FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)</b></p>	<p>___/___/___</p>

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

**VIOLATOR CERTIFICATION**

*I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.*

*I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.*

*If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.*

\_\_\_\_\_

Date

\_\_\_\_\_

Responsible Party

\_\_\_\_\_

Date

\_\_\_\_\_

Responsible Party

**SEEN AND AGREED**

\_\_\_\_\_

Date

\_\_\_\_\_

Fire Prevention Bureau