



**CONSTRUCTION CLASSIFICATION:**

**NFPA: TYPE 5 (1,1,1)**  
**IBC: TYPE 5A**

PROTECTED STRUCTURE:  
 THE BUILDING IS A '5A' PROTECTED STRUCTURE. PRIMARY AND SECONDARY STRUCTURE, INCLUDING WOOD AND STEEL, SHALL BE FIRE SPRAYED AND OR GWB ENCASED TO THICKNESS SHOWN IN THE PLANS.

NOTE:  
 PRIMARY WOOD BEAMS SHALL BE INDIVIDUALLY PROTECTED W/ F.C. GWB ENCASEMENT. SECONDARY MEMBERS SHALL BE A PART OF THE HORIZONTAL ASSEMBLY