

Model: WL-LED100

LEDme® Step Light

WAC LIGHTING

Responsible Lighting®




Fixture Type:

Catalog Number:

Project: _____

Location: _____



PRODUCT DESCRIPTION

Horizontal rectangle LEDme® Step Light. Designed for safety and style on stairways, patios, decks, balcony areas, walkways and building perimeters. Features an architectural design. Energy efficient for long-lasting indoor and outdoor lighting solutions. Creates an attractive, romantic impression at night.

FEATURES

- 316 marine grade cast stainless steel (SS) available
- Direct wiring, no driver needed
- Low profile, flush to wall aesthetics with no visible hardware
- Turtle friendly (AM, RD colors)
- 40,000 hour rated life
- Balanced lighting, free of shadows with minimum glare
- Up to 200 fixtures can be connected in parallel
- Replaceable LED module
- 5 year WAC Lighting product warranty

SPECIFICATIONS

Construction: Die-cast aluminum or 316 marine grade cast stainless steel

Power: Direct wiring, no remote driver needed. Input voltage: 120V or 277V AC 50/60Hz

Light Source: 3000K CCT Samsung HV-AC High Power LED, CRI: 85
Optional color lenses. Total power consumption of 3.9W

Mounting: Fits into 2" x 4" J-Box with minimum inside dimensions of 3"L x 2"W x 2"H

Includes bracket for J-Box mount. See next page for spacing recommendations

Dimming: Dim to 10% with electronic low voltage (ELV) dimmer
Approved dimmers: Lutron Skylark SELV-300P-WH and Leviton Vizia VPE04

Standards: IP66, UL & cUL Listed for wet locations


FIXTURE PERFORMANCE

Model #	Lm	Model #	Lm	Model #	Lm	Model #	Lm	Model #	Lm
WL-LED100-C-SS	45	WL-LED100-C-BK	31	WL-LED100-C-WT	68	WL-LED100-C-BN	31	WL-LED100-C-BZ	32
WL-LED100-AM-SS	28	WL-LED100-AM-BK	19	WL-LED100-AM-WT	38	WL-LED100-AM-BN	19	WL-LED100-AM-BZ	21
WL-LED100-RD-SS	3	WL-LED100-RD-BK	2	WL-LED100-RD-WT	4	WL-LED100-RD-BN	2	WL-LED100-RD-BZ	2
WL-LED100-BL-SS	5	WL-LED100-BL-BK	3	WL-LED100-BL-WT	8	WL-LED100-BL-BN	3	WL-LED100-BL-BZ	4
WL-LED100F-C-SS	37	WL-LED100F-C-BK	25	WL-LED100F-C-WT	58	WL-LED100F-C-BN	25	WL-LED100F-C-BZ	27
WL-LED100F-AM-SS	20	WL-LED100F-AM-BK	14	WL-LED100F-AM-WT	29	WL-LED100F-AM-BN	14	WL-LED100F-AM-BZ	15
WL-LED100F-RD-SS	2	WL-LED100F-RD-BK	1.5	WL-LED100F-RD-WT	3	WL-LED100F-RD-BN	1.5	WL-LED100F-RD-BZ	2
WL-LED100F-BL-SS	4	WL-LED100F-BL-BK	3	WL-LED100F-BL-WT	6	WL-LED100F-BL-BN	3	WL-LED100F-BL-BZ	3

ORDER NUMBER

Model #	Color	Finish
WL-LED100	C White 3000K	SS Stainless Steel
WL-LED100F	AM Amber 610nm	BK Black
	RD Red 640nm	WT White
	BL Blue 450nm	BN Brushed Nickel
		BZ Bronze

FINISHES



Example: WL-LED100F-BL-SS

WAC Lighting
www.waclighting.com
Phone (800) 526.2588 • Fax (800) 526.2585

Headquarters/Eastern Distribution Center
44 Harbor Park Drive • Port Washington, NY 11050
Phone (516) 515.5000 • Fax (516) 515.5050

Western Distribution Center
1750 Archibald Avenue • Ontario, CA 91760
Phone (800) 526.2588 • Fax (800) 526.2585

Model: WL-LED100


LEDme® Step Light

WAC LIGHTING


Responsible Lighting®

Spacing Recommendations for Optimal Light Distribution


Corridors / Hallways



Stairs - Wall Mount



Stairs - Step Mount



Mount in center of stair as close to the upper tread as possible.
For best results use one light per step for steps narrower than 5'.

WAC Lighting
www.waclighting.com
Phone (800) 526.2588 • Fax (800) 526.2585

Headquarters/Eastern Distribution Center
44 Harbor Park Drive • Port Washington, NY 11050
Phone (516) 515.5000 • Fax (516) 515.5050

Western Distribution Center
1750 Archibald Avenue • Ontario, CA 91760
Phone (800) 526.2588 • Fax (800) 526.2585