REPORT

April 30, 2015 14-1366.2 DRAFT - ISSUED FOR REVIEW IN ORDER TO BEGIN PHASE 1 OF SOIL STABILIZATION. REFERENCE 4.3.1 ALSO COMPLETE BACKFILL OF FOUNDATIONS NOT COMPLETED TO DATE PER ATTACHED SITE PHOTO (BUTTRESS FILL AND BACKFILL PLAN)

Geotechnical Engineering Services

Evaluation of Apparent Slope Movement Seaport Lofts 113 Newbury Street Portland, Maine

PREPARED FOR:

Landry/French Construction Attention: Denis R Landry 160 Pleasant Hill Road Scarborough, ME 04074

PREPARED BY:

S. W. Cole Engineering, Inc. 286 Portland Road Gray, ME 04039 T: (207) 657-2866



- Geotechnical Engineering
- Construction Materials Testing
- GeoEnvironmental Services
- Ecological Services

www.swcole.com

1.0 INTRODUCTION	1
1.1 Scope and Purpose	1
1.2 Site and Proposed Construction	2
2.0 EXPLORATION AND TESTING	3
2.1 Explorations	3
2.2 Testing	3
3.0 SITE AND SUBSURFACE CONDITIONS	4
3.1 Surficial	
3.2 Soil and Bedrock	4
3.3 Groundwater	
4.0 EVALUATION AND RECOMMENDATIONS	5
4.1 General Findings	5
4.2 Global Stability	6
4.3 Slope Stabilization	6
4.3.1 Option 1 – Double Sheetpile Walls	7
4.3.2 Option 2 – Pile Supported Retaining Wall	7
5.0 CLOSURE	8

TABLE OF CONTENTS

Attachment A	Limitations
Sheet 1	Exploration Location Plan
Sheets 2 - 5	Exploration Logs
Sheet 6	Key to Notes and Symbols used on Logs
Appendix A	Survey Monitoring and Slope Inclinometer Readings
Appendix B	Global Stability Analyses
Appendix C	Sketch Plans of Stabilization Options



14-1366.2

April 30, 2015

Landry/French Construction Attention: Denis R Landry 160 Pleasant Hill Road Scarborough, ME 04074

Subject: Geotechnical Engineering Consultation Services Evaluation of Apparent Slope Movement Seaport Lofts 113 Newbury Street Portland, Maine

Dear Denis:

As requested on April 10, 2015 and in accordance with our Agreement, dated April 16, 2015, we have initiated evaluation of an area of apparent slope movement around a retaining wall along the northwesterly site boundary generally between building lines 12 to 21. This report summarizes our findings and geotechnical recommendations for the repair scheme and its contents are subject to the limitations set forth in Attachment A.

1.0 INTRODUCTION

1.1 Scope and Purpose

The purpose of our services is to assist Landry/French Construction in geotechnical evaluation of the slope movement area and development of slope stabilization plans. Our scope of services included:

- Site reconnaissance on April 11, 2015,
- Consideration of Construction Documents,
- Consideration of Geotechnical Reports by Geotechnical Services, Inc. dated August 24, 2013 and Sebago Technics, Inc. dated October 3, 2007,
- Consideration of Optical Survey Data by H.B.Fleming, Inc. and Titcomb Survey on monitoring points established prior to April 11 and additional monitoring points recommended by S.W.COLE,

286 Portland Road, Gray, ME 04039-9586 • P: (207) 657.2866 • F: (207) 657.2840 • E: infogray@swcole.com



- Drilling two test borings to collect subsurface information and install two slope inclinometers,
- Periodic reading of two slope inclinometers,
- Slope stability analyses,
- Geotechnical consulting with Gagnon Engineering, H.B. Fleming and Landry/French Construction relative to slope stabilization options, and
- Preparation of this report.

1.2 Site and Proposed Construction

We understand a new building with associated paved areas is currently under construction at the site. Based on information provided on civil drawings, we understand that prior to the start of construction, the westerly portion of the L-shaped lot was relatively level at about elevation 40 feet (project datum) and the easterly portion sloped upward from about elevation 42 feet at Newbury Street to elevation 47 feet at the northerly property line. A concrete retaining wall exists along the northwesterly property line supporting higher ground to the north. Other shorter concrete retaining walls exist or existed along the northeasterly property line supporting higher ground to the north. Property on the northerly side of the site is at about elevation 52 to 56 feet and slopes generally upward to the north toward Federal Street. Several multi-story housing structures exist above the retaining walls along the northerly side of the site.

We understand the proposed four story, steel-framed building will be about 210 by 90 feet in plan dimensions. The on-grade level will be stepped from about elevation 40 to 44 feet (project datum) with residential units along Newbury Street and paved parking and mechanical space behind and partially underneath the second floor. We understand a tapered cut varying from about 2 to 6 feet is needed for the easterly and northerly portion of the site to achieve proposed grades; deeper excavations are needed to construct foundations and utilities.

We understand construction began in the fall of 2014 which has included installation of aggregate piers and grouted columns beneath foundation elements, construction of several interior column foundations and a recently constructed retaining wall located along the northwesterly site boundary.



Based on information provided by Landry/French Construction and other members of the construction team, we understand during removal of the sheetpile shoring installed to construct the retaining wall along northwesterly site boundary, slope movement was observed generally between column lines 12 and 20.5 extending onto three adjacent properties located on the north-northwesterly side of the site and within about 25 feet of the recently constructed retaining wall. We understand the recently constructed retaining wall. We understand the recently constructed retaining wall. We understand the area of the observed slope movement. Results of H.B.Fleming's survey monitoring of the affected retaining wall are attached in Appendix A.

Proposed and existing site features are shown on the "Exploration Location Plan" attached as Sheet 1.

2.0 EXPLORATION AND TESTING

2.1 Explorations

Two test borings (B-201 and B-202) were made at the site on April 17 and 18, 2015 by Great Works Test Boring, Inc. of Rollinsford, New Hampshire working under subcontract to S. W. Cole Engineering, Inc. (S.W.COLE). The exploration locations were selected and established in the field by S.W.COLE using measurements from existing site features. The approximate exploration locations are shown on the "Exploration Location Plan" attached as Sheet 1. Logs of the test borings are attached as Sheet 2 through 5. A key to the notes and symbols used on the logs is attached as Sheet 6.

Slope inclinometers were installed in borings B-201 and B-202. Graphical results of inclinometer readings to-date are attached in Appendix A.

2.2 Testing

The test borings were drilled using a combination of solid stem auger and cased washboring techniques. The soils were generally sampled at 5-foot intervals using a split spoon sampler and Standard Penetration Testing (SPT) techniques. Shelby tube sampling and in-situ Vane Shear Testing (VST) was performed where softer silty clay soils were encountered. SPT blow counts and VST results are shown on the logs.



Soil samples obtained from the explorations were returned to our laboratory for further classification and testing. Shelby tube samples are being held in our laboratory for additional geotechnical testing as may be needed.

3.0 SITE AND SUBSURFACE CONDITIONS

3.1 Surficial

The site is open and currently under construction. A 7 to 9 foot high reinforced concrete retaining wall supported on "improved" soil was recently cast along the northwesterly property line within the slope movement area generally between building lines 12 to 20.5. A portion of the temporary sheetpile shoring wall remains in-place on the downslope side of the affected new retaining wall. Other higher and shorter retaining walls were recently cast outside the apparent slope movement area. Several new interior column and perimeter wall foundations have been installed across the site. The site has been cut and generally backfilled to within about 1 foot of finished grade over the western portion. Foundations have been installed and mostly backfilled generally south of building line A and west of building line 12.

Tension cracks were observed upslope of the affect new retaining wall. The tension cracks form an apparent arc-shaped head scarp that intersects the deck posts of 38 and 40 Federal Street, the raised patio of 36 Federal Street and the foundation of 48 Hancock Street. The ground is visibly slumped, fence posts displaced and the foundation of 48 Hancock Street visibly displaced below the head scarp. The approximate location of the head scarp is illustrated on Sheet 1.

3.2 Soil and Bedrock

Test borings B-201 and B-202 were made within the area of apparent slope movement. The test borings encountered a soils profile generally consisting of urban fills overlying glaciomarine deposits (sand, silt and clay) overlying sands overlying glacial till overlying refusal surfaces (probable bedrock) at depths of about 39 and 41 feet.

The glaciomarine soils consisted of silty fine sand with silty clay seams overlying relatively soft silty clay with fine sand seams. The silty clay was encountered at a depth of about 7 feet and was about 16 and 17 feet thick. In-situ vane shear tests in the silty clay indicated virgin shear strengths of 470 to 620 psf and remolded shear strengths of 40 to 80 psf.



3.3 Groundwater

The soils encountered at the test borings were moist from the ground surface becoming saturated at a depth of about 5 feet. Groundwater likely becomes perched on the relatively impervious silty clay encountered in the test borings. Long-term groundwater information was not obtained. It should be anticipated that groundwater levels will fluctuate, particularly in response to snowmelt, precipitation and changes in site use.

4.0 EVALUATION AND RECOMMENDATIONS

4.1 General Findings

Based on the available information and our experience, we offer the following:

- The terrain, proposed grade changes, retaining walls and subsurface conditions warrant the evaluation of global stability for temporary excavations, as well as permanent retaining walls and slopes.
- The surficial presence of tension cracks, slumped ground, cracked foundations and displaced fence posts indicate ground movement has occurred.
- The site is underlain by glaciomarine deposits that are sensitive to strength loss when disturbed.
- The installation of ungrouted, vibro-stone column "ground improvement", in our opinion, likely remolded the glaciomarine clays resulting in reduced strength adversely impacting both bearing capacity and global slope stability.
- Survey monitoring data of the new retaining wall indicates that it began to settle at a pronounced rate shortly after removal of the front (downslope) sheetpiles commenced.
- The slope inclinometer readings to-date do not indicate adverse movement of ground at depth in the area downslope of the affected retaining wall, suggesting the remaining front sheetpiles and unexcavated earth immediately downslope are helping to counteract a broader global slope failure.

Based on the findings and our global stability analyses, it is our opinion that installation of permanent global stability measures and underpinning of affected foundations are necessary to adequately support the new construction, as well as protect adjacent property and public safety.



4.2 Global Stability

We employed SLOPE/W to model the affected slope movement area and estimate the factor of safety against global failure. In summary, we estimate the overall factor of safety at the "stop-work" condition on April 10, 2015 is below the typical 1.5 threshold for temporary stability supporting buildings. The factor of safety against global failure had the remaining front sheetpiles been removed and remaining earth been excavated, the "aspermitted" condition, is estimated below 1.0 which could have resulted in a catastrophic failure encompassing adjacent properties around the ground failure envelope.

Working with Gagnon Engineering and H.B.Fleming, we analyzed several options to stabilize the slope, while attempting to gain benefit to underpin the affected retaining wall and integral column footing. Our analysis included brainstorming sessions with the project construction team and designers, as well as analyses to develop a recommended construction sequence. We also analyzed for seismic loading associated with the peak ground acceleration estimated by the United States Geological Survey (USGS).

A tabulated summary of global stability models and factors of safety, as well as graphical outputs are attached as Appendix B.

4.3 Slope Stabilization

Based on the findings and our global stability analysis, we recommend installation of carefully sequenced slope stabilization measures that are closely monitored during construction to include:

Overall Stabilization Sequence (recommended)

- 1. Installation of a buttress fill downslope of the affected slope area,
- 2. Reinstallation of the front (downslope side of retaining wall) sheetpiles driven to about 1-foot below grade and permanently in contact with the retaining wall footing between building lines 12 to 20,
- 3. Installation of Option 1 or Option 2 Slope Stabilization, as presented herein
- 4. Remove the buttress fill,
- 5. Underpin affected building footings, as deemed necessary by engineer-of-record,
- 6. Underpin and repair adjacent properties, as deemed necessary by others.



4.3.1 Option 1 – Double Sheetpile Walls

This option installs sheetpiles in front and behind the new site retaining wall, as well as behind a basement wall to be cast between building lines 20 to 21, including:

Option 1 Sequence (recommended)

- Steps 1 and 2 of the Overall Stabilization Sequence
- Splice and extend front (PZ-22) sheetpiles to bedrock
- Install new rear (SCZ-14) sheetpiles driven to bedrock and permanently in contact with the retaining wall footing between building lines 12 to 21,
- Cut weepholes in the rear sheetpiles about 1-foot above the retaining wall foundation drain invert,
- Underpinning the retaining wall as necessary to support the modified loads, as deemed necessary by the engineer-of-record,
- Steps 4, 5 and 6 of the Overall Stabilization Sequence

Global stability analyses for each step are summarized in Appendix B. A sketch plan of Option 1 is attached in Appendix C.

4.3.2 Option 2 – Pile Supported Retaining Wall

This option entails installation of driven H-piles to support the site retaining wall, including:

Option 2 Sequence (recommended)

- Steps 1 and 2 of the Overall Stabilization Sequence;
- Drive new HP 10 x 42 plumb piles through the existing retaining wall footing
- Drive new HP 10 x 42 battered piles in-front of the existing retaining wall footing;
- Cast a new pile cap over the existing retaining wall footing providing structural connection between the new H-piles, front sheetpiles and existing retaining wall;
- Install new rear (SCZ-14) sheetpiles driven to bedrock and permanently in contact with the retaining wall footing between building lines 20 to 21;
- Cut weepholes in the rear sheetpiles about 1-foot above the retaining wall foundation drain invert,
- Steps 4, 5 and 6 of the Overall Stabilization Sequence



Global stability analyses for each step are summarized in Appendix B. A sketch plan of Option 2 is attached in Appendix C.

5.0 CLOSURE

It has been a pleasure to be of assistance to you with this phase of your project. We look forward to working with you during the installation of slope stabilization and underpinning measures.

Sincerely,

S. W. Cole Engineering, Inc.

Michael A. St. Pierre, P.E. Geotechnical Engineer

Timothy J. Boyce, P.E. Senior Geotechnical Engineer

MAS/TJB:tjb/pfk

Attachment A Limitations

This report has been prepared for the exclusive use of Landry/French Construction for specific application to the Evaluation of Apparent Slope Movement of the Seaport Lofts at 113 Newbury Street in Portland, Maine. S. W. Cole Engineering, Inc. (S.W.COLE) has endeavored to conduct our services in accordance with generally accepted soil and geotechnical engineering practices. No warranty, expressed or implied, is made.


The soil profiles described in the report are intended to convey general trends in subsurface conditions. The boundaries between strata are approximate and are based upon interpretation of exploration data and samples.

The analyses performed during this investigation and recommendations presented in this report are based in part upon the data obtained from subsurface explorations made at the site. Variations in subsurface conditions may occur between explorations and may not become evident until construction. If variations in subsurface conditions become evident after submission of this report, it will be necessary to evaluate their nature and to review the recommendations of this report.

Observations have been made during exploration work to assess site groundwater levels. Fluctuations in water levels will occur due to variations in rainfall, temperature, and other factors.

S.W.COLE's scope of services has not included the investigation, detection, or prevention of any Biological Pollutants at the project site or in any existing or proposed structure at the site. The term "Biological Pollutants" includes, but is not limited to, molds, fungi, spores, bacteria, and viruses, and the byproducts of any such biological organisms.

Recommendations contained in this report are based substantially upon information provided by others regarding the proposed project. In the event that any changes are made in the design, nature, or location of the proposed project, S.W.COLE should review such changes as they relate to analyses associated with this report. Recommendations contained in this report shall not be considered valid unless the changes are reviewed by S.W.COLE.



M — W — ____ +50.46 50.26 ++++49.68 FW GAS ORDINATI WITH UNITIL 48.36 AVING) -+++ 48.74 49.6 49.52 Ш TRE S HANCOCK 1446.98 47.56 |/ + 47.31 + / 46.92 ¥#146.34 46.20 + 45.62 CB WITH NEW PLUG AND ABANDON 44,76 45.34 EXIST. OUTFALL PIPE, ~ | | MODIFY OPENING FOR NEW 12"SD INV., OUT=40.24 \underline{N} 00 -15"SD-GV 0+|00 ____ \sim

+-+-+

 \bigcirc

__i___

LEGEND:


- APPROXIMATE BORING LOCATION

NOTES:

 $\sim \sim$

- 1. EXPLORATION LOCATION PLAN WAS PREPARED FROM THE FOLLOWING PLANS: A SCALE PLAN OF THE SITE ENTITLED "FOUNDATION PLAN," PREPARED BY JSN ASSOCIATES, INC., DATED 12/17/2014; A 1"=10' SCALE PLAN OF THE SITE ENTITLED "GRADING AND UTILITY PLAN," PREPARED BY SEBAGO TECHNICS, DATED 7/16/2013, REVISED 12/31/2014.
- 2. THE BORINGS AND APPROXIMATE HEAD SCARP WERE LOCATED IN THE FIELD BY TAPED MEASUREMENTS FROM EXISTING SITE FEATURES.
- 3. THIS PLAN SHOULD BE USED IN CONJUNCTION WITH THE ASSOCIATED S. W. COLE ENGINEERING, INC. GEOTECHNICAL REPORT.
- 4. THE PURPOSE OF THIS PLAN IS ONLY TO DEPICT THE LOCATION OF THE EXPLORATIONS IN RELATION TO THE EXISTING CONDITIONS AND PROPOSED CONSTRUCTION AND IS NOT TO BE USED FOR CONSTRUCTION.







HW

SS

PROJECT / CLIENT: SEAPORT LOFTS / LANDRY FRENCH CONSTRUCTION

GREAT WORKS TEST BORINGS

113 NEWBURY STREET, PORTLAND, MAINE

4"

1 3/8"

SIZE I.D. HAMMER WT. HAMMER FALL

140 LBS

140 LBS

BORING LOG

DRILLER: JEFF LEE

30"

30"

BORING NO.:	B-201
SHEET:	1 OF 2
PROJECT NO .:	14-1366.2
DATE START:	4/17/2015
DATE FINISH:	4/18/2015
ELEVATION:	46' +/-
SWC REP.:	M. ST. PIERRE

WATER LEVEL INFORMATION SOILS SATURATED BELOW 5'

SAMPLER: CORE BARREL:

CASING:

LOCATION: DRILLING CO. :

CASING BLOWS		SAN	/IPLE		SAMF	PLER BL	LOWS P	PER 6"	DEPTH	STRATA & TEST DATA
PER FOOT	NO.	PEN.	REC.	DEPTH @ BOT	0-6	6-12	12-18	18-24		
SSA									1.0'	BROWN GRAVELLY SAND, TRACE SILT, OCCASIONAL COBBLES (FILL)
									2.0'	BLACK SILTY SAND WITH ASH AND CONSTRUCTION DEBRIS (FILL)
									-	BROWN SILTY FINE SAND
									4.0'	
▼										GRAY SILTY FINE SAND WITH OCCASIONAL CLAYEY SILT SEAMS
PUSH	1D	24"	24"	7.0'	2	1	1	1	7.0'	VERVIOOSE
	1D	24	24	7.0	2	1	1	1	7.0	~VERY LOOSE~
									-	
	1V	9"	-	10.8'	3.5"x	7" TAPI	ERED \	ANE	1	Sv = 0.47 / 0.06 ksf ~VERY SOFT~
	1V'	9"	-	11.5'	3.5"x	7" TAPI	ERED \	ANE		Sv = 0.49 / 0.06 ksf
									-	
									4	GRAY SILTY CLAY
										WITH OCCASIONAL FINE SAND SEAMS
	1C	24"	20"	17.0'		STON S		ED	-	
	2V	24 9"	- 20	17.0' 17.8'		7" TAP				Sv = 0.57 / 0.10 ksf ~SOFT~
	2V'	9"	-	18.5		7" TAP				Sv = 0.57 / 0.16 ksf
					010 /					
	3V	9"	-	20.8'	3.5"x	3.5"x7" TAPERED VANE			Sv = 0.91 / 0.10 ksf PROBABLE SAND SEAM	
	3V'	9"	-	21.5'	3.5"x	3.5"x7" TAPERED VANE			Sv = 0.62 / 0.06 ksf ~MEDIUM~	
+									23.0'	
30										
35										GRAY SILTY SAND, SOME GRAVEL
60	00	0.4"	4.0"	07.0	00	40	0	0		
55 30	2D	24"	18"	27.0'	26	16	3	9		~MEDIUM DENSE~
30									-	
										BECOMES GRAVELLY WITH SUBANGULAR TO ANGULAR GRAVEL
50-60										(PROBABLE GRAVELS FROM VIBRO STONE COLUMN INSTALLATION)
	3D	24"	8"	32.0'	18	18	13	8		~DENSE~
▼									33.0'	
30										
25										
35	40	0.4"	40"	07.01	^	0	0	40	-	GRAY SILTY SAND, SOME GRAVEL (GLACIAL TILL)
45 50	4D	24"	10"	37.0'	3	8	8	10		~MEDIUM DENSE~
100									39.0'	
										BEDROCK - ADVANCED BY ROLLER CONE FROM 39 TO 42.9'
CAMP	-0.	1	1	sou 0	1 4 0 0 1			1		
SAMPLI D = SPL				SUILC	LASSI	FIED B	r:		REMAR	RKS: CONTINUED
C = 2" S					DRI	LLER -	VISUAI	LLY		STRATIFICATION LINES REPRESENT THE
S = 3" S				Х						APPROXIMATE BOUNDARY BETWEEN SOIL TYPES
U = 3.5"	SHELI	BY TUE	BE		LAB	ORATO	ORY TE	ST		AND THE TRANSITION MAY BE GRADUAL. BORING NO.: B-201



HW

SS

PROJECT / CLIENT: SEAPORT LOFTS / LANDRY FRENCH CONSTRUCTION

GREAT WORKS TEST BORINGS

113 NEWBURY STREET, PORTLAND, MAINE

4"

1 3/8"

SIZE I.D. HAMMER WT. HAMMER FALL

140 LBS

140 LBS

BORING LOG

DRILLER: JEFF LEE

30"

30"

BORING NO.:	B-201
SHEET:	2 OF 2
PROJECT NO .:	14-1366.2
DATE START:	4/17/2015
DATE FINISH:	4/18/2015
ELEVATION:	46' +/-
SWC REP.:	M. ST. PIERRE

WATER LEVEL	INFORMATION

SOILS SATURATED BELOW 5'

SAMPLER: CORE BARREL:

CASING:

LOCATION:

DRILLING CO. :

CASING BLOWS PER								DEPTH	STRATA & TEST DATA	
FOOT	NO.	PEN.	REC.	@ BOT	0-6	6-12	12-18	18-24		
									-	BEDROCK
										ADVANCED BY ROLLER CONE FROM 39 TO 42.9'
										BOTTOM OF EXPLORATION AT 42.9'
									-	
									-	
									-	
									-	
									-	
									-	
									-	
SAMPL	ES			SOIL C			۲·		REMAR	K8.
D = SPL		DON					••			\frown
C = 2" S						LLER -				STRATIFICATION LINES REPRESENT THE (3)
S = 3" S U = 3.5'				X		L TECH				APPROXIMATE BOUNDARY BETWEEN SOIL TYPES AND THE TRANSITION MAY BE GRADUAL. BORING NO.: B-201
			-	1						



HW

SS

PROJECT / CLIENT: SEAPORT LOFTS / LANDRY FRENCH CONSTRUCTION

GREAT WORKS TEST BORINGS

113 NEWBURY STREET, PORTLAND, MAINE

4"

1 3/8"

SIZE I.D. HAMMER WT. HAMMER FALL

140 LBS

140 LBS

BORING LOG

DRILLER: JEFF LEE

30"

30"

BORING NO .:	B-202
SHEET:	1 OF 2
PROJECT NO .:	14-1366.2
DATE START:	4/17/2015
DATE FINISH:	4/17/2015
ELEVATION:	45' +/-
SWC REP.:	M. ST. PIERRE

WATER LEVEL INFORMATION SOILS SATURATED BELOW 5'

SAMPLER: CORE BARREL:

CASING:

LOCATION:

DRILLING CO. :

	SING DWS		SAN	IPLE		SAMF	PLER BL	LOWS F	PER 6"	DEPTH	STRATA & TEST DATA
	ER OOT	NO.	PEN.	REC.	DEPTH @ BOT	0-6	6-12	12-18	18-24	DEFIN	
_	SA									1.0'	BROWN GRAVELLY SAND, TRACE SILT, OCCASIONAL COBBLES (FILL)
										2.0'	BLACK SILTY SAND WITH ASH AND CONSTRUCTION DEBRIS (FILL)
											BROWN SILTY FINE SAND
										4.0'	
-	7										GRAY SILTY FINE SAND WITH OCCASIONAL CLAYEY SILT SEAMS
PU	ISH		o ("	o ("				-			
		1D	24"	24"	7.0'	1	1	2	1	7.0'	~VERY LOOSE~
										-	GRAY SILTY CLAY
											WITH OCCASIONAL FINE SAND SEAMS
_		1V	9"	-	10.8'	3 5"v	7" TAP	ERED		1	Sv = 0.52 / 0.04 ksf ~SOFT~
		1V'	9"	-	11.5			ERED			Sv = 0.57 / 0.03 ksf
		IV	9	-	11.5	3.5 X		ERED		-	SV = 0.57 / 0.05 KSI
										1	
										-	
\vdash										1	SAND SEAMS/LAYERS BECOME FREQUENT BELOW ±15'
		1C	24"	20"	17.0'	PI	STON S	SAMPL	ER		
		2V	9"	-	17.8			ERED			Sv = 0.98 / 0.08 ksf PROBABLE SAND SEAM
		2V'	0"	-		0.0 /					NO PENETRATION
		3V	9"	-	20.8'	3.5"x	7" TAP	ERED	ANE	1	Sv = 0.88 / 0.08 ksf PROBABLE SAND SEAM
		3V'	9"	-	21.5		3.5"x7" TAPERED VANE		1	Sv = 0.59 / 0.08 ksf	
			-			2.0 /					~SOFT~
										24.0'	
25	, -35										
										1	GRAY SILTY SAND, SOME GRAVEL
		2D	24"	19"	27.0'	1	1	3	3	1	~LOOSE~
										1	
										1	
	,									30.0'	
35	-45										
		3D	24"	8"	32.0'	7	9	9	12	1	~MEDIUM DENSE~
]	
											GRAY SAND, SOME GRAVEL, TRACE SILT
										J	
]	
		4D	24"	6"	37.0'	8	9	4	4		~MEDIUM DENSE~
										39.0'	
6	60										GRAY GRAVELLY SAND, SOME SILT (GLACIAL TILL)
SAL	MPL	=S·			SOIL C			<u>۲</u> .		REMAR	RKS: CONTINUED
		_3. .IT SPC	ON		5012 0	2,000		•••			
			TUBE			DRI	LLER -	VISUAI	LLY		STRATIFICATION LINES REPRESENT THE (4)
			TUBE		Х			I VISI			APPROXIMATE BOUNDARY BETWEEN SOIL TYPES
			BY TUB					DRY TE			AND THE TRANSITION MAY BE GRADUAL. BORING NO.: B-202
									BURING NU.: B-202		



HW

SS

PROJECT / CLIENT: SEAPORT LOFTS / LANDRY FRENCH CONSTRUCTION

GREAT WORKS TEST BORINGS

113 NEWBURY STREET, PORTLAND, MAINE

4"

1 3/8"

SIZE I.D. HAMMER WT. HAMMER FALL

140 LBS

140 LBS

BORING LOG

DRILLER: JEFF LEE

30"

30"

BORING NO.:	B-202
SHEET:	2 OF 2
PROJECT NO.:	14-1366.2
DATE START:	4/17/2015
DATE FINISH:	4/17/2015
ELEVATION:	45' +/-
SWC REP.:	M. ST. PIERRE

WATER LEVEL INFORMATION

SOILS SATURATED BELOW 5'

SAMPLER: CORE BARREL:

CASING:

LOCATION:

DRILLING CO. :

CASING BLOWS		SAN	/IPLE		SAM	PLER BL	.OWS P	'ER 6"	DEDTU	STRATA & TEST RATA
PER FOOT	NO.	PEN.	REC.	DEPTH @ BOT	0-6	6-12	12-18	18-24	DEPTH	STRATA & TEST DATA
110	5D	11"	7"	40.9'	12	50/5"			40.9'	GRAY GRAVELLY SAND, SOME SILT (GLACIAL TILL)
										ADVANCED BY ROLLER CONE FROM 40.9 TO 45.9
									45.9'	
									10.0	
										BOTTOM OF EXPLORATION AT 45.9'
									-	
	-								-	
									-	
									-	
	-									
									-	
									-	
							-			
SAMPLES: SOIL CLASSIFIED BY: D = SPLIT SPOON					FIED B	/ :		REMAR	KS:	
						LLER -	//101141	IV		STRATIFICATION LINES REPRESENT THE 5
C = 2" S S = 3" S				Х						APPROXIMATE BOUNDARY BETWEEN SOIL TYPES
S = 3" SHELBY TUBE U = 3.5" SHELBY TUBE		X SOIL TECH VISUALLY LABORATORY TEST						AND THE TRANSITION MAY BE GRADUAL. BORING NO.: B-202		



• Geotechnical Engineering • Field & Lab Testing • Scientific & Environmental Consulting

KEY TO THE NOTES & SYMBOLS Test Boring and Test Pit Explorations

All stratification lines represent the approximate boundary between soil types and the transition may be gradual.

Key to Symbols Used:

- w water content, percent (dry weight basis)
- qu unconfined compressive strength, kips/sq. ft. laboratory test
- S_v field vane shear strength, kips/sq. ft.
- L_v lab vane shear strength, kips/sq. ft.
- q_p unconfined compressive strength, kips/sq. ft. pocket penetrometer test
- O organic content, percent (dry weight basis)
- W_L liquid limit Atterberg test
- W_P plastic limit Atterberg test
- WOH advance by weight of hammer
- WOM advance by weight of man
- WOR advance by weight of rods
- HYD advance by force of hydraulic piston on drill
- RQD Rock Quality Designator an index of the quality of a rock mass.
- γ_T total soil weight
- $\gamma_{\rm B}$ buoyant soil weight

Description of Proportions:

Description of Stratified Soils


		Parting:	0 to 1/16" thickness
Trace:	0 to 5%	Seam:	1/16" to 1/2" thickness
Some:	5 to 12%	Layer:	½" to 12" thickness
"Y"	12 to 35%	Varved:	Alternating seams or layers
And	35+%	Occasional:	one or less per foot of thickness
With	Undifferentiated	Frequent:	more than one per foot of thickness

REFUSAL: <u>Test Boring Explorations</u> - Refusal depth indicates that depth at which, in the drill foreman's opinion, sufficient resistance to the advance of the casing, auger, probe rod or sampler was encountered to render further advance impossible or impracticable by the procedures and equipment being used.

REFUSAL: <u>Test Pit Explorations</u> - Refusal depth indicates that depth at which sufficient resistance to the advance of the backhoe bucket was encountered to render further advance impossible or impracticable by the procedures and equipment being used.

Although refusal may indicate the encountering of the bedrock surface, it may indicate the striking of large cobbles, boulders, very dense or cemented soil, or other buried natural or man-made objects or it may indicate the encountering of a harder zone after penetrating a considerable depth through a weathered or disintegrated zone of the bedrock.

APPENDIX A



H.B. Fleming, Inc. Survey Monitoring of New Permenant Concrete Retaining Wall Seaport Lofts, Portland, Maine

MONDAY APRIL 27TH, 2015


negitive (-) indicates settlement


				ELEVATION			-					Delta from		ELEVATION			Delta fro
		ELEVATION		(HBF		Total			ELEVATION		Total	Previous,		(HBF		Total	Previou
		(HBF Assumed		Assumed	DELTA-Units	Settlement	••		(HBF Assumed	DELTA-Units	Settlement	after sheet		Assumed	DELTA-Units	Settlement	after she
	Date of Initial	Elevation		Elevation	in Decimal	to Date	Delta from		Elevation	in Decimal	to Date	extraction		Elevation	in Decimal	to Date	extractio
nt #	Reading	Datum)	DATE	Datum)	Feet	(INCHES)	Previous	DATE	Datum)	Feet	(INCHES)	(in)	DATE	Datum)	Feet	(INCHES)	(in)
400	4/3/2015	104.47	4/8/2015	104.47	0.00	-0.03	-0.03	4/10/2015	104.34	-0.13	-1.54	-1.51	4/17/2015	104.33	-0.14	-1.65	-0
401	4/3/2015	102.23	4/8/2015	102.20	-0.03	-0.36	-0.36	4/10/2015	102.07	-0.16	-1.90	-1.54	4/17/2015	102.03	-0.20	-2.42	-0
402	4/3/2015	102.23	4/8/2015	102.23	0.00	0.00	0.00	4/10/2015	102.13	-0.10	-1.25	-1.25	4/17/2015	102.08	-0.15	-1.83	-0
403	4/3/2015	102.29	4/8/2015	102.31	0.02	0.21	0.21	4/10/2015	102.17	-0.12	-1.43	-1.22	4/17/2015	102.13	-0.16	-1.92	-0
(40.4	2' Civil Elevatio	n = 100'-00" Stri nll Elevation = 12		••										ELEVATION (HBF Assumed Flevation	DELTA-Units		Previo after sh
(40.4 <u>Prop</u> <u>4/3/2</u> #400 #401 #402	2' Civil Elevatio osed Top of Wo 2015 = HBF Elevatio = HBF Elevatio = HBF Elevatio	n = 100'-00" Stra all Elevation = 12 n = 104.47' - 51. n = 102.23' - 51. n = 102.23' - 51.	uctural Elevation <u>10'-0''</u> 79' = 52.68' (Civi 79' = 50.44' (Civi 79' = 50.44' (Civi	n, Delta 59.58' il Elevation) + il Elevation) + il Elevation) +) 59.58' = 112.2 59.58' = 110.0 59.58' = 110.0)2' (Structural)2' (Structural	Elevation) Elevation)					400 401	DATE 4/27/2015 4/27/2015	(HBF Assumed Elevation Datum) 104.32 102.02	in Decimal Feet -0.15 -0.21	Settlement to Date (INCHES) -1.77 -2.54	Delta fr Previou after sh extracti (in) -(
(40.4 <u>Prop</u> <u>4/3/2</u> #400 #401 #402 #403	2' Civil Elevatio osed Top of Wo 2015 = HBF Elevatio = HBF Elevatio = HBF Elevatio	n = 100'-00" Stra all Elevation = 12 n = 104.47' - 51. n = 102.23' - 51.	uctural Elevation <u>10'-0''</u> 79' = 52.68' (Civi 79' = 50.44' (Civi 79' = 50.44' (Civi	n, Delta 59.58' il Elevation) + il Elevation) + il Elevation) +) 59.58' = 112.2 59.58' = 110.0 59.58' = 110.0)2' (Structural)2' (Structural	Elevation) Elevation)		:				4/27/2015 4/27/2015 4/27/2015	(HBF Assumed Elevation Datum) 104.32 102.02 102.07	in Decimal Feet -0.15 -0.21	Settlement to Date (INCHES) -1.77 -2.54 -1.95	Previou after sh extracti (in)


HORIZONTAL MONITORING


.

1							delta north	delta east				delta north	delta north	delta east	delta east
Pnt #	DATE	NORTHING	EASTING	DATE	NORTHING	EASTING	(ft)	(ft)	DATE	NORTHING	EASTING	(ft)	(in)	(ft)	(in)
400	4/3/2015	5151.92	4837.82	4/8/2015	5151.97	4837.83	0.05	0.01	4/10/2015	5151.92	4837.89	0.00	0.04	0.07	0.8:
401	4/3/2015	5151.72	4855.55	4/8/2015	5151.77	4855.56	0.05	0.01	4/10/2015	5151.75	4855.59	0.03	0.38	0.04	0.4
402	4/3/2015	5133.55	4886.97	4/8/2015	5133.60	4886.96	0.04	-0.01	4/10/2015	5133.61	4886.98	0.05	0.61	0.01	0.1
403	4/3/2015	5133.20	4903.12	4/8/2015	5133.22	4 <u>90</u> 3.12	0.02	0.00	4/10/2015	5133.27	4903. <u>1</u> 5	0.08	0.91	0.03	0.4
				· · · · · ·				400	4/17/2015	5151.9352	4837.9059	0.02	0.20	0.09	1.04
								401	4/17/2015	5151.7346	4855.5951	0.02	0.23	0.04	0.49
						1 - N 2		402	4/17/2015	5133.628	4886.9665	0.07	0.88	0.00	0.0
						5) 5	5	403	4/17/2015	5133.2839	4903.1472	0.09	1.03	0.03	0.3
							-	400	4/27/2015	5151.9044	4837.9058	-0.01	-0.17	0.09	1.04
							1	401	4/27/2015	5151.7373	4855.6019	0.02	0.26	0.05	0.57
								402	4/27/2015	5133.6127	4886.9768	0.06	0.70	0.01	0.13
						¥		403	4/27/2015	5133.2811	4903.1476	0.08	0.99	0.03	0.33









LOFTS B-202, B-Axis

APPENDIX B



SUMMARY OF GLOBAL STABILITY MODEL OUTPUT

PROJECT: PROPOSED SEAPORT LOFTS


CLIENT: LANDRY/FRENCH CONSTRUCTION

LOCATION: 113 NEWBURY STREET, PORTLAND, MAINE

	FACTOR OF SAFETY AGAINST GLOBAL FAILURE									
		B-201			B-202	20.2-21 line				
DESCRIPTION	STATIC	CV	SEISMIC	STATIC	CV	SEISMIC	Static	Seismic		
Stop Work Condition - Overall	1.31	-	1.02	1.36	-	0.93	-	-		
Stop Work Condition - Through Tension Crack	2.45	-	1.79	3.16	-	2.10	-	-		
As-Permitted	0.69	-	0.60	0.84	-	0.72	-	-		
As-Permitted - Without Ground Improvement	0.80	-	0.69	0.94	-	0.79	-	-		
Repair Stage 1 - Place Buttress Fill	1.78	1.56	1.36	-	-	-	-	-		
Repair Stage 2 - Remove Fill between Retaining Wall & PZ-22 Sheets	1.76	1.55	1.35	-	-	-	-	-		
Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock	2.86	2.50	2.19	-	-	-	-	-		
Repair Stage 4 - Install SCZ-14 Sheetpiles	2.86	2.50	2.19	-	-	-	-	-		
Repair Final - SCZ-14 and PZ-22 Sheetpiles to Bedrock	2.02	-	1.63	2.37	-	1.80	-	-		
Repair Stage 3 - Install PZ-22 Sheets (±23-foot lenghts)	2.25	1.98	1.73	-	-	-	-	-		
Repair Stage 4 - Install HP10x42 Plumb and Batter Piles	6.00	4.50	3.50	-	-	-	-	-		
Repair Final - Short PZ-22 Sheetpiles with HP10x42's to Bedrock	2.54	-	1.86	2.68	-	1.88	-	-		
Repair Final - SCZ-14 Sheetpile to Bedrock	-	-	-	-	-	-	2.55	1.84		
	Stop Work Condition - Overall Stop Work Condition - Through Tension Crack As-Permitted As-Permitted - Without Ground Improvement Repair Stage 1 - Place Buttress Fill Repair Stage 2 - Remove Fill between Retaining Wall & PZ-22 Sheets Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock Repair Stage 4 - Install SCZ-14 Sheetpiles Repair Final - SCZ-14 and PZ-22 Sheetpiles to Bedrock Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock Repair Stage 4 - Install HP10x42 Plumb and Batter Piles Repair Final - Short PZ-22 Sheetpiles with HP10x42's to Bedrock	Stop Work Condition - Overall1.31Stop Work Condition - Through Tension Crack2.45As-Permitted0.69As-Permitted - Without Ground Improvement0.80Repair Stage 1 - Place Buttress Fill1.78Repair Stage 2 - Remove Fill between Retaining Wall & PZ-22 Sheets1.76Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock2.86Repair Stage 4 - Install SCZ-14 Sheetpiles2.86Repair Final - SCZ-14 and PZ-22 Sheetpiles to Bedrock2.02Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock2.25Repair Stage 4 - Install HP10x42 Plumb and Batter Piles6.00Repair Stage 4 - Install HP10x42 Plumb and Batter Piles6.00	DESCRIPTIONB-201Stop Work Condition - Overall1.31-Stop Work Condition - Through Tension Crack2.45-As-Permitted0.69-As-Permitted - Without Ground Improvement0.80-Repair Stage 1 - Place Buttress Fill1.781.56Repair Stage 2 - Remove Fill between Retaining Wall & PZ-22 Sheets1.761.55Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock2.862.50Repair Stage 4 - Install SCZ-14 Sheetpiles2.862.50Repair Stage 3 - Install PZ-22 Sheets (±23-foot lenghts)2.251.98Repair Stage 4 - Install PZ-22 Sheets (±23-foot lenghts)2.251.98Repair Stage 4 - Install HP10x42 Plumb and Batter Piles6.004.50Repair Stage 4 - Install HP10x42 Plumb and Batter Piles6.004.50Repair Final - Short PZ-22 Sheetpiles with HP10x42's to Bedrock2.54-	DESCRIPTION STATIC CV SEISMIC Stop Work Condition - Overall 1.31 - 1.02 Stop Work Condition - Through Tension Crack 2.45 - 1.79 As-Permitted 0.69 - 0.60 As-Permitted - Without Ground Improvement 0.80 - 0.69 Repair Stage 1 - Place Buttress Fill 1.78 1.56 1.36 Repair Stage 2 - Remove Fill between Retaining Wall & PZ-22 Sheets 1.76 1.55 1.35 Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.86 2.50 2.19 Repair Stage 3 - Install SCZ-14 Sheetpiles 2.86 2.50 2.19 Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 Repair Stage 4 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 Repair Stage	DESCRIPTION STATIC CV SEISMIC STATIC Stop Work Condition - Overall 1.31 - 1.02 1.36 Stop Work Condition - Through Tension Crack 2.45 - 1.79 3.16 As-Permitted 0.69 - 0.60 0.84 As-Permitted - Without Ground Improvement 0.80 - 0.69 0.94 Repair Stage 1 - Place Buttress Fill 1.78 1.56 1.36 - Repair Stage 2 - Remove Fill between Retaining Wall & PZ-22 Sheets 1.76 1.55 1.35 - Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.86 2.50 2.19 - Repair Stage 4 - Install SCZ-14 sheetpiles 2.86 2.50 2.19 - Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 2.37 Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 2.37 Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 2.37 Repair Stage 4 - Install HP10x42 Plumb and Batter Piles	DESCRIPTION STATIC CV SEISMIC STATIC CV Stop Work Condition - Overall 1.31 - 1.02 1.36 - Stop Work Condition - Through Tension Crack 2.45 - 1.79 3.16 - As-Permitted 0.69 - 0.60 0.84 - As-Permitted - Without Ground Improvement 0.80 - 0.69 0.94 - Repair Stage 1 - Place Buttress Fill 1.78 1.56 1.36 - - Repair Stage 2 - Remove Fill between Retaining Wall & PZ-22 Sheets 1.76 1.55 1.35 - - Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.86 2.50 2.19 - - Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 2.37 - Repair Stage 3 - Install PZ-22 Sheets (±23-foot lenghts) 2.25 1.98 1.73 - - Repair Stage 4 - Install HP10x42 Plumb and Batter Piles 6.00 4.50 3.50 - - Repair Sta	DESCRIPTION STATIC CV SEISMIC STATIC CV SEISMIC Stop Work Condition - Overall 1.31 - 1.02 1.36 - 0.93 Stop Work Condition - Through Tension Crack 2.45 - 1.79 3.16 - 2.10 As-Permitted 0.69 - 0.60 0.84 - 0.72 As-Permitted - Without Ground Improvement 0.80 - 0.69 0.94 - 0.79 Repair Stage 1 - Place Buttress Fill 1.78 1.56 1.36 - - - Repair Stage 2 - Remove Fill between Retaining Wall & PZ-22 Sheets 1.76 1.55 1.35 - - - Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.86 2.50 2.19 - - - Repair Stage 3 - Install PZ-22 Sheetpiles to Bedrock 2.02 - 1.63 2.37 - 1.80 Repair Stage 3 - Install PZ-22 Sheets (±23-foot lenghts) 2.25 1.98 1.73 - - -	DESCRIPTION STATIC CV SEISMIC STATIC CV SEISMIC SEISMI		

NOTES: CV = Construction Vibration Seismic horizontal acceleration, $A_h = 0.085g$ CV horizontal acceleration, $A_h = 0.040g$ Repair Final includes 1/16-inch of pile corrosion


PROJECT NO.: 14-1366.2



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 1A: Stop Work Condition B-201 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


```
Case 1A: Stop Work Condition
B-201
Seismic (Ah = 0.085g)
```



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 1B: Stop Work Condition B-201 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 1B: Stop Work Condition B-201 Seismic (Ah = 0.085g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Saturna State S

Seaport Lofts 113 Newbury Street Portland, Maine


Case 2: As-Permitted B-201 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Saturna State S

Seaport Lofts 113 Newbury Street Portland, Maine


```
Case 2: As-Permitted
B-201
Seismic (Ah = 0.085g)
```



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 3: As-Permitted Without Ground Improvement B-201 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 3: As-Permitted Without Ground Improvement B-201 Seismic (Ah = 0.085g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 11&12. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4A: Repair Stage 1 Place Buttress Fill B-201 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 11&12. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4A: Repair Stage 1 Place Buttress Fill B-201 Construction Vibration (Ah = 0.04g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 11&12. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4A: Repair Stage 1 Place Buttress Fill B-201 Seismic (Ah = 0.085g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4B: Repair Stage 2 Remove Fill between Retaining Wall & PZ-22 Sheets B-201 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4B: Repair Stage 2 Remove Fill between Retaining Wall & PZ-22 Sheets B-201 Construction Vibration (Ah = 0.04g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock


Seaport Lofts 113 Newbury Street Portland, Maine

Case 4B: Repair Stage 2 Remove Fill between Retaining Wall & PZ-22 Sheets B-201 Seismic (Ah = 0.085g)



1. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&11. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock Seaport Lofts 113 Newbury Street Portland, Maine


Case 4C: Repair Stage 3 Install PZ-22 Sheets to Bedrock B-201 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock


Seaport Lofts 113 Newbury Street Portland, Maine

Case 4C: Repair Stage 3 Install PZ-22 Sheets to Bedrock B-201 Construction Vibration (Ah = 0.04g)



1. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&11. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock Seaport Lofts 113 Newbury Street Portland, Maine


Case 4C: Repair Stage 3 Install PZ-22 Sheets to Bedrock B-201 Seismic (Ah = 0.085g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4D: Repair Stage 4 Install SCZ-14 Sheetpiles B-201 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4D: Repair Stage 4 Install SCZ-14 Sheetpiles B-201 Construction Vibration (Ah = 0.04g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4D: Repair Stage 4 Install SCZ-14 Sheetpiles B-201 Seismic (Ah = 0.085g)



1&11. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&12. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock


Seaport Lofts 113 Newbury Street Portland, Maine

Case 5: Repair Final B-201 Static




1&11. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&12. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine




1. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&11. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock Seaport Lofts 113 Newbury Street Portland, Maine

Case 4C: Repair Stage 3 Install PZ-22 Sheets B-201 Static




1. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&11. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock Seaport Lofts 113 Newbury Street Portland, Maine

Case 4C: Repair Stage 3 Install PZ-22 Sheets B-201 Construction Vibration (Ah = 0.04g)



1. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&11. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock Seaport Lofts 113 Newbury Street Portland, Maine


Case 4C: Repair Stage 3 Install PZ-22 Sheets B-201 Seismic (Ah = 0.085g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4D: Repair Stage 4 Install Plumb and Batter Piles B-201 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4D: Repair Stage 4 Install Plumb and Batter Piles B-201 Construction Vibration (Ah = 0.040g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 4D: Repair Stage 4 Install Plumb and Batter Piles B-201 Seismic (Ah = 0.085g)



1&11. Concrete/Retaining Wall: Unit Wt = 150 pcf
2. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
10. Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 5: Repair Final B-201 Static



1&11. Concrete/Retaining Wall: Unit Wt = 150 pcf
2. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
10. Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 5: Repair Final B-201 Seismic (Ah = 0.085g)



Foundation/Retaining Wall: Unit Wt = 150 pcf
 1. Foundation/Retaining Wall: Unit Wt = 150 pcf
 2.11&12. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 10. Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 1A: Stop Work Condition B-202 Static



Foundation/Retaining Wall: Unit Wt = 150 pcf
 1. Foundation/Retaining Wall: Unit Wt = 150 pcf
 2.11&12. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 10. Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 1A: Stop Work Condition B-202 Seismic (Ah = 0.085g)



Foundation/Retaining Wall: Unit Wt = 150 pcf
 1. Foundation/Retaining Wall: Unit Wt = 150 pcf
 2.11&12. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 10. Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 1B: Stop Work Condition B-202 Static



Foundation/Retaining Wall: Unit Wt = 150 pcf
 1. Foundation/Retaining Wall: Unit Wt = 150 pcf
 2.11&12. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 10. Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 1B: Stop Work Condition B-202 Seismic (Ah = 0.085g)



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 2: As-Permitted B-202 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock


Seaport Lofts 113 Newbury Street Portland, Maine

Case 2: As-Permitted B-202 Seismic (Ah = 0.085g)




1. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&11. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5-7. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock Seaport Lofts 113 Newbury Street Portland, Maine

Case 3: As-Permitted Without Ground Improvement B-202 Static



1. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&11. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5-7. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock Seaport Lofts 113 Newbury Street Portland, Maine


Case 3: As-Permitted Without Ground Improvement B-202 Seismic (Ah = 0.085g)



1&12. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&11. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock


Seaport Lofts 113 Newbury Street Portland, Maine

Case 5: Repair Final B-202 Static



1&12. Concrete/Retaining Wall: Unit Wt = 150 pcf 2&11. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg 3&4. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg 5&6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf 7. Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf 8. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg 9. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg 10. Bedrock


Seaport Lofts 113 Newbury Street Portland, Maine



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 5: Repair Final B-202 Static



Concrete/Retaining Wall: Unit Wt = 150 pcf
 Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
 Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
 Silty Clay: Unit Wt = 105 pcf, C = 500 psf
 Remolded Silty Clay: Unit Wt = 100 pcf, C = 50 psf
 Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
 silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
 Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine


Case 5: Repair Final B-202 Seismic (Ah = 0.085g)



1&3. Concrete: Unit Wt = 150 pcf
2&4. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
5. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
7. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
8. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
9. Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine

Case 5: Repair Final 20.2-line to 21-line Static



1&3. Concrete: Unit Wt = 150 pcf
2&4. Granular Fill: Unit Wt = 130 pcf, Phi = 30 deg
5. Silty Sand: Unit Wt = 115 pcf, Phi = 28 deg
6. Silty Clay: Unit Wt = 105 pcf, C = 500 psf
7. Sand, sm gravel, tr silt: Unit Wt = 115 pcf, Phi = 28 deg
8. silty SAND, sm gravel: Unit Wt = 125 pcf, Phi = 30 deg
9. Bedrock

Seaport Lofts 113 Newbury Street Portland, Maine

Case 5: Repair Final 20.2-line to 21-line Static

APPENDIX C

