

13251 Seaport Lofts Average Grade Calculation

	Perimeter Length	Elevations	Extension
	30	39.50	1,185.00
	8	39.74	317.92
	17	40.07	681.19
	10	40.40	404.00
	17	40.73	692.41
	10	41.07	410.70
	17	41.35	702.95
	8	41.69	333.52
	8	41.74	333.92
	17	42.07	715.19
	10	42.40	424.00
	17	42.73	726.41
	10	43.07	430.70
	17	43.19	734.23
	10	43.32	433.20
	17	43.66	742.22
	33	45.43	1,499.19
	14	46.86	656.04
	29	48.13	1,395.77
	40	49.70	1,988.00
	27	42.35	1,143.45
	17	42.15	716.55
	120	41.05	4,926.00
	10	39.73	397.30
	28	39.45	1,104.60
	27	39.62	1,069.74
	39	39.62	1,545.18
	<hr/>		<hr/>
Total Perimeter (A) Length	607		
		Elevation Subtotal (B)	25,709.38
Average Grade (B/A)	42.35482702		