W1	W2
3 5/8"	6"

1. **CONT. METAL FLOOR AND CEILING RUNNER -** CHANNEL SHAPED 3 5/8" 25 MSG STEEL WITH 1 1/4" LONG LEGS FASTENERS @ 2'-0" O.C. MAX. WITHIN 1" OF ENDS
2. **STEEL STUDS -** CHANNEL SHAPED 25 MSG STEEL 3 5/8" STUDS SPACED MAX. 24" O.C. RUNT TO 2" ABOVE FINISHED CEILING (**USE 6" STUD AT W2 WALLS**)
3. **GYPSUM BOARD -** (1) LAYER 5/8" GYP. BD. EACH SIDE TO 12" ABOVE CEILING, PAPER SURFACED, APPLIED PERPENDICULAR TO FRAMING WITH 1" TYPE S STEEL SCREWS SPACED 8" O.C.. SEE NOTES FOR GYP. BD. TYPE
4. **SOUND ATTENUATION BATT -** FIBERGLASS BATT WITH UL CLASS AS TO SURFACE BURNING CHARACTERISTICS AND OR FIRE RESISTANCE REQUIRED
5. **SEALANT** - ACOUSTIC SEALANT BOTH SIDES.
6. **BLOCKING - (NOT SHOWN)** WOOD BLOCKING AS NEEDED
7. **TAPE AND COMPOUND - (NOT SHOWN)** VINYL, DRY OR PREMIXED JOINT COMPOUND, APPLIED IN TWO COATS TO JOISTS AND SCREW HEADS, PAPER TAPE, 2 IN. WIDE, EMBEDDED IN FIRST LAYER OF COMPOUND OVER ALL JOINTS.
8. **BASE -** SEE FINISH SCHEDULE
9. UNDERSIDE OF STRUCTURE
10. TOP OF STRUCTURE
11. **SOUND ATTENUATION BATT -** FIBERGLASS BATT WITH UL CLASS AS TO SURFACE BURNING CHARACTERISTICS AND OR FIRE RESISTANCE REQUIRED-

W3	W4
3 5/8"	6"

1. **CONT. METAL FLOOR AND CEILING RUNNER -** CHANNEL SHAPED 3 5/8" 25 MSG STEEL WITH 1 1/4" LONG LEGS FASTENERS @ 2'-0" O.C. MAX. WITHIN 1" OF ENDS
2. **STEEL STUDS -** CHANNEL SHAPED 25 MSG STEEL 3 5/8" STUDS SPACED MAX. 24" O.C. RUNT TO 2" ABOVE FINISHED CEILING (**USE 6" STUD AT W2 WALLS**)
3. **GYPSUM BOARD -** (1) LAYER 5/8" GYP. BD. EACH SIDE TO 12" ABOVE CEILING, PAPER SURFACED, APPLIED PERPENDICULAR TO FRAMING WITH 1" TYPE S STEEL SCREWS SPACED 8" O.C.. SEE NOTES FOR GYP. BD. TYPE
4. **SOUND ATTENUATION BATT -** FIBERGLASS BATT WITH UL CLASS AS TO SURFACE BURNING CHARACTERISTICS AND OR FIRE RESISTANCE REQUIRED
5. **SEALANT** - ACOUSTIC SEALANT BOTH SIDES.
6. **BLOCKING - (NOT SHOWN)** WOOD BLOCKING AS NEEDED
7. **TAPE AND COMPOUND - (NOT SHOWN)** VINYL, DRY OR PREMIXED JOINT COMPOUND, APPLIED IN TWO COATS TO JOISTS AND SCREW HEADS, PAPER TAPE, 2 IN. WIDE, EMBEDDED IN FIRST LAYER OF COMPOUND OVER ALL JOINTS.
8. **BASE -** SEE FINISH SCHEDULE
9. UNDERSIDE OF STRUCTURE
10. TOP OF STRUCTURE
11. **SOUND ATTENUATION BATT -** FIBERGLASS BATT WITH UL CLASS AS TO SURFACE BURNING CHARACTERISTICS AND OR FIRE RESISTANCE REQUIRED-
12. **FRP PANEL**-ATTACH PER MANUFACTURERS RECOMMENDATION

WALL TYPES

3 ADA WC BACK ELEVATION
1/2" = 1'-0"

4 TYPICAL ADA ELEVATION
1/2" = 1'-0"

5 ADA LAV ELEVATION
1/2" = 1'-0"

6 ACCESSIBLE SEATING SKETCH
1" = 1'-0"

7 ACCESSIBLE BAR SKETCH
1" = 1'-0"

GENERAL NOTE: 5% OF BAR AREA, OR MIN. OF 2'6", SHALL PROVIDE ADA ACCESSIBILITY. MIN. 5% OF SEATING AREA SHALL BE ACCESSIBLE. (INTERIOR AND EXTERIOR)

INTERIOR DETAILS

REGISTERED ARCHITECT WILLIAM KENNETH HOPKINS No. 1030 STATE OF MAINE

Reviewed for Code Compliance Inspections Division Date: 07/20/17

Prepared For: 16 Middle Street Associates, LLC

Consultant:

Architect: ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project: 16 Middle Street Maine Media
16 Middle Street Portland, Maine

Revisions:

Scale: As indicated

Date: APRIL 20, 2017

BENKAY WALL TYPES

A1.11