1 MAINE MEDIA FLOOR PLAN
1/8" = 1'-0"

2 5TH FLOOR RCP
1/8" = 1'-0"

ARMSTRONG MESA 24" X 24" BEVELED TEGULAR WITH 9/16" GRID

5/8" TYPE X GYPSUM

MAINE MEDIA DOOR SCHEDULE

DOOR No.	LOCATION	DOOR W	DOOR H	DOOR THCK	DOOR TYPE	DOOR MAT'L	DOOR FINISH	FRAME THRESHOLD	FRAME MAT'L	FRAME FINISH	Hardware	LABEL	REMARKS
5TH FLOOR													
M02	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M03	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M04	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M05	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M06	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M07	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M08	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M09	OFFICE	3'-0"	7'-0"	1 3/4"	4	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M10	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M11	CONFERENCE	3'-0"	8'-0"	1 3/4"	4	GLASS	ALUM		STOREFRONT	BRUSHED	PASSAGE		
M12	CONFERENCE	3'-0"	8'-0"	1 3/4"	4	GLASS	ALUM		STOREFRONT	BRUSHED	PASSAGE		
M14	WOMENS	3'-0"	7'-0"	1 3/4"	2	SC WOOD	POLY		MTL	PTD	PASSAGE		
M15	MENS	3'-0"	7'-0"	1 3/4"	2	SC WOOD	POLY		MTL	PTD	PASSAGE		
M16	BREAK	3'-0"	7'-0"	1 3/4"	4	WOOD/GLASS	POLY		MTL	PTD	PASSAGE		
M17	BREAK	3'-0"	7'-0"	1 3/4"	4	WOOD/GLASS	POLY		MTL	PTD	PASSAGE		
M18	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M19	IT	3'-0"	7'-0"	1 3/4"	2	SC WOOD	POLY		MTL	PTD	STOREROOM		
M20	STOR	5'-0"	7'-0"	1 3/4"	5	SC WOOD	POLY		MTL	PTD	PASSAGE		
M21	STOR	5'-0"	7'-0"	1 3/4"	5	SC WOOD	POLY		MTL	PTD	PASSAGE		
M22	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M23	RADIO	3'-0"	7'-0"	1 3/4"	4	WOOD/GLASS	POLY		MTL	PTD	PASSAGE		
M24	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M26	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M27	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M28	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M29	OFFICE	6'-0"	7'-0"	1 3/4"	1	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M30	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M31	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M32	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M33	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M34	JAN	3'-0"	7'-0"	1 3/4"	2	SC WOOD	POLY		MTL	PTD	PASSAGE		
M35	STOR	5'-0"	7'-0"	1 3/4"	5	SC WOOD	POLY		MTL	PTD	PASSAGE		
M36	STOR	5'-0"	7'-0"	1 3/4"	5	SC WOOD	POLY		MTL	PTD	PASSAGE		
M37	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M38	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M39	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M40	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M41	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M42	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M43	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M44	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M45	STOR	3'-0"	7'-0"	1 3/4"	2	SC WOOD	POLY		MTL	PTD	OFFICE		
M46	STOR	3'-6"	7'-0"	1 3/4"	5	SC WOOD	POLY		MTL	PTD	PASSAGE		
M47	STOR	5'-0"	7'-0"	1 3/4"	5	SC WOOD	POLY		MTL	PTD	PASSAGE		
M48	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M49	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		
M50	OFFICE	6'-0"	7'-0"	1/2"	3	WOOD/GLASS	POLY		MTL	PTD	OFFICE		

NOTE: DOORS TO BE ON CONCRETE FLOOR WITHOUT THRESHOLDS- ONLY UNDERCUT 1/4"

WOOD DOORS TO BE PREMIUM A GRADE PLAIN SLICED BIRCH BOOK AND RUNNING MATCH WITH CLEAR POLY FINISH

5 SHELVING DETAIL
1/2" = 1'-0"

4 CEILING TRANSITION
1" = 1'-0"

6 DETAIL AT WALL/WINDOW
1 1/2" = 1'-0"

7 MAINE MEDIA-ENLARGED BATHROOM
1/4" = 1'-0"

REGISTERED ARCHITECT WILLIAM KENNETH HOPKINS No. 1090 STATE OF MAINE

Reviewed for Code Compliance Department Director Fire Protection Services Date: 08/04/17

Prepared For: 16 Middle Street Associates, LLC

Consultant:

Architect: ARCHETYPE architects 48 Union Wharf Portland, Maine 04101 (207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project: 16 Middle Street Condominium — 16 Middle Street Portland, Maine

Revisions:

Scale: As indicated

Date: MAR. 29, 2017

MAINE MEDIA FIT UP PLAN

A1.1