PLUMBING FIXTURE CONNECTION SCHEDULE

TAG	DESCRIPTION	SAN	VENT	CW	HW	GAS
-	-	-	-	-	-	
P1	ADA FLOOR MOUNTED FV WC / non-ADA WC, 15" H. / ADA WC 17"H.	3"	2"	1"	-	
P2	ADA COUNTERTOP / WALL-MOUNT LAVATORY	2"	1-1/2"	1/2"	1/2"	
P3	ADA URINAL	2"	1½"	¾"	-	
P4	MOP SERVICE SINK	3"	2"	1/2"	1/2"	
-	-	-	-	-	-	
-	-	-	-	-	-	
-	-	-	-	-	-	
-	-	-	-	-	-	
-	-	-	-	-	-	
3"FD	3" FLOOR DRAIN w/ TRAP PRIMER CONNECTION	3"	2"	1/2"	-	
ETP	ELECTRONIC TRAP PRIMER (ETP)	-	-	1/2"	-	
I.W.	INDIRECT WASTE RECEPTOR	3"	2"		-	

MINIMUM SIZE OF BELOW SLAB SANITARY & VENT PIPING SHALL BE 2".

General Mechanical Notes

1. Exposed supply ductwork shall be double-wall, spiral seam, solid liner, 1" fiberglass insulation and Paint-Grip galvanizing for field painting. Exposed return air ductwork shall be spiral seam with Paint-Grip galvanizing for field painting.
2. Ductwork downstream of Variable Air Volume Boxes shall have ½" thick duct liner, Armaflex SA, or equal.
3. Provide combination fire / smoke dampers (FD / SD) at all locations where the ducts penetrate the shaft wall enclosures for ducts that penetrate two (2) or more floors. For ducts that only penetrate one (1) floor, fire dampers are required.
4. Concealed supply ductwork shall be insulated with 2" thick fiberglass ductwrap w/ FSK.
5. Domestic hot and cold water piping shall be insulated with 1" thick fiberglass pipe insulation.
6. Coordinate exposed ductwork with the lighting plan.
7. 90 degree duct elbows shall be mitered with single thickness turning vanes or radiused with a 6 radius equal to 1.5 times the duct width.
8. Branch ducts to VAV boxes shall be the box inlet size.

FAN / LIGHT PERFORMANCE SCHEDULE

TAG	AIRFLOW (CFM)	T.S.P (IN.W.G.)	NOISE (SONES)	RPM	DRIVE	ELECTRICAL REQUIREMENTS					BASIS OF DESIGN = PANASONIC "WhisperGreen Select"		
						HP	BHP	WATTS	AMPS	V/PH/HZ	SERVICE	ARRANGEMENT	MODEL
EF-T	50 / 110	0.25	0.4	-	DIRECT	-	-	11.0	0.2	120/1/60	TOILETS / JANITOR / ELECTRICAL	CEILING	FV-05-11VKL1
-	-	-	-		-	-	-	-	-	-	-	-	-

Notes EF-T shall come with motion sensors and be multi-speed with time delay and multi-speed plug n' play modules. See Plans for quantities.

Notes Furnish each fan-light unit with gravity operated backdraft damper and two (2) 7W. LED lamps.

TEMPERATURE MIXING VALVE PERFORMANCE SCHEDULE

TAG	FLOW RATE (GPM)	INLET CONNECTION (INCHES)	OUTLET CONNECTION (INCHES)	WPD (PSIG)	SET POINT (DEGREES F)	PROVIDE SPARE CARTRIDGE (Y) OR (N)	BASIS OF DESIGN LEONARD "Eco-Mix"		
							SERVICE	ARRANGEMENT	MODEL
TMV	9	¾	¾	10	115	N	DOMESTIC HW	INLINE	LV-20-E-LF-BDT
-	-	-	-	-	-	-	-	-	-

AIR DEVICE PERFORMANCE SCHEDULE

TAG	PANEL SIZE(IN)	NECK SIZE(IN)	AIRFLOW (MAX. CFM)	SP.LOSS (IN.W.G.)	THROW(L)	THROW(S)	Nc	BASIS OF DESIGN (F) FANTECH, PRICE		
								DUCT CONN.(IN)	PATTERN	MODEL
A	24x24	6x6	150	0.05	-	-	25	SEE DWGS	SEE DWGS	AMX-3AL
B	24x24	9x9	350	0.05	-	-	30	SEE DWGS	SEE DWGS	AMX-3AL
C	24x24	12x12	500	0.05	-	-	30	SEE DWGS	SEE DWGS	AMX-3AL
D	-	6	150	0.05	-	-	30	SEE DWGS	SEE DWGS	PPD2 w/ PIC
F	-	12x6	250	0.05	-	-	25	SEE DWGS	5? DN.	RCG / C / DVAL / BIZ
H	-	18x12	500	0.05	-	-	25	SEE DWGS	5? DN.	RCG / C / DVAL / BIZ
I	-	8"ϕ	220	0.05	-	-	18	SEE DWGS	ADJUSTABLE	(F) RHV
AA	-	8x8	100	0.05	-	-	30	SEE DWGS	1/2", 45^	630DAL
BB	-	12x12	400	0.05	-	-	30	SEE DWGS	1/2", 45^	630DAL
CC	-	16x16	600	0.05	-	-	30	SEE DWGS	1/2", 45^	630DAL
DD	-	22x22	1200	0.05	-	-	30	SEE DWGS	1/2", 45^	630DAL
EE	-	22x42	3000	0.05	-	-	25	SEE DWGS	1/2", 45^	630DAL
FF	-	24x16	1000	0.05	-	-	25	SEE DWGS	1/2", 45^	630DAL

ELECTRIC WATER HEATER PERFORMANCE SCHEDULE

TAG	STORAGE (GALS)	INPUT (KW)	REC'VRY. @ 100°F (GPH)	ELECTRICAL REQUIREMENTS			BASIS OF DESIGN AO Smith "Proline"			
				HP	WATTS	V/PH/HZ	SERVICE	FUEL	MODEL	DIMENSIONS
EWH	19.9	2.5	12.0	-	-	208/1/60	DOM HW	ELECTRIC	EJCS-20	24"H. x 18"ϕ
-	-	-	-	-	-	-	-	-	-	-

Note Electric heating elements shall be wired for "non-simultaneous" operation. See Drawings for quantities.

STATE OF MAINE — MICHAEL A. SCHUCK — LICENSED PROFESSIONAL ENGINEER

Reviewed for Code Compliance Inspection Division Portland, Maine

Date: 08/04/17

Prepared For: Archetype
Union Wharf
Portland, ME 04101

Consultant: BENNETT ENGINEERING
MECHANICAL • ELECTRICAL
(207) 865-9475

Architect: ARCHETYPE Architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project: 16 MIDDLE STREET OFFICE BUILDING
MIDDLE STREET
PORTLAND, MAINE

Revisions: 02/20/2017 - CD ISSUE

Scale: 1/8"=1'-0" U.N.O.

Date: 20 FEB 2017

Maine Media
HVAC 5th FLOOR PLAN

M1.01