

# Protection Professionals

325 U.S. Route 1  
 Falmouth, ME 04105  
 Ph 207-775-5755  
 Fax 207-781-2064

# Device List

No. 9479

List Date
6/1/2016

<b>Bill To Name / Address</b> Digital Sky, Inc. Attn: Accounts Payable 6 Proctor Road, Suite A Biddeford, ME 04005	<b>Job Site</b> 185 Fore Street Portland, ME 04101
--	--

<b>CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE</b> <b>Attach copy to Purchase Order for accounting</b>	<b>Estimate No.</b> _____
--	------------------------------

Item	Description	Qty To Order	Qty Ordered
	All smoke and or CO detection devices inside the units (except the utility closets) are 120 VAC. All 120 VAC devices shall be supplied by others. CO detectors and heat detectors in the utility closets are included with this parts list. These devices will be connected to the fire panel. CO detectors require 24 VDC from the fire panel. Pull stations are added to meet code. One pull station within five feet of each exit and on each level. Key box supplied by others. Elevator shaft is non-sprinkled. No devices in shaft.		
P300-3992643	Fire Alarm System Potter P300: 127 points expandable to 381 points Addressable Fire Alarm Control Panel, 2 NAC circuits @ 3 amps each, total power is 5 amps, 2 I/O circuits @ 1 amp each	1	
UD-1000-3006465	Potter UD-1000 Digital Alarm Communicator Transmitter	1	
Bat 12-18	Battery 12-18	2	
E120V-GT	Space Age 120V Surge Protector plus lockout and circuit breaker labels for FACP	1	
RA-6500-3992660	LCD remote annunciator, 160 characters	1	
PSA-1430800	Potter PSA Addressable Photo Smoke Detector	26	
RHA-1430804	Potter RHA Rate of Rise Heat Detector	8	
AB-6-1430806	Potter AB-6 six Inch Addressable Base	34	
TRM-4-1430824	Potter TRM-4 Twin Relay Module (elevator)	4	
DCM-4-1430822	Potter DCM-4 Dual Input Contact Module (sprinkler)	5	
MCM-1430820	Potter MCM Miniature Contact Module (elevator tampers)	1	
SSU00672	Fire Document box 12 inches wide X 13.1 inches high X 2.25 inches deep, CAT 30 keyed	1	
KEY-5250080	Key assembly including cam and lever for P series panels (WS-93)	1	
APS-DA-1430811	Potter ABS-DA Addressable Pull Station Dual Action	9	
HS-24WR-4890030	Horn/strobe wall adjustable candela	18	

Ordered By: \_\_\_\_\_

Date: \_\_\_\_\_

Received By: \_\_\_\_\_

Date: \_\_\_\_\_

# Protection Professionals

325 U.S. Route 1  
 Falmouth, ME 04105  
 Ph 207-775-5755  
 Fax 207-781-2064

# Device List

No. 9479

List Date
6/1/2016

Bill To Name / Address
Digital Sky, Inc. Attn: Accounts Payable 6 Proctor Road, Suite A Biddeford, ME 04005

Job Site
185 Fore Street Portland, ME 04101

**CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE**  
**Attach copy to Purchase Order for accounting**

Estimate No.

Item	Description	Qty To Order	Qty Ordered
MH-12/24R-4560041	Mini-horn, red (one per bedroom)	27	
BK-CO1224T	Carbon Monoxide Detector with alarm and trouble contacts, 20ma standby and 40ma in alarm, 12/24 VDC	8	
MCM-1430820	Potter MCM Miniature Contact Module 5.5% Maine Sales Tax	8	

Ordered By: \_\_\_\_\_

Date: \_\_\_\_\_

Received By: \_\_\_\_\_

Date: \_\_\_\_\_