SECOND FLOOR FINISH SCHEDULE

#	NAME	NO NEW WORK	FLOOR: RETAIN EXISTING	FLOOR: MATCH EX AS REQ'D	FLOOR: NEW VCT	FLOOR: NEW CARPET	FLOOR: NEW SHEET VINYL	BASE: RETAIN EXISTING	BASE: MATCH EX AS REQ'D	BASE: WOOD TYPE "A"	BASE: WOOD TYPE "B"	WALLS: RETAIN EXISTING	WALLS: MATCH EX AS REQ'D	WALLS: NEW 1/2 GYP OVER EX	WALLS: NEW 5/8 GYP "X"	WALLS: NEW 5/8 GYP "MR"	CEILING: NEW PAINT	CEILING: RETAIN EX	CEILING: MATCH EX AS REQ'D	CEILING: NEW 1/2 GYP	CEILING: NEW SUSP CLG	HGT	NOTES
200	HALL				X			X						X			X		X				1. FIN CL TO MATCH ROOM, UON
200B	BATH					X				X						X	X			X		9'0	2. BOX GYP AROUND NEW HEADERS, TYP
201	STUDY	X						X				X					X	X					
202	BEDROOM																						SAME AS 200
203	LIVING ROOM	X						X				X					X	X					1
ST.A	GRAND STAIR				X			X							X		X	X					
204	HALL				X			X					X				X	X					
205	GUEST ROOM				X				X				X				X	X					
207	LIVING ROOR																						
208	BEDROOM																						
208A	BATH																						
209	STORAGE																						
212	BEDROOM																						
212B	BATH																						
213	STUDY	X						X				X					X	X					
214	HALL																						
ST.B	STAIR				X			X							X		X	X					
212B	GUEST BATH				X				X				X				X	X					

Sheet 1-3 SECOND FLOOR PLAN

CATHEDRAL OF THE IMMACULATE CONCEPTION

Project

Plotted by: JMB

Plot date: 12-30-98

AutoCAD file name: CFLA3

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 07/31/13

#	REVISION
1	DOORS 27,28 FROM 206A,209 REVISED
2	ROOMS 209,206,205B
3	RELEASED FOR CONSTRUCTION
4	RM 201 RETURNED TO ORIGINAL, BATH 202B ADD

DEARBORN/WHITED
ARCHITECTS ENGINEERS
(207) 774-2135
P. O. BOX 127 - PORTLAND, MAINE 04112

RENOVATIONS TO RECTORY BUILDING
CATHEDRAL OF THE IMMACULATE CONCEPTION
PORTLAND, MAINE

PROJECT
DRAWING

SECOND FLOOR PLAN
SCALE 1/4" = 1'0"

CONSTRUCTION FROM THIS DRAWING IS AUTHORIZED ONLY WHEN STAMPED BY RESPONSIBLE ARCHITECT OR ENGINEER

DATE 12-14-87
DWN JWB OK'D WW

A-3

SHEET 10 OF 38