BASEMENT ROOM FINISH SCHEDULE

#	NAME	NO NEW WORK	FLOOR: RETAIN EXISTING MATCH EX AS REQ'D	FLOOR: NEW VCT	FLOOR: NEW CARPET	FLOOR: NEW SHEET VINYL	BASE: RETAIN EXISTING MATCH EX AS REQ'D	BASE: WOOD TYPE A	BASE: WOOD TYPE B	WALLS: RETAIN EXISTING MATCH EX AS REQ'D	WALLS: NEW 1/2 GYP OVER EX	WALLS: NEW 5/8 GYP	WALLS: NEW 5/8 GYP "X"	WALLS: NEW 5/8 GYP "MR"	WALLS: NEW PAINT	CEILING: RETAIN EX	CEILING: MATCH EX AS REQ'D	CEILING: NEW 5/8 GYP	CEILING: NEW SUSP CLG	HGT	NOTES
01	STORAGE	X														X					
02	CONFERENCE			X					X			X			X		X				3
03	HALL			X					X			X			X			X		7'6	
04	MECHANICAL RM	X					X			X					X			X		8'6	4
05	ELEV MACH RM	X					X			X					X			X		8'6	4
06	PARISH RECORDS			X					X	X					X			X		8'6	
07	PASTORS OFFICE			X					X			X			X		X				3
ST.B	STAIR			X				X			X				X		X				
08	PARISH OFFICE			X					X			X			X		X				3
09	HALL			X					X			X			X			X		7'6	1
09B	BATH				X				X					X	X			X		8'6	1
ST.C	BSMT STAIR			X				X			X			X	X		X				
10	LAUNDRY			X					X	X					X		X				
11	EX MACH RM	X					X			X					X	X					
12	STORAGE	X																			
13	STORAGE	X																			
15	EX BOILER RM	X																			
16	ELEC RM		X				X			X					X		X			4	
17	CONFERENCE			X					X			X			X		X			3	

NOTES:
1. FIN CL TO MATCH ROOM, UON
2. BOX GYP AROUND NEW HEADERS, TYP
3. NEW WAINSCOT @ ALL WALLS, SEE DTL
4. 1-HR RATED CLG

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/15/13

#	REVISION
1	DOOR #10 MOVED, DOOR #16 SWING REVERSED RELEASED FOR CONSTRUCTION

DEARBORN/WHITED
ARCHITECTS ENGINEERS
(207) 774-2135
P. O. BOX 127 - PORTLAND, MAINE 04112

RENOVATIONS TO RECTORY BUILDING
CATHEDRAL OF THE IMMACULATE CONCEPTION
PORTLAND, MAINE
PROJECT
BASEMENT PLAN
SCALE: 1/4" = 1'0"
DRAWING

CONSTRUCTION FROM THIS DRAWING IS AUTHORIZED ONLY WHEN STAMPED BY RESPONSIBLE ARCHITECT OR ENGINEER

DATE 12-14-87
DWN JWB CK'D WW

A-1

SHEET 8 OF 38

Printed by: JWB
Plot date: 12/15/88
AutoCAD file name: CR.V1
SHEET: BASEMENT PLAN
Project: CATHEDRAL OF THE IMMACULATE CONCEPTION