FOURTH FLOOR FINISH SCHEDULE

#	NAME	NO NEW WORK	FLOOR: RETAIN EXISTING	FLOOR: MATCH EX AS REQ'D	FLOOR: NEW WOOD	FLOOR: NEW CARPET	FLOOR: NEW SHEET VINYL	BASE: RETAIN EXISTING	BASE: MATCH EX AS REQ'D	BASE: WOOD TYPE 'A'	BASE: WOOD TYPE 'B'	WALLS: RETAIN EXISTING	WALLS: MATCH EX AS REQ'D	WALLS: NEW 1/2" GYP OVER EX	WALLS: NEW 5/8" GYP	WALLS: NEW 5/8" GYP 'X'	WALLS: NEW 5/8" GYP MR	CEILING: NEW PAINT	CEILING: RETAIN EX.	CEILING: MATCH EX AS REQ'D	CEILING: NEW 5/8" GYP	CEILING: NEW SUSP. ACT.	HGT	NOTES
400	ATTIC	X																						
401	LANTERN					X				X				X					X	X				
403	SITTING ROOM					X				X				X					X	X				
403A	STORAGE						X				X			X					X	X				
404	BEDROOM					X				X				X					X	X				1
404B	BATH						X				X						X		X	X				
405	LIVING ROOM					X				X				X					X	X				1
407	HALL					X				X				X					X	X				
409	LIVING ROOM					X				X				X					X	X				1
411	BEDROOM					X				X				X					X	X				1
411B	BATH						X				X						X		X	X				
412	BEDROOM					X				X				X					X	X				1
413	LIVING ROOM					X				X				X					X	X				1,2
413B	BATH						X				X						X		X	X				
ST.B	STAIR					X				X						X			X		X			
414	STORAGE						X			X				X	X						X			1,2

NOTES:
1. FIN CL TO MATCH ROOM, UON
2. BOX GYP AROUND NEW HEADERS, TYP

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/15/13

#	REVISION
1	ROOM 414 ADDED
2	CL 404A,405A,499A,473A RELEASED FOR CONSTRUCTION

DEARBORN/WHITED
ARCHITECTS ENGINEERS
(207) 774 2135

RENOVATIONS TO RECTORY BUILDING
CATHEDRAL OF THE IMMACULATE CONCEPTION
PORTLAND, MAINE

PROJECT: CATHEDRAL OF THE IMMACULATE CONCEPTION
DRAWING: FOURTH FLOOR PLAN

CONSTRUCTION
THIS DRAWING IS AUTHORIZED ONLY WHEN STAMPED BY RESPONSIBLE ARCHITECT OR ENGINEER

DATE 12-14-08
DWN. JWB CKD.

A-1

SHEET 12 OF

AutoCAD filename: ACADVORLAS Plot date: 9-5-08 Plotted by: JWB
SHEET: FOURTH FLOOR PLAN
Project: CATHEDRAL OF THE IMMACULATE CONCEPTION