

LIGHTING SCHEDULE						
TYPE	DESCRIPTION	MANUFACTURER/MODEL	LAMPS	FIXTURE WATTS	MOUNTING	NOTES
L1	POSSINI EURO SVEN BRUSHED NICKEL MODERN VANITY LIGHT	EURO STYLE LIGHTING EUST757	LED	22	FLUSH MOUNT WALL VANITY	1760 LUMENS, 3000K COLOR TEMP., 120V
L2	16" DIAMETER LOW PROFILE CEILING FIXTURE WITH WHITE FINISH	ETI 54075142 (COMES IN QUANTITIES OF 4)	LED	22	SURFACE MOUNT CEILING	1700 LUMENS, 4000K COLOR TEMP., 120V, 5-YEAR WARRANTY, UL LISTED FOR DAMP OR DRY LOCATIONS, ENERGY STAR RATED.
L3	12" DIAMETER LOW PROFILE CEILING FIXTURE WITH WHITE FINISH	ETI 54074142 (COMES IN QUANTITIES OF 24)	LED	14	SURFACE MOUNT CEILING	1000 LUMENS, 4000K COLOR TEMP., 120V, 5-YEAR WARRANTY, UL LISTED FOR DAMP OR DRY LOCATIONS, ENERGY STAR RATED.
L4	4' LITEPUFF LINEAR LOW PROFILE	LITHONIA FMLL 9 30840	LED	36	WALL MOUNT SURFACE MTD AT 7' TO CENTER	5-YEAR WARRANTY, 3074 LUMENS, 120V, 4000K COLOR TEMP.
L5	2'X4' RECESSED INDIRECT LED FIXTURE WITH WHITE FINISH	FINELITE HPR LED-A-2X4-DCO-SO-3500K-120V-SC-XX	LED	36	RECESSED CEILING	10-YEAR WARRANTY, 3786 LUMENS, 120V, 3500K COLOR TEMP.
L6	2'X2' RECESSED INDIRECT LED FIXTURE WITH WHITE FINISH	FINELITE HPR LED-A-2X2-DCO-SO-3500K-120V-SC-XX	LED	37	RECESSED CEILING	10-YEAR WARRANTY, 3338 LUMENS, 120V, 3500K COLOR TEMP.
L7	4' LINEAR LED PENDANT MOUNT FIXTURE	FINELITE HP-4 ID-4-SO-HO-3500K-TG-120-FA-SC-C4	LED	72	PENDANT MOUNTED AT 7.5' A.F.F. TO CENTER	10-YEAR WARRANTY, 4431 LUMENS, 120V, 3500K COLOR TEMP
L8	4' LINEAR SURFACE VOLUMETRIC HIGH LUMEN	COLUMBIA LIGHTING LCL-4-35-HL-E-U	LED	55	SURFACE MOUNT CEILING	5-YEAR WARRANTY, 6100 LUMENS, 120V, 3500K COLOR TEMP.
L9	2'X2' SURFACE MOUNT LED FIXTURE WITH WHITE FINISH	FINELITE HPR LED-A-2X2-DCO-SO-3500K-120V-SC-DW	LED	37	SURFACE MOUNT CEILING	10-YEAR WARRANTY, 3338 LUMENS, 120V, 3500K COLOR TEMP. COMES WITH DRYWALL KIT FOR SURFACE MOUNTING
L10	4' LINEAR SURFACE VOLUMETRIC LOW WATTAGE	COLUMBIA LIGHTING LCL-4-35-LW-E-U	LED	25	SURFACE MOUNT CEILING	5-YEAR WARRANTY, 2500 LUMENS, 120V, 3500K COLOR TEMP.
L11	PENDANT FIXTURE	ASL RPPS-LED-38-3500K-DVD-561-D30-ES	LED	38	PENDANT MOUNT	4000 LUMENS, 3500K COLOR TEMP. 5-YEAR WARRANTY
L12	7" SURFACE MOUNT ROUND LED MODULE	PRESCOLITE LBSLEDA10L-35K-9-WH	LED	17	SURFACE MOUNT CEILING	1000 LUMENS, 3500K COLOR TEMP., 5-YEAR WARRANTY,
L13	HIGH LUMEN FLEXIBLE OPTICALLY CLEAR LIGHTING	JESCO DL-AC-FLEX 8' MOUNTING CHANNEL DL-AC-FLEX-CH8 SNAP IN "U" CLIP DL-AC-FLEX-MC HARDWIRE CONNECTION DL-AC-FLEX-HW END CAP DL-AC-FLEX-EC	LED	5 PER FOOT	SURFACE MOUNT CEILING	500 LUMENS PER FOOT, 3000K COLOR TEMP., 5-YEAR WARRANTY, 120V.
L14	4' LINEAR LED PENDANT MOUNT FIXTURE	FINELITE HP-4 ID-4-SO-SO-3500K-TG-120-FA-SC-C4	LED	36	PENDANT MOUNT	10-YEAR WARRANTY, 3127 LUMENS, 120V, 3500K COLOR TEMP
L15	8' LINEAR LED PENDANT MOUNT FIXTURE	FINELITE HP-4 ID-8-SO-HO-3500K-TG-120-FA-SC-C4	LED	144	PENDANT MOUNTED AT 7.5' A.F.F. TO CENTER	10-YEAR WARRANTY, 8862 LUMENS, 120V, 3500K COLOR TEMP
L16	SIGN LIGHTER DUAL LED GOOSENECK	JUNO LIGHTING GROUP S412L2-3K-FL-BLK-1	LED	18	WALL MOUNT	ENERGY STAR COMPLIANT, 960 LUMENS, 120V
L17	SLIM WALLPACK	RAB LIGHTING SLIM-18	LED	18	WALL MOUNTED AT 8'	DARK SKY APPROVED, 1,242 LUMENS, 120V, 3000K COLOR TEMP.
L18	2'X4' RECESSED INDIRECT LED FIXTURE WITH WHITE FINISH	FINELITE HPR LED-A-2X4-DCO-HO-3500K-120V-SC-XX	LED	57.5	RECESSED CEILING	10-YEAR WARRANTY, 5585 LUMENS, 3500K COLOR TEMP.
EMERGENCY LIGHTING						
LE1	LED EXIT SIGN WITH BATTERY BACKUP, THERMOPLASTIC HOUSING, CONCEALED CHEVRON KNOCKOUTS	LITHONIA LQM-S-W-3-R-120/277-EL-N-EA-WGEXT	LED	1	CEILING/WALL	PROVIDE SINGLE OR DOUBLE FACE AS REQUIRED, 5-YEAR WARRANTY, UL LISTED
LE2	LED EMERGENCY LIGHT WITH BATTERY BACKUP, THERMOPLASTIC HOUSING	LITHONIA ELM2-LED-W-WRS	LED	3	SURFACE MOUNT WALL	PROVIDE WITH FIDO WIRELESS SELF DIAGNOSTICS WITH EDGE ROUTER MOUNTED IN MECH RM. REMOTE HEADS AS SHOWN IN
LE3	SINGLE HEAD REMOTE EMERGENCY LIGHT	LITHONIA LEA-Q-L0304	LED	1.5	SURFACE MOUNT WALL	UL LISTED, DAMP LOCATION LISTED
NOTES:						
1. THE PRODUCTS LISTED ABOVE ARE REPRESENTATIVE OF THE DESIRED TYPE AND FEATURES. ALTERNATIVES MAY BE ACCEPTABLE IF SUBMITTED WITH CUTSHEETS AND PHOTOMETRIC DATA DEMONSTRATING THEIR EQUIVALENCE.						
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUPPLYING AND INSTALLING ALL NECESSARY SUPPORTS, FITTINGS, TRIMS, MASTS, BRACKETS, HOUSINGS, CANOPIES, AND ACCESSORIES TO MAKE A COMPLETE LIGHTING ASSEMBLY.						
3. ALL LED LUMINAIRES SHALL BE LM-79 AND LM-80 TESTED WITH MINIMUM 50K HOUR RATED LIFE.						

LIGHTING CONTROLS						
S	INDUSTRIAL GRADE WALL MOUNTED TOGGLE SWITCH	LEVITON 1222-2T	-	-	RECESSED WALL	20A RATED, 120-277V, SELF GROUNDING
S3	INDUSTRIAL GRADE WALL MOUNTED 3-WAY TOGGLE SWITCH	LEVITON 1223-2T	-	-	RECESSED WALL	20A RATED, 120-277V, SELF GROUNDING
OS	ULTRASONIC LOW VOLTAGE CEILING OCCUPANCY SENSOR	WATTSTOPPER WT-2255	-	-	SURFACE MOUNT CEILING	SET TIME DELAY FOR 20 MIN U.O.N., 90' NARROW COVERAGE FOR HALLWAYS, 5-YEAR WARRANTY
OS1	DUAL TECHNOLOGY LOW VOLTAGE CEILING OCCUPANCY SENSOR	WATTSTOPPER DT-300	-	-	SURFACE MOUNT CEILING	SET TIME DELAY FOR 20 MIN U.O.N., 36' WIDE COVERAGE FOR ROOMS, 5-YEAR WARRANTY
OS2	ULTRASONIC LOW VOLTAGE CEILING OCCUPANCY SENSOR	WATTSTOPPER UT-300	-	-	SURFACE MOUNT CEILING	SET TIME DELAY FOR 20 MIN U.O.N., 12' WIDE COVERAGE FOR ROOMS, 5-YEAR WARRANTY
OSS	ULTRASONIC LOW VOLTAGE WALL SWITCH OCCUPANCY SENSOR	WATTSTOPPER UW-100-W	-	-	WALL MOUNT RECESSED	5-YEAR LIMITED WARRANTY, SET TIME DELAY FOR 20 MIN U.O.N.
PP	L17	WATTSTOPPER BZ-150	-	-	ACCESSIBLE IN CEILING	5-YEAR WARRANTY, 120/227V, USED IN CONJUNCTION WITH CEILING OCCUPANCY SENSORS FOR LOW VOLTAGE WIRING. MUST BE ACCESSIBLE IN CEILING
PC	OUTDOOR WET LOCATION LISTED PHOTO CELL, EXTRA HEAVY DUTY DIE CAST HOUSING	INTERMATIC K4136M	-	-		