

**GENERAL NOTES**

- THE NOTES ON THESE DRAWINGS ARE NOT INTENDED TO REPLACE SPECIFICATIONS. SEE SPECIFICATIONS FOR REQUIREMENTS IN ADDITION TO GENERAL NOTES. INCONSISTENCIES BETWEEN THESE DRAWINGS AND THE SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO PROCEEDING WITH THE AFFECTED PORTION OF THE WORK.
- STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH JOB SPECIFICATIONS AND ARCHITECTURAL, MECHANICAL, ELECTRICAL, PLUMBING, AND SITE DRAWINGS. CONSULT THESE DRAWINGS FOR LOCATIONS AND DIMENSIONS OF OPENINGS, CHASES, INSERTS, REGLETS, SLEEVES, DEPRESSIONS, AND OTHER DETAILS NOT SHOWN ON STRUCTURAL DRAWINGS.
- ALL DIMENSIONS, EXISTING CONDITIONS, AND AS-BUILT CONDITIONS MUST BE VERIFIED IN THE FIELD. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE STRUCTURAL ENGINEER BEFORE PROCEEDING WITH THE AFFECTED PART OF THE WORK.
- THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE ONLY AFTER THE STRUCTURAL WORK CONTAINED IN THE 5- DRAWINGS IS COMPLETED. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE ERECTION PROCEDURES AND SEQUENCE TO ENSURE THE SAFETY OF THE BUILDING AND ITS COMPONENTS DURING ERECTION. THIS INCLUDES THE ADDITION OF NECESSARY SHORING, SHEETING, TEMPORARY BRACING, GUYS OR TIEDOWNS. SUCH MATERIAL SHALL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER COMPLETION OF THE PROJECT.
- SECTIONS AND DETAILS SHOWN ON ANY STRUCTURAL DRAWINGS SHALL BE CONSIDERED TYPICAL FOR SIMILAR CONDITIONS AS DETERMINED BY THE STRUCTURAL ENGINEER. THE STRUCTURAL ENGINEER RESERVES THE RIGHT TO INTERPRET DETAILS TO ADDRESS OTHER PROJECT CONDITIONS.
- PROVIDE AND INSTALL NECESSARY MATERIAL TO CONNECT ELEVATOR SUPPORT BEAMS AND GUIDE RAILS. LOCATION AND SIZE OF MEMBERS AND ANY INSERTS REQUIRED SHALL BE DETERMINED BY THE ELEVATOR MANUFACTURER.
- THE CONTRACTOR SHALL SUBMIT COMPLETE SHOP DRAWINGS FOR ALL PARTS OF THE WORK INCLUDING DESCRIPTION OF SHORING, AND CONSTRUCTION METHODS AND SEQUENCING WHERE APPLICABLE. NO PERFORMANCE OF THE WORK INCLUDING, BUT NOT LIMITED TO, DEMOLITION OF EXISTING STRUCTURE, OR FABRICATION OR ERECTION OF NEW STRUCTURAL ELEMENTS, SHALL COMMENCE WITHOUT REVIEW OF THE SHOP DRAWINGS BY THE ARCHITECT AND ENGINEER. SUBMIT ONE COPY AND ONE SEPIA. COPY WILL BE REVIEWED AND SEPIA WILL BE RETURNED FOR SHOP DRAWINGS AND SUBMITTALS REQUIRED, REFERENCE THE PROJECT SPECIFICATIONS.
- ALL APPLICABLE FEDERAL, STATE, AND MUNICIPAL REGULATIONS SHALL BE FOLLOWED, INCLUDING THE FEDERAL DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND HEALTH ACT.
- IN ACCORDANCE WITH THE INTERNATIONAL BUILDING CODE (2009 EDITION, SECTION 1704.1), A STATEMENT OF SPECIAL INSPECTIONS IS REQUIRED AS A CONDITION FOR PERMIT ISSUANCE BY THE LOCAL CODE OFFICIAL. THIS STATEMENT SHALL INCLUDE A COMPLETE LIST OF MATERIALS AND WORK REQUIRING SPECIAL INSPECTIONS, THE INSPECTIONS TO BE PERFORMED AND A LIST OF THE INDIVIDUALS, APPROVED AGENCIES AND FIRMS INTENDED TO BE RETAINED FOR CONDUCTING SUCH INSPECTIONS.
- REFERENCE THE PROJECT SPECIFICATIONS FOR ALL TESTING REQUIREMENTS.

**DESIGN LOADS**

- BUILDING CODE:**  
INTERNATIONAL BUILDING CODE, 2009 EDITION  
ASCE 7-05 MINIMUM DESIGN LOADS FOR BUILDINGS  
AND OTHER STRUCTURES.
- DESIGN FLOOR LIVE LOADS:**  
PUBLIC ROOMS AND CORRIDORS SERVING THEM: 100 PSF  
PRIVATE ROOMS AND CORRIDORS SERVING THEM: 40 PSF  
STAIRS: 100 PSF
- DESIGN ROOF SNOW LOAD:**  
GROUND SNOW LOAD (Pg): 60 PSF  
SNOW EXPOSURE FACTOR (Ce): 1.0  
SNOW LOAD IMPORTANCE FACTOR (Is): 1.0  
SNOW LOAD THERMAL FACTOR (Ct): 1.1  
FLAT ROOF SNOW LOAD (Pf): 46 PSF + DRIFT
- DESIGN WIND LOAD:**  
BASIC WIND SPEED: 100 MPH  
WIND LOAD IMPORTANCE FACTOR (Iw): 1.00  
WIND EXPOSURE: B  
INTERNAL PRESSURE COEFFICIENT: ±0.18
- DESIGN SEISMIC LOADS:**  
EQUIVALENT LATERAL FORCE PROCEDURE  
OCCUPANCY CATEGORY: II  
SEISMIC IMPORTANCE FACTOR (Ie): 1.0  
MAPPED SPECTRAL RESPONSE ACCELERATIONS:  
Ss: 0.314  
S1: 0.077  
SEISMIC SITE CLASS: E  
SPECTRAL RESPONSE COEFFICIENTS:  
Sds: 0.481  
Sd1: 0.179  
SEISMIC DESIGN CATEGORY: C  
BASIC STRUCTURAL SYSTEM: BEARING WALL SYSTEM  
BASIC SEISMIC FORCE RESISTIVE SYSTEM:  
LIGHT FRAMED WALLS SHEATHED WITH WOOD STRUCTURAL PANELS  
RESPONSE MODIFICATION FACTOR (R): 6.5  
SEISMIC RESPONSE COEFFICIENT (Cs): 0.074

**FOUNDATION NOTES (SOIL SUPPORTED)**

- FOUNDATIONS HAVE BEEN DESIGNED IN ACCORDANCE WITH A REPORT ENTITLED "GEOTECHNICAL REPORT, NEW APARTMENT BUILDING, BOYD AND OXFORD STREETS, PORTLAND, ME." PREPARED BY SUMMIT GEOENGINEERING SERVICES, DATED SEPTEMBER, 2013. THE RECOMMENDATIONS OF THE REPORT ARE PART OF THIS WORK. REFER TO THIS REPORT FOR SPECIFIC RECOMMENDATIONS.
- FOUNDATION DESIGN IS BASED ON SHALLOW SPREAD FOOTINGS BEARING ON COMPACTED CRUSHED STONE FULLY WRAPPED IN NON-WOVEN GEOTEXTILE FABRIC PER THE REQUIREMENTS OF THE GEOTECHNICAL REPORT. REFER TO THIS REPORT FOR SPECIFIC BEARING RECOMMENDATIONS.
- ALLOWABLE BEARING CAPACITY 1500 PSF.
- EXTEND BOTTOM OF EXTERIOR FOOTINGS AT LEAST 4.0 FEET BELOW THE FINAL EXTERIOR GRADE FOR PROTECTION AGAINST FROST.
- NO FILL FOR BUILDING SUPPORT SHALL BE PLACED UNTIL SUBGRADES HAVE BEEN OBSERVED AND APPROVED BY THE GEOTECHNICAL ENGINEER.
- REFERENCE THE GEOTECHNICAL REPORT FOR ALL EXCAVATION, BACKFILL, COMPACTION, CONSTRUCTION DEWATERING AND PERMANENT DRAINAGE REQUIREMENTS.
- SOILS EXPOSED AT THE BASE OF ALL SATISFACTORY FOUNDATION EXCAVATIONS SHOULD BE PROTECTED AGAINST ANY DETRIMENTAL CHANGE IN CONDITION, SUCH AS DISTURBANCE FROM RAIN OR FROST. SURFACE RUNOFF SHOULD BE DRAINED AWAY FROM THE EXCAVATIONS AND NOT BE ALLOWED TO POND. FOUNDATION EXCAVATIONS AND SHOULD BE ADEQUATELY PROTECTED FROM RAINFALL OR FREEZING CONDITIONS. GROUNDWATER SHOULD BE ANTICIPATED FOR EXCAVATIONS AND APPROPRIATE DEWATERING MEASURES SHALL BE EMPLOYED.
- EXCAVATIONS FOR BUILDING CONSTRUCTION SHALL BE IN ACCORDANCE WITH OSHA REQUIREMENTS. BRACED EXCAVATIONS SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF NEW HAMPSHIRE. DO NOT UNDERMINE EXISTING FOUNDATIONS OF ANY ADJACENT STRUCTURES. REFER TO THE GEOTECHNICAL REPORT FOR ADDITIONAL AND/OR MORE SPECIFIC REQUIREMENTS.

**CONCRETE NOTES**

- CONCRETE WORK SHALL CONFORM TO "ACI MANUAL OF CONCRETE PRACTICE", LATEST EDITION. THIS PUBLICATION IS AVAILABLE THROUGH THE AMERICAN CONCRETE INSTITUTE (248) 848-3800.
- ALL CONCRETE SHALL HAVE A 28-DAY COMPRESSIVE STRENGTH OF 3,500 PSI FOR FOOTINGS, WALLS AND SLABS U.N.O. EXTERIOR SLAB-ON-GRADE SHALL HAVE A 28-DAY COMPRESSIVE STRENGTH OF 5,000 PSI. ADDITIONAL CONCRETE MIX PERFORMANCE DATA INCLUDING AIR CONTENT, WATER-CEMENT RATIO, AGGREGATE SIZE, SLUMP, ETC. HAS BEEN INCLUDED IN THE PROJECT SPECIFICATIONS. SEE THE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- CONCRETE SHALL NOT BE PLACED IN WATER OR ON FROZEN GROUND.
- PROVIDE PVC SLEEVES WHERE PIPES PASS THROUGH EXTERIOR CONCRETE, OR SLABS.
- REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60 DEFORMED BARS AND SHALL BE DETAILED, FABRICATED AND PLACED IN ACCORDANCE WITH ACI 315, LATEST EDITION.
- WELDED WIRE FABRIC SHALL CONFORM TO ASTM A-185 AND BE PROVIDED IN FLAT SHEETS.
- FIBER REINFORCEMENT SHALL BE TYPE III SYNTHETIC VIRGIN HOMOPOLYMER POLYPROPYLENE FIBERS CONFORMING TO ASTM C1116.
- MINIMUM CONCRETE PROTECTIVE COVERING FOR REINFORCEMENT, UNLESS NOTED OTHERWISE, SHALL BE AS FOLLOWS:  
A) SURFACES CAST AGAINST AND PERMANENTLY IN CONTACT WITH EARTH, 3.0"  
B) FORMED SURFACES IN CONTACT WITH EARTH OR EXPOSED TO WEATHER #5 BARS, 5/8" DIAMETER WIRE, AND SMALLER, 1.5"  
#6 THROUGH #11 BARS, 2.0"  
C) SURFACES NOT IN CONTACT WITH EARTH OR EXPOSED TO WEATHER WALLS, SLABS, JOISTS #11 BARS AND SMALLER, 1.0"  
BEAMS, GIRDERS, AND COLUMNS; ALL REINFORCEMENT, 1.5"
- REINFORCEMENT SHALL BE CONTINUOUS AROUND CORNERS AND AT INTERSECTIONS. PROVIDE LAPPED BARS AT NECESSARY SPLICES OR HOOKED BARS AT DISCONTINUOUS ENDS. PROVIDE TENSION LAP SPLICES PER THE SCHEDULE DWG S200, FOR ALL REINFORCING UNLESS OTHERWISE SHOWN ON PLAN.
- WELDING OF REINFORCEMENT IS NOT PERMITTED.
- FOR ALL OPENINGS IN CONCRETE WALLS AND SLABS, PROVIDE SUPPLEMENTAL REINFORCING AROUND OPENING AS SHOWN ON THE CONTRACT DOCUMENTS TYPICAL DETAILS.
- CONSTRUCTION JOINTS SHOWN ON DRAWINGS ARE MANDATORY. OMISSIONS, ADDITIONS, OR CHANGES SHALL NOT BE MADE EXCEPT WITH THE SUBMITTAL OF A WRITTEN REQUEST TOGETHER WITH DRAWINGS OF THE PROPOSED JOINT LOCATIONS FOR APPROVAL OF THE STRUCTURAL ENGINEER. WHERE CONSTRUCTION JOINTS ARE NOT SHOWN, OR WHEN ALTERNATE LOCATIONS ARE PROPOSED, DRAWINGS SHOWING LOCATION OF CONSTRUCTION AND CONTROL JOINTS AND CONCRETE PLACING SEQUENCE SHALL BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR REVIEW PRIOR TO PREPARATION OF THE REINFORCEMENT SHOP DRAWINGS. CONCRETE SHALL BE PLACED WITHOUT HORIZONTAL CONSTRUCTION JOINTS EXCEPT WHERE SHOWN OR NOTED. VERTICAL CONSTRUCTION JOINTS AND STOPS IN CONCRETE BEAMS/GRADE BEAMS SHALL BE MADE AT MIDSPAN OR AT POINTS OF MINIMUM SHEAR, UNLESS NOTED OTHERWISE.
- SPACING OF CONSTRUCTION JOINTS, UNLESS NOTED OTHERWISE SHALL BE AS FOLLOWS:  
A) FOOTINGS AND WALLS MAX LENGTH 40'-0" NOR 15'-0" FROM ANY CORNER\*\*  
B) SLABS ON GRADE SEE FOUNDATION PLAN
- \*\* EXCEED ONLY WHERE INTERMEDIATE CONTRACTION JOINTS ARE PROVIDED. MINIMUM OF 72 HOURS SHALL ELAPSE BETWEEN ADJACENT CONCRETE PLACEMENTS.
- ANCHOR RODS SHALL BE HEADED RODS CONFORMING TO ASTM F1554, GRADE 36 KSI WELDABLE STEEL, UNLESS NOTED OTHERWISE ON DRAWINGS. ANCHOR RODS THAT ARE TO BE IN CONTACT WITH PRESSURE TREATED LUMBER SHALL BE HOT-DIPPED GALVANIZED.
- ALL GROUT BENEATH BASE PLATES & BEARING PLATES SHALL BE "5-STAR" 5000-PSI NON-SHRINK GROUT BY U.S. GROUT CORP.
- SLAB THICKNESSES INDICATED ON THE DRAWINGS ARE MINIMUMS. PROVIDE SUFFICIENT CONCRETE TO ACCOUNT FOR STRUCTURE DEFLECTION, SUBGRADE FLUCTUATIONS, AND TO OBTAIN THE SPECIFIED SLAB ELEVATION AT THE FLATNESS AND LEVELNESS INDICATED.

**STRUCTURAL STEEL NOTES**

- STRUCTURAL STEEL FABRICATION, ERECTION, AND CONNECTION DESIGN SHALL CONFORM TO AISC "SPECIFICATION FOR THE DESIGN FABRICATION, AND ERECTION OF STRUCTURAL STEEL" LATEST EDITION, AND THE "CODE OF STANDARD PRACTICE, LATEST EDITION.
- STRUCTURAL STEEL: STEEL PLATES, SHAPES, AND BARS, CONFORM TO ASTM A36 UNLESS NOTED OTHERWISE (U.N.O.). STRUCTURAL STEEL SHAPES DESIGNATED ON THE DRAWINGS FOR WIDE-FLANGE SECTIONS: ASTM A992 (ASTM A572 GRADE 50 WITH SPECIAL REQUIREMENTS PER AISC TECHNICAL BULLETIN #3 DATED MARCH, 1997)
- STRUCTURAL TUBING: CONFORM TO ASTM A500 GRADE B46 KSI.
- FIELD CONNECTIONS SHALL BE BOLTED USING ASTM A325N HIGH STRENGTH BOLTS (U.N.O.) EXCEPT WHERE SLIP CRITICAL CONNECTIONS ARE REQUIRED AND NOTED BY A325 (SC) ON THE DRAWINGS. PROVIDE SLIP CRITICAL (SC) CONNECTIONS AT ALL MOMENT CONNECTIONS, BRACED FRAMES, RELIEVING ANGLES AND AS OTHERWISE NOTED. USE A490 BOLTS WHERE INDICATED.
- WHERE WELDING IS INDICATED, ALL WELDING SHALL CONFORM TO AWS D1.1- LATEST EDITION. ELECTRODES SHALL BE CONFORM TO AWS A5.1 E70XX SERIES WITH PROPER ROD TO PRODUCE OPTIMUM WELD (LOW HYDROGEN).
- SEE CONCRETE NOTES AND DRAWINGS FOR ANCHOR BOLT INFORMATION, TYP.
- PROVIDE 1/4" THICK LEVELING PLATE UNDER ALL COLUMN BASE PLATES UNLESS OTHERWISE NOTED. LEVELING PLATES SHALL BE SET AND GROUTED PRIOR TO ERECTING COLUMNS.
- PROVIDE ALL MISCELLANEOUS ANGLES, PLATES, ANCHORS, BOLTS, ETC., SHOWN ON ARCHITECTURAL DRAWINGS FOR SUPPORT OF BLOCKING, PARAPETS, FINISHES, ETC. COORDINATE WITH MISCELLANEOUS METAL FABRICATOR TO ENSURE COMPLETE COVERAGE OF ALL ITEMS.

**MASONRY NOTES**

- ALL MASONRY CONSTRUCTION SHALL CONFORM TO ACI 530.1, LATEST EDITION.
- ALL CONCRETE MASONRY UNITS SHALL BE ASTM C90 GRADE N, TYPE I STANDARD WEIGHT BLOCKS INCLUDING STRETCHERS AND CORNER BLOCKS. MINIMUM PRISM STRENGTH OF BLOCK SHALL BE F'M = 1500 PSI IN 28 DAYS.
- MORTAR SHALL CONFORM TO ASTM SPECIFICATION C270, TYPE M OR S
- GROUT SHALL CONFORM TO ASTM-C476
- REINFORCING FOR BOND BEAMS, LINTEL BLOCKS AND VERTICAL WALL REINFORCING SHALL BE BILLET STEEL CONFORMING TO ASTM A615, GRADE 60
- HORIZONTAL JOINT REINFORCING SHALL BE DUR-O-WAL TRUSS DESIGN, STANDARD CLASS MILL GALVANIZED WITH 3/16" DIAMETER SIDE RODS AND 9 GAUGE CROSS TIES, UNO. REINFORCING SHALL BE PLACED IN MASONRY WALLS AT EVERY SECOND BLOCK COURSE.
- CONCRETE MASONRY UNITS SHALL BE LAID IN RUNNING BOND UNLESS OTHERWISE NOTED. PROVIDE FULL MORTAR COVERAGE ON ALL WEBS AND FACE SHELLS. PROVIDE CORNER BLOCKS AND END BLOCKS TO FINISH ALL 90 DEGREE CORNERS AND WALL OPENINGS.
- PROVIDE LINTELS AT ELEVATOR DOOR PENETRATIONS: 8"H W/ 2#5 BOT CONT IN FULL GROUT, 8" BEARING EACH END.
- STANDARD LAP LENGTH OF GRADE 60 MASONRY REINFORCING BARS SHALL BE 48 BAR DIAMETERS FOR #5 AND SMALLER. PROVIDE CORNER BARS TO MATCH HORIZONTAL REINFORCEMENT.
- CELLS TO BE GROUTED SHALL BE 2-CELL BLOCK. ALIGN CELLS TO MAINTAIN A CLEAR UNOBSTRUCTED, CONTINUOUS VERTICAL CHASE. CELLS MUST BE KEPT CLEAN OF PROTRUSIONS OR FINIS OF MORTAR. FILL CELLS OF MASONRY UNITS AND WALL CAVITIES WHERE INDICATED WITH 2500 PSI GROUT. MAXIMUM GROUT LIFT WITHOUT CLEAN-OUTS SHALL BE 5'-0". HIGH LIFT GROUTING SHALL CONFORM TO CODE REQUIREMENTS WITH A MINIMUM CONTENT OF 8 SACKS PER CUBIC YARD. SUPPORT ALL VERTICAL BARS IN CENTER OF GROUTED CELLS WITH VERTICAL BAR POSITIONER.
- FIELD PENETRATIONS THROUGH BLOCK WALLS SHALL NOT BE MADE THROUGH BOND BEAMS, LINTELS OR GROUTED CELLS.

**WOOD TRUSS NOTES:**

**GENERAL**

- TRUSSES SHALL BE DESIGNED, FABRICATED, ERECTED, AND BRACED IN ACCORDANCE WITH WTCA/TPI BCSI 1-LATEST BOOKLET AS NOTED IN THE NOTES AND SPECIFICATIONS AND ALL OTHER APPLICABLE CODES.
- ERECTION AND TEMPORARY BRACING SHALL CONFORM TO WTCA/TPI BCSI 1-LATEST.

**DESIGN**

- SEE FRAMING PLANS FOR TRUSS ORIENTATION AND LOCATIONS.
- SEE ARCHITECT FOR ALL TRUSS PROFILES AND DIMENSIONS.
- TEMPORARY BRACING SHALL BE LEFT IN PLACE AND SERVE AS PART OF THE PERMANENT BRACING SYSTEM.
- PERMANENT CONTINUOUS LATERAL BRACING, INDICATED BY THE TRUSS DESIGNER, WILL BE REVIEWED DURING THE SHOP DRAWING PHASE. DIAGONAL STRUTS AND CONNECTIONS INDICATED ON THESE DRAWINGS SHALL BE APPLIED AT LOCATIONS GIVEN BY THE TRUSS DESIGNER.
- TRUSS DESIGNER SHALL DESIGN TRUSS TO MINIMIZE CONTINUOUS LATERAL BRACING REQUIRED TO BE INSTALLED IN THE FIELD.
- TRUSS DESIGNER SHALL PROVIDE ALL CONNECTION DESIGN FOR TRUSS TO TRUSS CONNECTIONS.
- ALL TRUSSES SHALL BE DESIGNED FOR UNBALANCED LOADS.
- PROVIDE GABLE END TRUSSES WITH VERTICALS AT 24" O.C. MAX. CALCULATE WIND LOADS PERPENDICULAR TO TRUSS MEMBERS PER CRITERIA INDICATED IN DESIGN LOADS SECTION.

**WOOD TRUSS NOTES (CONTINUED):**

**SUBMITTALS**

- TRUSS MANUFACTURER SHALL SUBMIT A TRUSS PLACEMENT DRAWING INDICATING THE FOLLOWING.  
A. SLOPE  
B. SPAN  
C. SPACING  
D. TRUSS NUMBER THAT CORRESPONDS TO TRUSS DESIGN DRAWING.  
E. LOCATION OF PERMANENT LATERAL BRACING.
- TRUSS DESIGN DRAWINGS/CALCULATIONS STAMPED BY REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF MAINE.
- TRUSS DESIGN DRAWINGS SHALL INCLUDE THE FOLLOWING:  
A. SLOPE, SPAN, AND SPACING.  
B. LOCATION OF ALL JOINTS.  
C. REQUIRED BEARING WIDTHS.  
D. CHORD AND WEB MEMBER SIZE, GRADE, AND SPECIES.  
E. CALCULATED HORIZONTAL DEFLECTION AND VERTICAL DEFLECTION.  
F. MAXIMUM AXIAL AND COMPRESSION FORCES IN EA OF THE TRUSS MEMBERS TO ENABLE THE BUILDING DESIGNER TO REVIEW THE SIZE, CONNECTIONS, AND ANCHORAGE OF PERMANENT CONTINUOUS LATERAL BRACING.  
G. REQUIRED PERMANENT TRUSS BEARING LOCATIONS.

**TIMBER NOTES**

- ALL TIMBER FRAMING SHALL BE IN ACCORDANCE WITH THE AITC TIMBER CONSTRUCTION MANUAL - LATEST EDITION AND THE AF & PA NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION (NDS) LATEST EDITION.
- INDIVIDUAL TIMBER FRAMING MEMBERS SHALL BE VISUALLY GRADED. MINIMUM GRADE NO1/NO2 SPRUCE-PINE-FIR KILN DRIED TO 19% MAXIMUM MOISTURE CONTENT UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
- ENGINEERED WOOD PRODUCTS SHALL BE AS SPECIFIED ON THE DRAWINGS. REFER TO MANUFACTURER'S LITERATURE FOR PROPER HANDLING AND INSTALLATION GUIDELINES. MANUFACTURER AND PRODUCT SHALL BE:  
**I-LEVEL:** I-JOIST (TJI), PARALLAM (PSL), MICROLAM (LVL), TIMBERSTRAND (LSL)  
**BOISE:** I-JOIST (BCI), VERSALAM (LVL)
- PRESSURE TREATED LUMBER SHALL BE USED FOR SILL MEMBERS, EXTERIOR EXPOSURE, OR WHERE SHOWN ON THE DRAWINGS. TIMBER SHALL BE SOUTHERN YELLOW PINE TREATED WITH CCA OR ACQ TO 0.4 #/CF IN ACCORDANCE WITH AWP C-18. ACZA IS STRICTLY PROHIBITED.
- ALL ROOF AND WALL SHTG SHALL BE APA PERFORMANCE-RATED. WALL SHTG SHALL BE PLYWOOD PRODUCT. NOT S.O.B. SHTG SHALL BE NAILED TO THE FRAMING AS FOLLOWS, U.N.O.:  
A. ROOFS: 8d NAILS AT 6" O.C. AT SUPPORTED PANEL EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS.  
B. WALLS: 8d NAILS AT 6" O.C. AT SUPPORTED PANEL EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. SEE DWG S302 FOR SHTG ATTACHMENT AT SHEARWALLS.

- FLOOR SHTG SHALL BE 3/4" TONGUE AND GROOVE, ADVANTECH PANELS. GLUE AND NAIL TO FLOOR FRAMING WITH 8d RING SHANK NAILS AT 6" O.C. AT SUPPORTED PANEL EDGES, 12" O.C. AT INTERMEDIATE SUPPORTS.
- ALL BUILT-UP BEAMS AND COLUMNS SHALL BE NAILED AS FOLLOWS (FASTENING IN EACH PLY):

**UNIFORMLY LOADED BEAMS:**

BEAM DEPTH <16" - 2 ROWS OF 16d NAILS AT 12" O.C., STAGGERED  
BEAM DEPTH >=16" - 3 ROWS OF 16d NAILS AT 12" O.C., STAGGERED  
NOTE: SIDE LOADED BEAMS REQUIRE ADDITIONAL FASTENING. SEE DETAILS.

**COLUMNS:**

2-10d NAILS AT 6" O.C.

- ALL TIMBER CONNECTION HARDWARE (JOIST HANGERS, POST BASES, SHEARWALL HOLD-DOWNS, ETC) SHALL BE AS INDICATED ON THE DRAWINGS AND MANUFACTURED BY SIMPSON STRONG-TIE. ALL CONNECTION HARDWARE SHALL BE HOT-DIPPED GALVANIZED G-90 (U.N.O.). CONNECTION HARDWARE USED IN CONJUNCTION WITH PRESERVATIVE TREATMENT SHALL BE GALVANIZED G185 (ZMAX.) USE FASTENERS & HANGERS OF SAME MATERIAL & COATING. REFER TO MANUFACTURER'S LITERATURE FOR PROPER HANDLING AND INSTALLATION GUIDELINES.
- FASTENERS USED IN CONJUNCTION WITH P.T. LUMBER, BUT NOT AT TIMBER CONNECTION HARDWARE REFERENCED IN NOTE 8, SHALL BE POST HOT DIPPED GALVANIZED (ASTM A153.)
- FASTENING NOT SPECIFIED SHALL CONFORM WITH IBC TABLE 2304.9.1. NAIL FASTENERS SHALL MEET THE REQUIREMENTS OF ASTM F1667, UNLESS NOTED OTHERWISE, NAILS REFERENCED ON DRAWINGS ARE TO BE COMMON NAILS WITH DIMENSIONS AS FOLLOWS.  
6d: 2" LONG BY 0.113" DIAMETER SHANK WITH 0.266" DIAMETER HEAD  
8d: 2 1/2" LONG BY 0.131" DIAMETER SHANK WITH 0.281" DIAMETER HEAD  
10d: 3" LONG BY 0.148" DIAMETER SHANK WITH 0.312" DIAMETER HEAD  
12d: 3 1/4" LONG BY 0.148" DIAMETER SHANK WITH 0.148" DIAMETER HEAD  
16d: 3 1/2" LONG BY 0.162" DIAMETER SHANK WITH 0.162" DIAMETER HEAD  
20d: 4" LONG BY 0.192" DIAMETER SHANK WITH 0.406" DIAMETER HEAD  
30d: 4 1/2" LONG BY 0.207" DIAMETER SHANK WITH 0.438" DIAMETER HEAD
- IF PANELIZED CONSTRUCTION IS UTILIZED, VERTICAL JOINTS IN WALL PANELS SHALL BE FASTENED TOGETHER W/10d NAILS @ 12" O.C., EXCEPT AT SHEARWALLS. REFER TO THESE DRAWINGS FOR FASTENING AT SHEARWALLS.
- EXTERIOR PANELS SUPPORTING SIDING SHALL BE FASTENED TO WALL STUDS PER DIVISION 7 PROJECT SPECIFICATIONS.



14 BAXTER BLVD  
PORTLAND, ME 04101  
P: 207.773.4753

307 CUMBERLAND AVE  
PORTLAND, ME 04101  
P: 207.553.7777

217 COMMERCIAL STREET, STE 200  
PORTLAND, MAINE 04101  
207.772.1950 V. F. 207.772.0712

75 YORK ST.  
PORTLAND, ME 04101  
P: 207.879.1838

400 COMMERCIAL ST.  
SUITE 404  
PORTLAND, ME 04101  
P: 207.772.2891

190 US ROUTE ONE  
PMB 346 FALMOUTH, ME  
04105  
P: 207.847.3445

**PRICING DOCUMENTS**

Project: BAYSIDE ANCHOR PHDC & Avesta  
81 East Oxford Street  
Portland, ME

Drawing:	General Notes	Drawn by:	APP
Scale:	Noted	Date:	8/28/15
Date:	8/28/15	Revised:	