

CITY OF PORTLAND  
 FIRE PREVENTION BUREAU  
 380 Congress Street, Portland, Maine 04101  
 fireprevention@portlandmaine.gov  
 (207) 874-8400

**NOTICE OF VIOLATION AND ORDER TO CORRECT**

June 23, 2017

<b>Responsible Party 1:</b> Noddin Richard 679 DEERWANDER RD HOLLIS CENTER, ME 04042		
<b>Location</b> 46 SMITH ST	<b>CBL</b> 022 J013001	<b>Inspection Date</b> 6/9/2017
<b>Inspector</b> Daniel Small	<b>Inspection Type</b> FP Routine Inspection	<b>Status</b> Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

**You must send this form to the Fire Prevention Bureau no later than 7/15/2017.**

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
<b>NFPA 101- 7.5.1.1 EXIT OBSTRUCTED;</b> Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to not less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4. Debris in front and rear stairways	IMMEDIATELY remove all obstructions from the exits. Your signature below indicates that all obstructions have been removed and will not be replaced.
<b>NFPA 101- 7.2.1.8.1 FIRE DOORS MUST BE SELF- OR AUTO-CLOSING;</b> A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3. Several doors without self closing or adjusted hinges	____/____/____
<b>NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED;</b> In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements. 1st floor apartment-1 missing and 1 inoperative	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.

Violation	Proposed Date of Completion
<p><b>NFPA 30- TABLE 9.6.2.1 FLAMMABLE/COMBUSTIBLE LIQUIDS STORAGE EXCEED LIMIT;</b> See NFPA 30 Table 9.6.2.1 for special occupancy limits for flammable and combustible liquid storage. Gas can and gas lawn mower located under rear deck/exit</p>	<p>IMMEDIATELY remove all excess flammable/combustible material from the interior of the structure. Your signature below indicates that all excess material has been removed, will not be replaced, and will be properly disposed of or stored elsewhere.</p>
<p><b>NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS;</b> Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating. 3rd floor rear stairway has wires hanging from ceiling</p>	<p>___ / ___ / ___</p>
<p><b>NFPA 70- 590.6 EXTENSION CORDS;</b> Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities. 3rd floor apartment has extension cord to refrigerator</p>	<p>___ / ___ / ___</p>
<p><b>NFPA 70 MISSING BOX COVERS;</b> Refer to NFPA 70, National Electrical Code, on standards for missing box covers. Several in basement</p>	<p>___ / ___ / ___</p>
<p><b>FINAL DATE OF COMPLETED VIOLATION(S)</b></p>	<p>___ / ___ / ___</p>
<p><b>FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)</b></p>	<p>___ / ___ / ___</p>

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

**VIOLATOR CERTIFICATION**

*I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.*

*I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.*

*If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.*

\_\_\_\_\_  
Date

\_\_\_\_\_  
Responsible Party

\_\_\_\_\_  
Date

\_\_\_\_\_  
Responsible Party

**SEEN AND AGREED**

\_\_\_\_\_  
Date

\_\_\_\_\_  
Fire Prevention Bureau