

ROOM FINISH GENERAL NOTES

- 1 ALSO SEE INTERIOR ELEVATIONS FOR GRAPHIC DEPICTIONS OF EXTENT OF FINISHES
- 2 INSTALL MOISTURE RESISTANT GWB IN BASEMENTS AND ALL AREAS WHERE PLUMBING FIXTURES EXIST
- 3 CLOSETS SHALL BE FINISHED AS THE ROOMS THEY SERVICE
- 4 ALL SPACES DESIGNATED AS CLOSET OR 'CL.' ARE TO RECEIVE ONE CLOTHING ROD 5'-2" AFF AND ONE 12" WIRE SHELF ABOVE THE ROD ALONG THE WALL OPPOSITE THE DOOR UNLESS NOTED OTHERWISE:  
ALL SPACES DESIGNATED AS LINEN CLOSETS (LIN) OR PANTRY (PAN) ARE TO RECEIVE FOUR 12" WIRE SHELVES SPACED AT 1'-6" OC STARTING AT FINISH FLOOR.  
ALL LAUNDRY CLOSETS ARE TO RECEIVE ONE 12" WIRE SHELF AT 4'-6" A.F.F.
- 5 PROVIDE APPROPRIATE BLOCKING IN WALLS OF ALL BATHROOMS BEHIND FIXTURES, PARTITIONS AND ACCESSORIES. PROVIDE BLOCKING FOR GRAB BARS IN WALLS OF 1 ST FLOOR AS WELL AS TOWNHOUSE BATHROOMS, SEE SHEET A2.3
- 6 PROVIDE APPROPRIATE BLOCKING IN WALLS FOR DOOR STOPS
- 7 BOTTOM EDGE OF GWB ON WALL SURFACES TO BE HELD UP 1/2" FROM CONCRETE FLOOR SURFACES
- 8 PROVIDE VINYL TRANSITIONS STRIPS AT ALL FLOOR TRANSITIONS
- 9 UNLESS OTHERWISE NOTED IN DRAWINGS THE TYPICAL WALL TYPE IS N.W. ALL OTHER PARTITION TYPES WILL BE INDICATED.
- 10 INSTALL MOISTURE RESISTANT GWB IN WALKER DRESSER CLOSETS
- 11 INSTALL 1/4" PLYWD. UNDERLAY AT ALL AREAS WHERE LINOLEUM IS TO BE INSTALLED.

1