FRAMING PLAN SYMBOLS KEY	
▫	CFMF POST
○	STEEL COLUMN
(X)	NUMBER OF CFMF STUDS IN POST BELOW
A	COLUMN ABOVE THIS LEVEL
C	COLUMN CONTINUOUS THROUGH THIS LEVEL
◄	JOIST BEARING
—✓—	CONTINUOUS JOIST WITH INTERMEDIATE BEARING
⊢	FLUSH FRAMED JOIST BEARING WITH HANGER
	BEARING WALL BELOW
	SHEAR WALL
"X"T	NUMBER OF TRIM STUDS UNDER HEADER
"X"K	NUMBER OF KING STUDS ADJACENT TO HEADER

LEGEND	
DROPPED BEAM	- - - - -
FLUSH BEAM	———

LAYOUT FLOOR FRAMING TO AVOID CONFLICTS WITH PLUMBING.

MEZZANINE FRAMING PLAN

0' 1' 5' 10'

SCALE 1/4"=1'-0"

NOTES:

1. SEE SHEET S1.0 FOR GENERAL STRUCTURAL NOTES
2. FLOOR SHEATHING SHALL BE 3/4" -TYP. SEE GENERAL NOTES FOR MORE INFO.
3. USE MIN. #10 SCREWS AT ALL CFMF CONNECTIONS -TYP. UNO
4. TEMPORARY SHORING OF ALL WORK BY CONTRACTOR -TYP.

FOR PERMIT

Structural Integrity Consulting Engineers, Inc.

77 Oak Street
Portland, ME, 04101
p. 207-774-4614
f. 866-793-7835
www.structuralinteg.com

BUILD WITH CONFIDENCE

© 2017 Structural Integrity Consulting Engineers, Inc.

SI # 17-0113

STATE OF MAINE
AARON C. JONES
No. 10966
LICENSED
PROFESSIONAL ENGINEER
May 12th, 2017

Date: 08/02/17

© 2017 RYAN SENATORE ARCHITECTURE

RISING TIDE BREWING - EXPANSION

103 FOX STREET
PORTLAND, MAINE 04101

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS ST. SUITE 304
PORTLAND, MAINE 04101
207-650-6414
senatorearchitecture.com

CONSULTANTS:

STRUCTURAL:
Structural Integrity
77 Oak Street
Portland, ME 04101
207-774-4614

REVISIONS:

DATE:	12 April, 2017
PROJECT No.	1718
DRAWN BY:	BDH
CHECKED BY:	ACJ
SCALE:	AS NOTED

SHEET TITLE:

MEZZANINE FRAMING PLAN

S1.1