



SYMBOL	QTY.	DESCRIPTION	MANUFACTURER	LOCATION	REMARKS
F1	54	FIELD CURVABLE BLUE LED STRIP LIGHT IN 1/2" INCREMENTS. LINE VOLTAGE (REQUIRING NO REMOTE DRIVER), UP TO 100 LINEAR FEET ON ONE CIRCUIT, INTEGRATED MOUNTING BRACKET, END TO END CONNECTIONS, ELY DIMMING CAPABILITY	PHILIPS T8D	SALES AREA CIRCULAR COVE LIGHTING	
F2	14	NOM. 3.5" DIAMETER RECESSED ADJUSTABLE 20W MR 16 CERAMIC METAL HALIDE GX10 ACCENT LIGHT, WHITE POLISHED TRIM, SQUARE LENS, ELECTRONIC BALLAST	ELEMENT LIGHTING ESRFF-C-A-N-O-W-ABRISA SQUARE LENS	SALES GRP. CEILING	
F3	10	PAINTED 7" DIAMETER COMPACT FLUORESCENT DOWNLIGHT - WHITE REFLECTOR W/ HAZE FINISH (NO TRIM)	COOPER C7042-E-EDM32-7001-H-WF	SALES AREA	1. LIGHTS WITH 'NL' DESIGNATION, WIRE THROUGH NIGHTLIGHT CIRCUIT 2. LIGHTS WITH 'EM' DESIGNATION PROVIDE W/ EMERGENCY BALLAST
F3a	18	FIXED 7" DIAMETER COMPACT FLUORESCENT DOWNLIGHT - REFLECTOR W/ HAZE FINISH (NO TRIM)	COOPER C7042-E-EDM32-7001-H	SALES AREA	1. LIGHTS WITH 'NL' DESIGNATION, WIRE THROUGH NIGHTLIGHT CIRCUIT 2. LIGHTS WITH 'EM' DESIGNATION PROVIDE W/ EMERGENCY BALLAST
F4	2	CANOPY MOUNTED CMH MR16 MONOPPOINT ACCENT LIGHT, LOCKING TILT AND ROTATION, ON-OFF SWITCH, ALUMINUM SOFT FOCUS LENS AND HOLDER, SQUARE MONOPPOINT CANOPY ACCESSORY, WHITE FINISH	HALO STARS E50519-20CMH-P-111-LMS16-1973 CANOPY	SALES AREA ACENT LIGHT (WHITE CEILING)	
F7	26	CANOPY MOUNTED CMH MR16 MONOPPOINT ACCENT LIGHT, LOCKING TILT AND ROTATION, ON-OFF SWITCH, ALUMINUM SOFT FOCUS LENS AND HOLDER, SQUARE MONOPPOINT CANOPY ACCESSORY, WHITE FINISH	HALO STARS E50519-20CMH-P-111-LMS16-1973 CANOPY	SALES AREA COVE LIGHTING	
F7a	0	(2) LAMP ADJUSTABLE STAGGER LINEAR T5 FLUORESCENT STRIP WITH 6" OVERLAP T5 STANDARD OUTPUT LAMPS, (7a) INTEGRAL ELECTRONIC BALLAST, LEVEL, NOM. 4' LENGTH (7a) NOM. 3' LENGTH)	BARTELO F7- BC128-28/6 LAMP: GE T28W/9/SPX35 LAMP: GE T28W/9/SPX35 LAMP: GE T28W/9/SPX35	SALES AREA COVE LIGHTING	
F8	33	NOM. 4" DIAMETER LOW VOLTAGE PINHOLE FIXED DOWNLIGHT WITH LOW PROFILE HOUSING AND INTEGRAL MAGNETIC TRANSFORMER, DEBATED WATTAGE LABEL, 20W MAX	HALO H4981-1419W-DEBATED WATTAGE LABEL, 20W LAMP: PHILIPS 20MRC-16/INC/NFL24	SALES AREA GRP. MWU SOFFITS ABOVE MWU	1. LIGHTS WITH 'NL' DESIGNATION, INSTALL WITHOUT LAMP'S 2. CUSTOM PAINT PINHOLE TRIM AND BAFFLE ORANGE TO MATCH P.3
F9	4	SEMI-RECESSED COMPACT FLUORESCENT DOWNLIGHT WITH DECORATIVE OPAL GLASS TRIM	LOUIS POULSEN 'BALLERUP' BAL-1/18W/CF GX24q-2/120-277V-WHT	SALES AREA SERVICE COUNTER TASK LIGHTING	
F10	13	FIXED 6" DIAMETER COMPACT FLUORESCENT OPEN WALL WASHER - WHITE PAINTED SELF FLANGED REFLECTOR W/ HAZE FINISH, DEBATED WATTAGE LABEL FOR 32W MAX	COOPER OS142-E-EDM32-6111-H-WF DBL REFLECTOR MODEL: OS142-E-EDM32-6121-H-WF	SALES/SERVICE AREA WHITE CEILING	1. LIGHTS WITH 'EM' DESIGNATION PROVIDE W/ EMERGENCY BALLAST 2. LIGHTS WITH 'A' DESIGNATION PROVIDE DBL REFLECTOR MODEL