

GENERAL CONDITIONS

THE AMERICAN INSTITUTE OF ARCHITECTS "GENERAL CONDITIONS OF CONTRACTS FOR CONSTRUCTION" AND SUPPLEMENTAL CONDITIONS REQUIREMENTS (CURRENT EDITIONS) SHALL RELATE TO THE WORK OF THE PROJECT AND IS HEREBY MADE A PART OF THESE CONTRACT DRAWINGS AS THOUGH FULLY CONTAINED.

DRAWINGS AND SPECIFICATIONS ARE INTENDED TO BE COMPLEMENTARY. SPECIFIC INFORMATION MAY BE FOUND IN EITHER OR BOTH.

THE CONTRACTOR SHALL LAY OUT WORK IN CONFORMITY WITH REQUIREMENTS OF ESTABLISHMENT AND MAINTENANCE OF ALL LINES AND DIMENSIONS BEFORE DOING ANY WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER RECORDING OF ALL LINES AND DIMENSIONS AND NOTIFY THE DESIGNER OF ANY DISCREPANCIES AND RESULTING ERRORS CAUSED BY THE FAILURE OF THE CONTRACTOR(S) TO EXERCISE SUCH PRECAUTION SHALL NOT BE CONSIDERED SUBSEQUENTLY AS A BASIS FOR ANY ADDITIONAL COMPENSATION.

IF ANY DISCREPANCIES, ERRORS, OR OMISSIONS ARE DISCOVERED IN THE CONTRACT DOCUMENTS, CONTACT THE STORE DESIGNER BEFORE PROCEEDING WITH RELATED WORK. OTHERWISE, THE CORRECTION OF SUCH ITEMS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR(S). CONTRACTOR(S) SHALL VERIFY LANDLORD'S PLACEMENT OF WALL STUDS AND ADVISE LANDLORD AND OWNER OF DISCREPANCIES IMMEDIATELY. FAILURE TO NOTIFY LANDLORD OF DISCREPANCIES SHALL BE DEEMED AS ACCEPTANCE AND CONSENT BY THE CONTRACTOR(S) TO THE WORK. DISCREPANCIES SHALL BE IN STRICT ACCORDANCE WITH THE ORDINANCES, STATE AND LOCAL BUILDING CODES, AND STANDARDS.

LATEST EDITION. ALL PERMITS, INSPECTIONS AND LICENSES NECESSARY FOR PROPER EXECUTION OF THE WORK SHALL BE SECURED AND PAID FOR BY THE CONTRACTOR(S) INVOLVED.

THE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR FULLY FAMILIARIZING HIMSELF WITH THE LANDLORD'S TENANT HANDBOOK AND DESIGN CRITERIA. ANY CONFLICTS BETWEEN "WORKING DRAWINGS" AND LANDLORD DIRECTION MUST BE BROUGHT TO THE ATTENTION OF THE STORE DESIGNER BEFORE WORK BEGINS.

ALTERATIONS:

A. BARRICADE - THE GENERAL CONTRACTOR SHALL PROVIDE BARRICADE.

B. TEMPORARY TRASH STORAGE AND REMOVAL - THE GENERAL CONTRACTOR(S) SHALL PROVIDE TRASH STORAGE AND REMOVAL FROM THE SITE OF CONSTRUCTION OF DEMOLITION DEBRIS AND SHALL PAY ALL COSTS THAT ARISE FROM SUCH PROVISION.

THE CONTRACTOR(S) SHALL USE DIMENSIONS ONLY. DO NOT SCALE PLANS. ALL DIMENSIONS ARE TO FINISHED FACE UNLESS OTHERWISE NOTED.

ALL WOOD FRAMING, BLOCKING, ETC. TO BE FIRE RETARDANT.

NO WOOD OR COMBUSTIBLE MATERIAL OF ANY KIND SHALL BE USED ABOVE THE 10' CEILING.

UPON COMPLETION OF WORK GENERAL CONTRACTOR IS TO OBTAIN CERTIFICATION OF COMPLETION FROM BUILDING DEPARTMENT AND/OR OTHER AUTHORITIES FOR PROVISION OF WORK. ANY SUBMIT WORK TO BE SUBJECT LANDLORD BECAUSE OF OPERATIONS BEING CARRIED OUT ADJACENT TO OR ABOVE. SHALL BE COVERED, BOARDED UP OR SUBSTANTIALLY ENCLOSED WITH ADEQUATE PROTECTION. ALL FORMS OF PROTECTION SHALL BE CONSTRUCTED IN SUCH A MANNER SUCH THAT, UPON COMPLETION, THE ENTIRE WORK SHALL BE DELIVERED TO THE TENANT AND OWNER IN PROPER WHOLE AND UNBLEMISHED CONDITION.

13. MATERIAL SUBSTITUTIONS: MANUFACTURER'S NAMES ARE LISTED HEREIN TO ESTABLISH A STANDARD. THE PRODUCTS OF OTHER MANUFACTURERS WILL BE ACCEPTABLE IF APPROVED BY THE TENANT'S STORE DESIGNER.

14. MATERIALS: RECOMMENDED BY THE MANUFACTURER. ALL LIQUE MATERIALS USED SHALL BE NEW AND FREE FROM ANY DEFECTS. ALL LIKE MATERIALS USED SHALL BE OF THE SAME MANUFACTURER AND QUALITY UNLESS OTHERWISE SPECIFIED.

WORKMANSHIP: ALL WORK UNDER THIS CONTRACT SHALL BE PERFORMED BY COMPETENT WORKMEN AND EXECUTED IN A NEAT AND WORKMANLIKE MANNER. ALL MATERIALS AND WORKMANSHIP SHALL BE GUARANTEED FOR ONE YEAR AFTER THE DATE OF ACCEPTANCE OF THE SPACE BY THE TENANT.

15. SHOP DRAWINGS AND CHANGING DATA: ALL SHOP DRAWINGS AND EQUIPMENT AND MATERIALS AND CHANGING DATA MUST BE SUBMITTED IN ACCORDANCE WITH THE SPECIFICATIONS AND CHANGING DATA TO THE MANUFACTURER AND APPROVED BY THE MANUFACTURER AND THE CONTRACTOR(S) BEFORE THE WORK BEGINS.

16. DELAY OR CHANGES DURING CONSTRUCTION: ONE (1) SET OF REPRODUCTION REQUIRED FOR EACH SUBMITTAL. ALL SUBMITTALS TO BE SENT TO: RICHARD M. COLE AND ASSOCIATES, 15 SOUTH 3RD STREET, PHILADELPHIA PA 19106.

ALL WELDING TO THE LANDLORD'S STRUCTURE MUST BE APPROVED IN WRITING BY THE LANDLORD'S REPRESENTATIVE.

DESIGN LOADS: LOADS AND CODE RESTRICTIONS FOR ALL DESIGN CONSIDERATIONS SHALL CONFORM TO ALL APPLICABLE ORDINANCES, STATE AND LOCAL BUILDING CODES, LATEST EDITION.

18. THE TENANT'S STORE DESIGNER HAS NOT BEEN RETAINED TO SUPERVISE CONSTRUCTION. THE GENERAL CONTRACTOR SHALL SUPERVISE, COORDINATE & SCHEDULE THE VARIOUS TRADES THROUGHOUT THE PROJECT.

19.

1. THIS SECTION IS INCLUDED FOR GENERAL REFERENCE OF WORK TO BE REMOVED BY THE CONTRACTOR(S).

2. DEMOLITION INCLUDES THE REMOVAL OF EXISTING INTERIORS, IF REQUIRED, BUT NOT LIMITED TO INTERIOR PARTITIONS, CABINETS, SUSPENDED CEILINGS, ETC. AS REQUIRED BY THE CONTRACTOR(S) AND AS REQUIRED BY THE MANUFACTURER. ALL FLOOR SURFACES AND CONCEALED ABOVE CEILINGS: ALL ABANDONED DUCTWORK, LIGHTS, DIFFUSERS, ETC. SHALL BE REMOVED.

3. THE CONTRACTOR(S) SHALL COOPERATE AND COORDINATE WITH THE LANDLORD, THE OWNER OF THE ADJACENT BUILDINGS AND THE OWNER, IN SCHEDULING WORK IN ORDER TO CAUSE THE LEAST INCONVENIENCE TO PERSONNEL, AND PROPERTY.

4. THE CONTRACTOR(S) SHALL ARRANGE WITH THE LANDLORD A CONVENIENT TIME TO PERFORM DEMOLITION WORK AND INSTALL TEMPORARY PROTECTED MEANS OF EGRESS FROM REQUIRED EXITS, INCLUDING TEMPORARY LIGHTING AND SAFETY DEVICES, ALL IN ACCORDANCE WITH GOVERNING STATE ORDINANCES AND LOCAL CODES AND LANDLORD REQUIREMENTS.

5. SEE NOTE 2 "CONCRETE"

6. NO EXPLOSIVES ARE ALLOWED FOR DEMOLITION WORK.

7. THE CONTRACTOR SHALL PROTECT ALL EXISTING BUILDING AREAS NOT SCHEDULED FOR DEMOLITION, AND SHALL BE RESPONSIBLE FOR THE COST OF THE REPAIRS OF ANY ACCIDENTAL DAMAGE HE INFLECTS UPON THE EXISTING BUILDING OR UTILITIES. IF THE CONTRACTOR BELIEVES THAT DAMAGE TO THE EXISTING BUILDING IS UNAVOIDABLE, HE MUST SUBMIT A WRITTEN NOTIFICATION OF THIS BEFORE THE DAMAGES OCCUR. IN THE ABSENCE OF WRITTEN NOTIFICATION, THE CONTRACTOR(S) WILL BE RESPONSIBLE FOR DAMAGE AND THE COST OF STRUCTURALLY REPAIRING OR REPLACING THE DAMAGED AREAS OF THE EXISTING BUILDING AND UTILITIES.

CONCRETE

ANY FORM CONTRACTORS REQUIRED TO TRENCH OR CHIP CONCRETE FLOOR SLABS FOR THEIR PORTION OF THE WORK SHALL BE RESPONSIBLE FOR THE BACKFILLING AND PATCHING AS REQUIRED TO RETURN SLAB TO ITS ORIGINAL CONDITION.

THE CONTRACTOR SHALL REMOVE ALL EXISTING FLOORING WITHIN THE DESIGNATED PREMISES TO ACCOMMODATE THE NEW FLOORING PLAN. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR FLASH PATCHING, SCRAPPING OR GRINDING THE EXISTING SLAB TO PROVIDE A SMOOTH SURFACE FREE FROM HOLES, BUMPS, OR CRACKS PRIOR TO THE APPLICATION OF ANY NEW FLOORING.

METALS

METAL STUDS AND LIGHT GAUGE METAL FRAMING SHALL BE GALVANIZED STEEL STUDS, SIZED AS INDICATED ON DRAWINGS OR AS REQUIRED, INCLUDING ALL ACCESSORIES SUCH AS BRIDGING, TRACK, ETC. GENERAL CONTRACTOR TO PROVIDE ALL MISCELLANEOUS BOLTS, CLIPS, ANCHORS, ANGLES, BRACKETETS, SLEEVES, FASTENERS, AND OTHER METAL ITEMS AS REQUIRED.

STRUCTURAL METALS: THE DESIGN OF ALL MISCELLANEOUS METAL LINTELS, COLUMNS SUPPORTS AND FRAMING REQUIRED, INCLUDING ALL STOREFRONT WORK, SHALL BE THE SOLE RESPONSIBILITY OF THE GENERAL CONTRACTOR. SHOP DRAWINGS OF SUCH METALS SHALL BE SUBMITTED TO TENANT FOR APPROVAL.

WOOD AND WOOD PRODUCTS

1. ALL ARCHITECTURAL WOODWORK SHALL BE MANUFACTURED IN ACCORDANCE WITH THE STANDARDS IN THE CURRENT EDITION OF THE ARCHITECTURAL WOODWORK INSTITUTE QUALITY STANDARDS MANUAL IN THE GRADE OR GRADES HEREIN/AFTER SPECIFIED OR SHOWN ON THE DRAWINGS.

2. IT IS NECESSARY TO SUBMIT (3) MATCHING SAMPLES OF COLORED LACQUER, SPECIAL PAINTS, AND SAWN FINISHES FOR APPROVAL BY TENANT OR STORE DESIGNER BEFORE WORK IS BEGUN.

3. TO WOOD: PLYWOOD SHALL BE PAINT GRADE BIRCH IN CABINETS. IF PAINT FINISH IS TO BE APPLIED TO WOOD SURFACES, FINISHES SHALL BE APPROVED BY THE MANUFACTURER. C-PD GRADE: ALL EXPOSED EDGES SHALL HAVE A 1/4" THICK HARDWOOD EDGE BAND. PARTICLE BOARD: ALL PARTICLE BOARD SHALL BE HIGH DENSITY INDUSTRIAL GRADE. PLASTIC LAMINATE: ALL PLASTIC LAMINATE SHALL BE 1/16" THICK UNLESS OTHERWISE NOTED. ALL PLYWOOD AND PARTICLE BOARD DOORS WHICH ARE TO HAVE A PLASTIC LAMINATE FACE SHALL HAVE A PLASTIC LAMINATE BALANCE SHEET ON BACK.

DOORS AND HARDWARE

1. HOLLOW AND SOLID CORE WOOD: DOORS SHALL BE MANUFACTURED IN ACCORDANCE WITH THE LATEST NATIONAL WOODWORK MANUFACTURER'S ASSOCIATION INDUSTRY STANDARD. WOOD DOORS SHALL BE PAINT GRADE BIRCH UNLESS NOTED OTHERWISE.

2. DOOR SHEDGES: DOORS SHALL CONSIST OF (2) FLUSH FACES OF 14 GAUGE STEEL, ONE PIECE QUALITY EPOXY SHEET STEEL WITH ONE PIECE SOUND INSULATED CORE BONDED TO BOTH FACES. TOP AND BOTTOM CHANNELS TO BE .16 GAUGE STEEL. HINGE REINFORCEMENTS TO BE 10 GAUGE STEEL. FRAME DOORS THAT HAVE SPECIAL REQUIREMENTS, SEE DOOR SCHEDULE. ALL RATED DOORS TO BE "UL" OR FACTORY MUTUAL (FM) LISTED.

4. THE CONTRACTOR(S) SHALL INSTALL ALL DOORS, FRAMES, AND HARDWARE AND RELATED PARTS AND MATERIALS AS INDICATED ON DRAWINGS AND ON THE DOOR SCHEDULE. ALL DOORS, FRAMES AND HARDWARE SHALL BE FABRICATED AND ERECTED TRUE, PLUMB, AND SQUARE AS SPECIFIED, AS DETAILED AND AS PER MANUFACTURER'S RECOMMENDATIONS.

GELS

1. REQUIRED FIRE RATED CEILING ASSEMBLY AS SHOWN ON DRAWINGS, OR WHERE ASSEMBLY REQUIREMENTS: TOTAL ASSEMBLY TO BE 1 HR. FIRE RATED.

2. SUSPENSION GRID SYSTEM: AS SPECIFIED ON SHEET A-60. WITH SUSPENSION SYSTEM AND RELATED ACCESSORIES AS SHOWN ON DRAWINGS AND AS SPECIFIED.

3. GILLES, DIFFUSERS, AND OTHER NORMAL ACCESSORIES. ALL SYSTEM COMPONENTS SHALL BE FROM A SINGLE MANUFACTURER.

4. INSTALL CEILING AND SUSPENSION SYSTEMS IN STRICT ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. FINISHED CEILING SHALL BE WATER LEVEL WITH JOINTS SQUIG AND SQUARE, AND TILES IN PERFECT CONDITION. INSTALL SECURITY GRIP CLIPS ON FIRST TWO TILES AROUND PERIMETER OF STORE. Gypsum BOARD PROVIDE ALL ADDITIONAL PROTECTION AS REQUIRED INCLUDING GYPSUM BOARD BRUSH TO TENANT NOT LESS THAN 2 UNOPENED BOXES OF EACH TILE USED.

FLOOR COVERING

1. THE CONTRACTOR SHALL COORDINATE INSTALLATION OF ALL FLOOR COVERINGS AS SHOWN ON DRAWINGS AND AS NOTED ON THE DRAWINGS FOR LOCATION AND EXTENT.

2. CONTRACTOR TO FLASH PATCH OR SCRAP AS REQUIRED TO PROVIDE A SMOOTH LEVEL FLOOR SURFACE FREE FROM HOLES, CRACKS OR BUMPS.

3. FILL ALL CRACKS, JOINTS, ETC. IN SUB-FLOOR WITH CRACK FILLER. APPROVED BY MANUFACTURER.

4. FLOORING MANUFACTURER: INSTALL ALL MATERIALS WITH WATERPROOF TYPE ADHESIVES AS RECOMMENDED BY FLOORING MANUFACTURER AND SURFACE INVOLVED.

5. CONTRACTOR TO "FLOAT-UP" SUB-FLOOR AS REQUIRED TO BRING CARPET OR COMPOSITION TILE FLUSH WITH ADJACENT FLOOR FINISHES. MATERIAL AND METHODS TO BE DETERMINED BY CARPET MANUFACTURER. SEAL ALL SEAMS WITH SEAM ADHESIVE RECOMMENDED BY CARPET MANUFACTURER.

GYPSUM BOARD

ALL GYPSUM BOARD SHALL BE "US GYPSUM" 5/8" THICK FIRE CODE SHEETROCK. (TYPE "X" PANELS OF STANDARD QUALITY) UNLESS OTHERWISE NOTED. FASTENERS, FASTENERS SHALL BE DRYWALL SCREWS OF PROPER SIZE AND TYPE PER MANUFACTURER'S RECOMMENDATION.

ALL GYPSUM BOARD AT OUTSIDE CORNERS SHALL RECEIVE "USG" DUR-A-BEAD #103. USE "USG" 200B METAL TRIM WHERE ENDS ARE EXPOSED. ALL JOINTS SHALL HAVE "USG" PERF-A-TAPE JOINT SYSTEM. ALL SURFACES TO BE TAPER, SPACKLED, AND Sanded TO A CONDITION TO ACCEPT ALL NEW FINISHES.

THE CONTRACTOR(S) SHALL FINISH AND INSTALL ALL GYPSUM BOARD AND SYSTEMS COMPLETE WITH PARTITION FRAMING, CEILING SUSPENSION SYSTEMS AND RELATED ACCESSORIES, PARTS, MATERIALS, ETC. AS SHOWN ON DRAWINGS AND AS SPECIFIED. INSTALL ALL MATERIALS PER MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.

PAINTING

1. THE CONTRACTOR IS RESPONSIBLE FOR VISITING AND INSPECTING THE TENANT SPACE PRIOR TO THE APPLICATION OF ANY PAINT OR FINISHING MATERIAL. IF ANY NEW OR EXISTING SURFACE TO BE FINISHED CANNOT BE PUT IN PROPER CONDITION BY CUSTOMARY CLEANING, SANDING, AND PUTTING OPERATIONS, THE GENERAL CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER OR ASSUME RESPONSIBILITY FOR, AND REPLY ANY UNSATISFACTORY RESULTING FINISH.

2. THE INTENT IS TO PROVIDE A SATISFACTORY FINISH TO ALL PARTS OF THE PROJECT, WHETHER NOTED HEREIN OR NOT, UNLESS SPECIFICALLY NOTED OTHERWISE. THE CONTRACTOR(S) SHALL APPLY ADDITIONAL COATS OF FINISHING MATERIAL TO ACCOMPLISH THE INTENT, THEN APPLY ADDITIONAL COATS OF SPECIFIED MATERIAL TO GIVE SATISFACTORY COVERAGE. SEE FINISH SCHEDULE.

3. STAINLESS STEEL, ALUMINUM, CHROME PLATED SURFACES, AND ALL OTHER BRIGHT METAL FINISHES SHALL NOT BE PAINTED UNLESS OTHERWISE NOTED.

4. USE ONLY PAINT AND RELATED MATERIALS OF THE MANUFACTURER(S) SPECIFIED.

5. ALL PAINTED SURFACES SHALL BE PREPARED IN STRICT ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS (ESPECIALLY IN REGARD TO PRIMING EXISTING SURFACES).

6. PAINTED GYPSUM BOARD TO RECEIVE ONE COAT LATEX PRIMER AND TWO COATS OF SPECIFIED PAINT. SPOTS OF UNIFORM DAMAGE TO SPECIFIED PAINT, TOUCH UP BEFORE APPLYING SECOND COAT TO PRODUCE AN EVEN RESULT IN THE FINISH COAT. DRY ALL COATS THOROUGHLY BEFORE APPLYING SUCCEEDING COATS. FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR RE-COAT TIME. SEAL ALL DRYWALL SURFACES BEHIND MIRRORS.

7. WASH ALL METAL SURFACES WITH MINERAL SPIRITS TO REMOVE ALL DIRT AND GREASE BEFORE APPLYING FINISH. WHERE RUST AND/OR SCALE IS PRESENT, WIRE BRUSH OR SAND CLEAN BEFORE APPLYING FINISH.

8. PUTTY ALL NAIL HOLES, COUNTERSUNK SCREWS, BOLTS, CRACKS, ETC. BEFORE FINISHING.

9. SANDING FINISH SURFACES SMOOTH AND EVEN BEFORE APPLYING FINISH.

10. FINISHING AND BETWEEN COATS.

11. MOUNTING BOARDS, ETC. PAINT TO MATCH ADJACENT WORK UNLESS OTHERWISE SPECIFIED.

12. SANDPAPER TO PROVIDE SMOOTH FINISH.

13. MAKE FINISH WORK UNIFORM AND SMOOTH. FREE OF BUBBS, SAGS, DEFECTIVE BRUSHING AND CLOGGING. MAKE EDGES OF PAINT ADJOINING OTHER MATERIALS OR COLORS SHARP AND CLEAN WITHOUT OVERLAPPING.

14. COMPLETELY FINISHED AT FACTORY UNLESS SPECIFICALLY DESIGNATED. GENERAL CONTRACTOR SHALL LEAVE SUFFICIENT MATERIAL FOR TOUCHUP OF FINISHES. TOUCH WALL PAINT USED ON THE PROJECT.

15. THE CONTRACTOR SHALL REMOVE ALL PAINT RAGS, EMPTY CANS, AND WASTE FROM THE TENANT SPACE EACH DAY.

16. CLEANING AND TOUCHUP IN ADDITION TO THE CLEANING REQUIRED IN THE "FINISHING AND TOUCHUP" SECTION. THE CONTRACTOR SHALL UPON COMPLETION: (1) REMOVE ALL PAINT AND/OR PASTE WHERE IT HAS BEEN SPILLED, SPLASHED OR SPLATTERED (INCLUDING FIXTURES, GLASS, HARDWARE, CARPETING, ETC.) (2) TOUCHUP AND RESTORE THE FINISH OF ANY ITEM MARRED OR DAMAGED DURING FINISH OPERATIONS OR CLEAN-UP.

MILLWORK

1. THE FIXTURE CONTRACTOR SHALL FABRICATE, FINISH, AND DELIVER ALL FINISHED MILLWORK, CABINET WORK, LOOSE FIXTURES, PANELING, ETC. AS SHOWN ON DRAWINGS OR AS DIRECTED BY OWNER.

2. THE FIXTURE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR:

A. ALL INFORMATION CONTAINED ON THE ENCLOSED DRAWINGS, EXCEPT WHERE OTHERWISE NOTED.

B. PREPARING DETAILED INSTRUCTIONS ON AREAS THAT REQUIRE BLOCKING OR REINFORCING FOR WORK HE PROVIDES.

C. LAMPS, CORDS, CANNOPLES, LENS, ETC. FOR ALL LIGHTING AND ELECTRICAL FIXTURES HE PROVIDES.

NEW UTILITY SETUP

1. GENERAL CONTRACTOR IS TO CONTACT LOCAL PROVIDER/LANDLORD TO SET UP UTILITIES (ELECTRIC, GAS, PROPANE, WATER, SEWER).

2. GENERAL CONTRACTOR IS TO CHANGE BILLING ADDRESS, NAME TO: AT&T, ATTENTION: DEBBIE WRUBLESKI, 12555 CONIGLAR WAY, ALPHARETTA, GA 30004 (ACQUIRE AT&T W-9 IF NEEDED).

3. GENERAL CONTRACTOR IS TO COMPLETE REQUIRED UTILITY APPLICATION FORMS AND PROCESS ANY REQUIRED DEPOSITS. AT&T RETAIL CONSTRUCTION WILL REIMBURSE G.C. ASSIST G.C. IN COMPLETING REQUIRED FORMS AND PROVIDING SIGNATURES TO COMPLETE ACTIVATION (IF REQUIRED).

4. GENERAL CONTRACTOR IS TO COMMUNICATE UTILITY INFORMATION TO AT&T PAYMENT PROCESSING MANAGER WITHIN 48 HOURS CONTACT: DEBBIE WRUBLESKI (678) 893-3964 (E: PHYSICAL ADDRESS, CITY, STATE, ZIP CODE, ACCOUNT NUMBERS, METER NUMBERS, UTILITY VENDOR NAME, ETC.)

REVISIONS

DATE: 08-14-08
JOB NO: 2992
DRAWN:
CHECKED:

711 N. FLEDER RD.
ARLINGTON, TX 76012
PH: (817) 635-5996
FAX: (817) 635-5999

PROJ. COORDINATOR
15 South 3rd Street
Philadelphia, PA 19106
216.922.0690
FAX.922.4546

RICHARD M. COLE
& ASSOCIATES

211 MARGINAL WAY
PORTLAND, MAINE 04101

at&t

ARCHITECTURAL SPECIFICATIONS

A-7.1

SHEET NUMBER

REVISIONS