Verizon Wireless
Sign Details

Inspections Division
Date: 11/22/17

A B

A B **ELEVATION VIEW** - 53.7 SF
Scale: 3/8" = 1'-0"

GENERAL SPECIFICATIONS:

Two (2) sets of 2" deep LED illuminated channel letters flush mounted to wall.
Letters to be internally illuminated via LED lighting, with power supplies located in remote raceway installed behind wall.
All elements of letters to have matte finish.
Letters to mount to wall with mechanical fasteners as required for wall conditions.

COLOR SPECIFICATIONS

3M #3630-143 Poppy Red Translucent Vinyl / MP #643 Matte PMS 485

#7328 P95 Matte White Acrylic / MP #6425 SP Matte Hi Hide White

LED LAYOUT
Scale: NTS

E
402 ea. GEMX71-W1 (201')
34 ea. Principal PL-FS3-RD1-P (11.3')
4 ea. GEPS12-60U-NA
Total Electrical Amp Load = 2.3 Amps
One (1) 120 Volt - 20 Amp
Circuit Breaker Required for Sign

- Trimcap seam location
- Return seam location
- Trimcap and Return seam location

TRIMCAP AND RETURN SEAM LOCATIONS

Construction Details - Flush Mount Channel Letters

Page 6 of 10

SIDE SECTION VIEW
Scale: NTS

c MET us LISTED **ELECTRIC SIGN**

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF **ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE** AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

GROUNDED ELECTRICAL CONNECTIONS

Allen Industries
FILE NUMBER: E212503

MOUNTING HARDWARE CHART

	MASONRY	WOOD	METAL
1/4" ZINC PLATED STEEL THREADED ROD THRU WALL	●	●	●
3/8" LAGS WITH SHIELDS	●		
3/8" LAG BOLTS		●	
3/8" TOGGLE BOLTS			●

NOTE:
1.) THREADED ROD WILL BE PROVIDED STANDARD - ALL OTHER HARDWARE IS TO BE PROVIDED BY THE INSTALLER AS REQ.

BURR SIGNS

Client & Location	Customer Approval Signature	Revisions	Drawing ID	Date	Page #
verizon 3 Somerset St Portland ME				10.26.17	
			Drawn By	Sales Rep	WO #