



1 PLUMBING ENLARGED ABOVE FLOOR PLAN - MARKET LEVEL - NORTHEAST CORNER

- WALK-IN COOLER AND FREEZER EVAPORATOR DRAIN NOTES:**
- \*ALL PIPING IS TO BE INSTALLED AS SHOWN IN CASE'S, AVAILABLE TO THE PUBLIC. INSTRUCTIONS WITH CLEANOUTS AT CONNECTION TO EVAPORATOR. PROVIDE RAY-CHEM XL-TRACE FREEZE PROTECTION HEATING CABLE ON CONDENSATE DRAINS, COVERED WITH 1/2" ELASTOMERIC DAM INSULATION. FOLLOW MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION.
  - ① ROUTE CONDENSATE PIPING FROM EVAPORATORS IN DELI COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.
  - ② ROUTE CONDENSATE PIPING FROM EVAPORATORS IN COUNTRY COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.
  - ③ ROUTE CONDENSATE PIPING FROM EVAPORATORS IN CHEESE COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.
  - ④ ROUTE CONDENSATE PIPING FROM EVAPORATORS IN BAKERY COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.
  - ⑤ ROUTE CONDENSATE PIPING FROM EVAPORATORS IN SEAFOOD COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.
  - ⑥ ROUTE CONDENSATE PIPING FROM EVAPORATORS IN BAKERY COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.
  - ⑦ ROUTE CONDENSATE PIPING FROM EVAPORATORS IN BAKERY COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.
  - ⑧ ROUTE CONDENSATE PIPING FROM EVAPORATORS IN BAKERY COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.
  - ⑨ ROUTE CONDENSATE PIPING FROM EVAPORATORS IN BAKERY COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.
  - ⑩ ROUTE CONDENSATE PIPING FROM EVAPORATORS IN BAKERY COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION.