



- WALK-IN COOLER AND FREEZER EVAPORATOR DRAIN NOTES:**
- 1. ALL PIPING IS TO BE SLOTTED, SO THAT IT IS NOT USABLE TO THE PUBLIC.
 - 2. ALL PIPING TO BE 1/2" DIA. OR LARGER, WITH COMPACT WITH DRAINAGE CAPS.
 - 3. PROVIDE RAY-CHEM XL-TRACE FREEZE PROTECTION FOR ALL WALK IN FREEZERS AND MEAT, SEAFOOD AND POULTRY COOLERS, COVERED WITH 1/2" INSULATION. FOLLOW MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION.
 - 4. ROUTE CONDENSATE PIPING FROM EVAPORATORS IN DELI COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION. SEE DETAIL 1/P7.03.
 - 5. ROUTE CONDENSATE PIPING FROM EVAPORATORS IN POULTRY COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION. SEE DETAIL 1/P7.03.
 - 6. ROUTE CONDENSATE PIPING FROM EVAPORATORS IN CHEESE COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION. SEE DETAIL 1/P7.03.
 - 7. ROUTE CONDENSATE PIPING FROM EVAPORATORS IN BAKERY COOLER AND WALK-IN FREEZER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION. SEE DETAIL 1/P7.03.
 - 8. ROUTE CONDENSATE PIPING FROM EVAPORATORS IN SECCOOD FREEZER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION. SEE DETAIL 1/P7.03.
 - 9. ROUTE CONDENSATE PIPING FROM EVAPORATORS IN DAIRY COOLER TO THESE I.D. PROVIDE AIR GAP AT TERMINATION. SEE DETAIL 1/P7.03.
 - 10. ROUTE CONDENSATE PIPING FROM EVAPORATORS IN PRODUCE COOLER TO THIS I.D. PROVIDE AIR GAP AT TERMINATION. SEE DETAIL 1/P7.03.
 - 11. ROUTE CONDENSATE PIPING FROM AHU-7 TO THIS I.D. SEE DETAIL 1/P7.03.
 - 12. ROUTE CONDENSATE PIPING FROM AHU-8 TO THIS I.D. SEE DETAIL 1/P7.03.
 - 13. ROUTE CONDENSATE PIPING FROM AHU-9 TO THIS I.D. SEE DETAIL 1/P7.03.