

2. SILT SACKS TO BE INSTALLED DURING CONSTRUCTION OPERATIONS WHEN THE POTENTIAL FOR SEDIMENT TO ENTER EXISTING & PROPOSED BASINS EXISITS.

DETAILS

RJDIV

CIVIL

1. INSTALL SILTSACK PER MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS. EMPTY OR REMOVE SEDIMENT FROM SILTSACK WHEN RESTRAINT CORD IS NO LONGER VISIBLE. CLEAN, RINSE, AND REPLACE AS NEEDED.

11-13-08

PERMIT SUBMITTAL

PERMIT SUBMITTAL

REVISE BLDG LAYOUT
& ADD BUS DROP

PFRMIT ~

100%

- 1" REBAR FOR LIF AND REMOVAL

Service A page 4

STABILIZED

EXISTING GROUND

CONSTRUCTION MANAGER:

84 Middle Street
Portland, Maine 04101
CONSIGLI

Phone 207-773-3000
Fax 207-773-2800

PARKING GARAGE ARCHITECT:

55 York Street
Portland, Maine 04101
Phone 207-772-4656
Fax 207-828-4656
Fax 207-828-4656
Fax 207-879-1838
Fax 207-879-1838
Fax 207-879-1838

Temporary

Erosion

Control:

Dates for use

EROSION AND SEDIMENT CONTROL NOTES

Erosion Control:

Dates for use

When no frost is in ground

Sept. 16 to Oct. 31

Before soil disturbance, install downhill of areas to be disturbed and around material stockpiles.

Before soil disturbance, install uphill of areas to be disturbed and material stockpiles.

During dry weather, apply water and calcium chloride to control dust.

Soil stockpiles that are not covered and disturbed areas that will not be disturbed again within 14 days. If grass growth provides less than 95% soil coverage by Nov. 1, apply mulch and anchor with netting or hydraulically applied bonded fiber matrix.

On all areas of exposed soil that are not temporarily seeded or that will not be disturbed again within 14 days, apply 70 to 90 lbs. mulch (2 bales) per 1,000 sq. ft. within the 21 day period.

On all areas of exposed soil that are not temporarily seeded or that will not be disturbed again within 7 days, apply 150 to 170 lbs. mulch (4 bales) per 1,000 sq. ft. within the 2 day period. Erosion control blanket may be used as a substitute for winter mulch.

On all areas of exposed soil that are not temporarily seeded, apply 150 to 170 lbs. mulch (4 bales) per 1,000 sq. ft. and anchor with netting at the end of each working day. Erosion control blanket may be used as a substitute for winter mulch.

It land the erosion and sedimentation control measures daily, and maintain and repair as necessary.

HARRIMAN

123 Middle Street Portland, Maine 04101 207.775.0053 tel 207.775.0460 fm.

Sept. 16 to April 15

Install only in areas shown on the plan, shortly after pavement base is brought to final grade.

Install near completion of project.

On final grade areas, within 7 days of grade preparation, prepare topsoil, followed by seed and mulch application.

On final grade areas, with prepared topsoil. Apply seed at double the specified rate on bare soil, and follow with an application of winter mulch.

Install with final landscaping.

BAYCO LLC.
BAYSIDE
DEVELOPMENT

Inspections: Regular inspections of all erosion and sedimentation controls shall be made weekly and prior to and following storm events. Minimum inspections shall listed in the table below.

at least be made

Thin mulch or inadequate application.
Wind movement.

Poor seed germination.
Loss of mulch.
Development of rivulets.

Sediment build—up to one half the height of th Undermining of the barrier.

Supporting stakes loose, toppled, or unmarked.
Breaks in barrier.

Discharge is to stabilized area.
Erosion or breaks in barrier.

Supporting stakes loose, toppled or unmarked.
Sediment build—up and structure blockages.
Slow flow/Ponding water.
Breaks in fabric or voids in barrier.

Breaks in fabric or supporting structure.
Slow flow, indicating high sediment build—up.
Sedimentation of roadways.
Off—site dust complaints.