DOOR AND FRAME																
DOOR NO.	LOCATION		DOOR					FRAME								
	ROOM NO.	ROOM NAME	OPENING		PANEL					DETAILS			RATING	HDWR	COMMENTS
			WIDTH	HEIGHT	TYPE	MATL	THICK	TYPE	MATL	HEAD	JAMB	SILL			
LEVEL 3															
303A	303	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PRIVACY	
304A	304	LG CONF	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
304B	304	LG CONF	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
305A	305	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PRIVACY	
306A	306	SHP / RCG / ENV / RECYC / STOR	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/CLOSER	
306B	306	SHP / RCG / ENV / RECYC / STOR	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					STOREROOM/CLOSER	
306C	306	SHP / RCG / ENV / RECYC / STOR	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/ CLOSER W/ HOLD OPEN	
307A	307A	DATA	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					CARD READER/CLOSER	
307B	307B	ELEC	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM				90 MIN.	STOREROOM/CLOSER	
310A	310	OFF	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
311A	311	OFF	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
312A	312	OFF	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
313A	313	BILLING	3' - 0"	7' - 0"	FG		1 3/4"								
314A	314	CALL CENTER	4' - 0"	7' - 0"	FG		1 3/4"								
316A	316A	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PRIVACY	
317A	317	LOUNGE	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					PASSAGE/CLOSER	
318A	318	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PRIVACY	
320A	320A	CLOSET	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/CLOSER	
321A	321	OFFICE/ FUTURE EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
321B	321	OFFICE/ FUTURE EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
322A	322	PROVIDER	3' - 0"	7' - 0"	FG	WD	1 3/4"	2	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
323A	323	PROVIDER	3' - 0"	7' - 0"	FG	WD	1 3/4"	2	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
324A	324	PROVIDER	3' - 0"	7' - 0"	FG	WD	1 3/4"	2	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
325A	325	PROVIDER	3' - 0"	7' - 0"	FG	WD	1 3/4"	2	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
326A	326	PROVIDER	3' - 0"	7' - 0"	FG	WD	1 3/4"	2	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
327A	327	OFF	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
328A	328	OFF	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
329A	329	OFF	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
330A	330	STOR.	2' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					STOREROOM/CLOSER	
331A	331	EXAM-SN	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
332A	332	CLEAN SUPPLY	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					COMBI LOCK /CLOSER	
333A	333	WORK	3' - 0"	7' - 0"	N	WD	1 3/4"	-	-					BARN DOOR SLIDER	DOOR PANEL TO BE 4" LARGER THEN OPENING
335A	335	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
337A	337	RECEPTION	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					OFFICE	
338A	338	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
339A	339	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
340A	340	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
341A	341	OFFICE-NP	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					OFFICE	
342A	342	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
343A	343	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
346A	344	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
348A	348	C/O	3' - 6"	7' - 0"	FG	WD	1 3/4"	1	AL					BARN DOOR SLIDER	DOOR PANEL TO BE 4" LARGER THEN OPENING; DECORATIVE RESIN PANEL INSERT W/ CUSTOM WOOD APPLIQUE
351A	351	CONSULT / CONF	3' - 6"	7' - 0"	FG	WD	1 3/4"	1	AL					PRIVACY	
352	352	TEL.	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					STOREROOM/CLOSER	
353	353	ELECTRIC ROOM	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					STOREROOM/CLOSER	
354A	354	PHLEB	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
355A	355	SOILED HOLD	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					COMBI LOCK /CLOSER	
356A	356	ROOMERS	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					OFFICE	
356B	356	ROOMERS	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					OFFICE	
357A	357	WAITING	3' - 6"	7' - 0"	N	WD	1 3/4"	1	AL					ELECTRONIC LOCK W/ CARD READER AND CLOSER	
357B	357	WAITING	3' - 6"	7' - 0"	N	WD	1 3/4"	1	AL					ELECTRONIC LOCK W/ CARD READER AND CLOSER	
358A	358	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
359A	359	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
360A	360	C/O	3' - 6"	7' - 0"	FG	WD	1 3/4"	1	AL					BARN DOOR SLIDER	DOOR PANEL TO BE 4" LARGER THEN OPENING; DECORATIVE RESIN PANEL INSERT W/ CUSTOM WOOD APPLIQUE
362A	362	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
363A	363	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
364A	364	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
365A	365	OFFICE-NP	3' - 6"	7' - 0"	N	WD	1 3/4"	1	HM					OFFICE	
366A	366	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
367A	367	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
368A	368	EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
370A	370	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
372A	372	WORK	3' - 0"	7' - 0"	N	WD	1 3/4"	-	-					BARN DOOR SLIDER	DOOR PANEL TO BE 6" LARGER THEN OPENING
373A	373	CLEAN SUPPLY	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					STOREROOM/CLOSER	
374A	374	EXAM-SN	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	
375A	375	STOR	2' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/CLOSER	
376A	376	SVCS-OFF	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					CLASSROOM	
376B	376	SVCS-OFF	2' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					CLASSROOM	
377A	377	SVCS-OFF	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					CLASSROOM	
377B	377	SVCS-OFF	2' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					BARN DOOR SLIDER	DOOR PANEL TO BE 6" LARGER THEN OPENING
381A	381	PROVIDER	3' - 0"	7' - 0"	FG	WD	1 3/4"	1	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
382A	382	PROVIDER	3' - 0"	7' - 0"	FG	WD	1 3/4"	2	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
383A	383	PROVIDER	3' - 0"	7' - 0"	FG	WD	1 3/4"	2	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
384A	384	PROVIDER	3' - 0"	7' - 0"	FG	WD	1 3/4"	2	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
385A	385	PROVIDER	ETR..... ETR.....	ETR..... ETR.....	ETR ETR	ETR ETR	ETR..... ETR.....	2	HM					OFFICE	GLAZING FILM - GF-1 [CORRIDOR SIDE]; GF-2 [PROVIDER SIDE]
386A	386	OFFICE/ FUTURE EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	

DOOR AND FRAME																
DOOR NO.	LOCATION		DOOR					FRAME								
	ROOM NO.	ROOM NAME	OPENING		PANEL					DETAILS			RATING	HDWR	COMMENTS
			WIDTH	HEIGHT	TYPE	MATL	THICK	TYPE	MATL	HEAD	JAMB	SILL			
386B	386	OFFICE/ FUTURE EXAM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
C320A	C320	CORRIDOR	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					ELECTRONIC LOCK W/ CARD READER AND CLOSER	
C330B	C330	CORRIDOR	3' - 6"	7' - 0"	N	WD	1 3/4"	1	HM					ELECTRONIC LOCK W/ CARD READER AND CLOSER	
C350A	C350	CIRCULATION	3' - 6"	7' - 0"	N	WD	1 3/4"		HM					ELECTRONIC LOCK W/ CARD READER AND CLOSER	
C360A	C360	CORRIDOR	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					ELECTRONIC LOCK W/ CARD READER AND CLOSER	
E-ST13	ST13	STAIR NO.1	3' - 0"	7' - 0"	F	WD	1 3/4"	ETR	ETR				45 MIN.	ETR	ETR
E-ST23	ST23	STAIR NO. 2	3' - 0"	7' - 0"	F	WD	1 3/4"	ETR	ETR				45 MIN.	ETR	ETR
L300A	L300	ELEV. LOBBY	3' - 6"	7' - 0"	N	WD	1 3/4"	1	HM					ELECTRONIC LOCK W/ CARD READER AND CLOSER	RELEASE IN ALARM
LEVEL 4															
400A	400	PATHOLOGY LAB	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM				45 MIN.	CARD READER/CLOSER	
400B	400	PATHOLOGY LAB	5' - 10"	7' - 0"	F	WD	1 3/8"	1	HM					BY-PASS SLIDER	
401A	400	PATHOLOGY LAB	3' - 0"	7' - 0"	FG	WD	1 3/4"	1	HM					BARN DOOR SLIDER	DOOR PANEL TO BE 4" LARGER THAN OPENING
402A	402	STAFF LOUNGE	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM				45 MIN.	COMBI LOCK /CLOSER	TBD
403A	403	INFUSION CENTER	3' - 6"	7' - 0"	FG	WD	1 3/4"	1	HM					ENTRANCE LOCK /CLOSER	
404A	404	OFFICE	3' - 0"	7' - 0"	FG	WD	1 3/4"	1	HM					BARN DOOR SLIDER	DOOR PANEL TO BE 4" LARGER THAN OPENING
406A	406	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
407A	C400	CIRCULATION	2' - 8"	7' - 0"	F	WD	1 3/4"		HM					STOREROOM/CLOSER/HOLD OPEN	
408A	408	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					COMBI LOCK /CLOSER/ DEAD BOLT	
409A	409	LOCKER ROOM	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					COMBI LOCK /CLOSER	
410A	427	NURSE.	2' - 6"	7' - 0"	F		1 3/4"								
411A	411	RECEPTION	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					OFFICE	
412A	412	WAITING	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM				45 MIN.	KEYED ENTRY WAITING	
413A	413	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
414A	414	TLT	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
416A	C410	CIRCULATION	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM				45 MIN.	STOREROOM/CLOSER	
421A	421	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					COMBI LOCK /CLOSER/ DEAD BOLT	
422A	422	STAFF WORK RM	3' - 0"	7' - 0"	N	WD	1 3/4"	-	-					BARN DOOR SLIDER	DOOR PANEL TO BE 6" LARGER THEN OPENING
423A	423	OFFICE	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					OFFICE	
424A	424	TLT	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
428A	428	TLT	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
440A	C440	CIRCULATION	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM				45 MIN.	STOREROOM/CLOSER	
441A	441	SUPPLY	4' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					COMBO LOCK/ CLOSER	
442A	441	SUPPLY	4' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					COMBO LOCK/ CLOSER	
443A	443	CONSULT RM	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					PRIVACY	
444A	444	STOR	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					COMBO LOCK/ CLOSER	
446A	C440	CIRCULATION	2' - 8"	7' - 0"	F	WD	1 3/4"	1	HM					COMBI LOCK /CLOSER	
450A	450	PROCEDURE	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/ CLOSER W/ HOLD OPEN	DOOR PROTECTION 1-SIDE
450B	450	PROCEDURE	4' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	DOOR PROTECTION 2-SIDES; DOOR EDGE - DE TO 4'4"; DOOR FRAME - DF TO 4'-4"
451A	451	PROCEDURE	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/ CLOSER W/ HOLD OPEN	DOOR PROTECTION 1-SIDE
451B	451	PROCEDURE	4' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	DOOR PROTECTION 2-SIDES; DOOR EDGE - DE TO 4'4"; DOOR FRAME - DF TO 4'-4"
452A	452	TOILET/ SHOWER	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PRIVACY W/ DEADBOLT	
453A	453	CLEAN SUPPLY	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					COMBI LOCK/ CLOSER	
454A	454	JAN	2' - 8"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/CLOSER/HOLD OPEN	
455A	455	SOILED UTILITY	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					PASSAGE/CLOSER	
456A	456	TOILET/ SHOWER	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PRIVACY W/ DEADBOLT	
457A	457	PROCEDURE	4' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	DOOR PROTECTION 2-SIDES; DOOR EDGE - DE TO 4'4"; DOOR FRAME - DF TO 4'-4"
457B	457	PROCEDURE	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/ CLOSER W/ HOLD OPEN	DOOR PROTECTION 1-SIDE
458A	458	PROCEDURE	4' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	DOOR PROTECTION 2-SIDES; DOOR EDGE - DE TO 4'4"; DOOR FRAME - DF TO 4'-4"
458B	458	PROCEDURE	3' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/ CLOSER W/ HOLD OPEN	DOOR PROTECTION 1-SIDE
459A	459	PROCEDURE	4' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	DOOR PROTECTION 2-SIDES; DOOR EDGE - DE TO 4'4"; DOOR FRAME - DF TO 4'-4"
459B	459	PROCEDURE	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/ CLOSER W/ HOLD OPEN	DOOR PROTECTION 1-SIDE
460A	460	SCOPE REPROCESS	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					PASSAGE/CLOSER	
461A	461	SCOPE STOR.	3' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					PASSAGE/CLOSER	
462A	461	SCOPE STOR.	3' - 0"	7' - 0"	G	WD	1 3/4"	1	HM					PASSAGE/CLOSER	
463A	463	PROCEDURE	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE/ CLOSER W/ HOLD OPEN	DOOR PROTECTION 1-SIDE
463B	463	PROCEDURE	4' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					PASSAGE	DOOR PROTECTION 2-SIDES; DOOR EDGE - DE TO 4'4"; DOOR FRAME - DF TO 4'-4"
464A	C450	CORRIDOR	4' - 4"	7' - 0"	F	WD	1 3/4"	1	HM					COMBI LOCK /CLOSER - ELECTRIFIED	
483A	483	TLT	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
493A	493	TLT	3' - 6"	7' - 0"	F	WD	1 3/4"	1	HM					HOSPITAL PRIVACY	
C400A	C400	CIRCULATION	6' - 0"	7' - 0"	FG	WD	1 3/4"	1	HM				45 MIN.	ENTRANCE/CLOSER/ ADA OPENER	FIRE RATED GLAZING
C410A	C410	CIRCULATION	4' - 0"	7' - 0"	N	WD	1 3/4"	1	HM				45 MIN.	ELECTRONIC LOCK W/ CARD READER AND CLOSER	FREE ACCESS ON PUSH SIDE
C440A	C440	CIRCULATION	4' - 0"	7' - 0"	N	WD	1 3/4"	1	HM					ELECTRONIC LOCK W/ CARD READER AND CLOSER	RELEASE IN ALARM
C450A	C450	CORRIDOR	4' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					ELECTRONIC LOCK W/ CARD READER AND CLOSER	RELEASE IN ALARM
C450B	C450	CORRIDOR	8' - 3 1/2"	7' - 5 1/4"		AL		-	AL					PASSAGE - AUTODOOR OPENER	ALUMINUM FOLDING
C450C	C450	CORRIDOR	8' - 3 1/2"	7' - 5 1/4"		AL		-	AL					PASSAGE - AUTODOOR OPENER	ALUMINUM FOLDING
C450D	C450	CORRIDOR	4' - 0"	7' - 0"	F	WD	1 3/4"	1	HM					ELECTRONIC LOCK W/ CARD READER AND CLOSER	FREE ACCESS ON PUSH SIDE
E-ST14	ST14	STAIR NO. 1	3' - 0"	7' - 0"	F	WD	1 3/4"	ETR	ETR						ETR - NEW DOORS? OR?
E-ST24	ST24	STAIR NO. 2	3' - 0"	7' - 0"	F	WD	1 3/4"	ETR	ETR						ETR - NEW DOORS? OR?

DOOR AND WINDOW NOTES

1. ALL HARDWARE TO BE ADA COMPLIANT LEVER STYLE HANDLES
2. PACK MINERAL-FIBER INSULATION IN ALL INTERIOR HOLLOW METAL FRAMES IN STUD WALLS.
3. REFER TO SPECIFICATIONS FOR LOCATIONS OF TEMPERED, LAMINATED, WIRED, AND INSULATING GLASS.
4. PROVIDE DOOR STOPS TO PROTECT WALLS AT ALL LOCATIONS WHERE A DOOR SWING WILL STRIKE THE WALL.
5. CONFIRM EXISTING HARDWARE TYPE/ QUALITY OF "E" EXISTING DOORS TO REMAIN.



Door Elevation Legend
3/8" = 1'-0"



Door Frame Legend
3/8" = 1'-0"

ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

Reviewed for Code Compliance
Portland Inspections Division
Approved with Conditions
Date: 05/03/16

COPYRIGHT 2016
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

PORTLAND GASTROENTEROLOGY CENTER

161 Marginal Way Portland, Maine

No.	Date	Description

Revision Schedule

REGISTERED ARCHITECT
ANN M. FONTAINE-FISHER
HOWARD
STATE OF MAINE

JOB NO.
14054

DRWN. CHK
Checker

SCALE:

ISSUE
PERMIT SET
03/18/16

TITLE
DOOR SCHEDULE

SHEET
A601

3/18/2016 5:29:46 PM