Room Finish Schedule

NUMBER	ROOM NAME	Finish Style (Hide)	FLOOR	BASE MATL	WALLS N	WALLS S	WALLS E	WALLS W	NOTES
LEVEL 3									
301	OPEN WORK	OFFICE	CPT-4	RB-2	P	P	P	P	
302	PRINT STATION	OFFICE	CPT-4	RB-2	P	P	P	P	
303	TLT	TOILET - STAFF	CT-1	CT-2	CT-2 / P	CT-2 / P	CT-2 / P	CT-2 / P	
304	LG CONF	(none)	CPT-1	WD	P	P	P	P	
305	TLT	TOILET - STAFF	CT-1	CT-2	CT-2 / P	CT-2 / P	CT-2 / P	CT-2 / P	
306	SHP / RCG / ENV / RECYC / STOR	(none)	RF-7	RB-3	P	P	P	P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
307	MAIL	(none)	RF-1	RB-2	P	P	P	P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
307A	DATA	(none)	RF-7	RB-3	P	P	P	P	
307B	ELEC	(none)	RF-7	RB-3	P	P	P	P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
310	OFF	OFFICE	CPT-4	RB-2	P	P	P	P	
311	OFF	OFFICE	CPT-4	RB-2	P	P	P	P	
312	OFF	OFFICE	CPT-4	RB-2	P	P	P	P	
313	BILLING	OFFICE	CPT-4	RB-2	P	P	P	P	
314	CALL CENTER	OFFICE	CPT-4	RB-2	P	P	P	P	
315	SCHEDULING & IT/REC	OFFICE	CPT-4	RB-2	P	P	P	P	
316	COATS	(none)	RF-1	RB-2	P	P	P	P	
316A	TLT	TOILET - STAFF	CT-1	CT-2	CT-2 / P	CT-2 / P	CT-2 / P	CT-2 / P	
317	LOUNGE	(none)	RF-1 / RF-6	RB-2	P	P	P	P	GLASS TILE BACKSPLASH
318	TLT	TOILET - STAFF	CT-1	CT-2	CT-2 / P	CT-2 / P	CT-2 / P	CT-2 / P	
320	OPEN WORK	OFFICE	CPT-4	RB-2	P	P	P	P	
320A	CLOSET	(none)	RF-1	RB-2	P	P	P	P	
321	OFFICE/ FUTURE EXAM	OFFICE	CPT-4	RB-2	P	P	P	P	
322	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
323	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
324	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
325	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
326	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
327	OFF	OFFICE	CPT-4	RB-2	P	P	P	P	
328	OFF	OFFICE	CPT-4	RB-2	P	P	P	P	
329	OFF	OFFICE	CPT-4	RB-2	P	P	P	P	
330	STOR.	(none)	RF-1	RB-2	P	P	P	P	
331	EXAM-SN	EXAM	RF-2	RB-2	P	P	P	P	
332	CLEAN SUPPLY	(none)	RF-1	RB-2	P	P	P	P	SEE WALL PROTECTION PLAN
333	WORK	OFFICE	CPT-4	RB-2	P	P	P	P	
334	MED SUPPLY	(none)	RF-1	RB-2	P	P	P	P	
335	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	PROVIDE NURSE CALL
336	SCALE	(none)	RF-1	RB-2	P	WC	P	P	
337	RECEPTION	OFFICE	CPT-4	RB-2	P	P	P	P	
338	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
339	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
340	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
341	OFFICE-NP	OFFICE	CPT-4	RB-2	P	P	P	P	
342	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
343	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
344	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
347	C/O	LOBBY	CPT-1	RB-1	P	P	P	P	
348	C/O	LOBBY	CPT-1	RB-1	P	P	P	P	
351	CONSULT / CONF	LOBBY	CPT-1	RB-1	P	P	P	P	
352	TEL.	(none)	RF-1	RB-1	P	P	P	P	
353	ELECTRIC ROOM	(none)	SC	RB-3	P	P	P	P	
354	PHLEB	EXAM	RF-2	RB-2	P	P	P	P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
355	SOILED HOLD	(none)	RF-4A	RB-2	EP	EP	EP	EP	
356	ROOMERS	(none)	CPT-4	RB-2	P	P	P	P	
357	WAITING	(none)	CPT-1	RB-1	P	P	P	P	
358	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	PROVIDE NURSE CALL
359	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	PROVIDE NURSE CALL
360	C/O	(none)	CPT-1	RB-1	P	P	P	P	
361	C/O	(none)	CT-1	RB-1	P	P	P	P	
362	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
363	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
364	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
365	OFFICE-NP	OFFICE	CPT-4	RB-2	P	P	P	P	
366	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
367	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
368	EXAM	EXAM	RF-2	RB-2	P	P	P	P	
369	SCALE	(none)	RF-1	RB-2	P	WC	P	P	
370	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	PROVIDE NURSE CALL
371	MED SUPPLY	CORRIDOR	RF-1 / CPT-1	RB-1	P	P	P	P	
372	WORK	OFFICE	CPT-4	RB-2	P	P	P	P	
373	CLEAN SUPPLY	CORRIDOR	RF-1 / CPT-1	RB-1	P	P	P	P	SEE WALL PROTECTION PLAN
374	EXAM-SN	EXAM	RF-2	RB-2	P	P	P	P	
375	STOR	CORRIDOR	RF-1 / CPT-1	RB-1	P	P	P	P	
376	SVCS-OFF	OFFICE	CPT-4	RB-2	P	P	P	P	
376A	STOR.	OFFICE	CPT-4	RB-2	P	P	P	P	PROVIDE NURSE CALL
377	SVCS-OFF	OFFICE	CPT-4	RB-2	P	P	P	P	
377A	STOR.	OFFICE	CPT-4	RB-2	P	P	P	P	
380	OPEN WORK	OFFICE	CPT-4	RB-2	P	P	P	P	
380A	PRINT STATION	OFFICE	CPT-4	RB-2	P	P	P	P	
381	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
382	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
383	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
384	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
385	PROVIDER	OFFICE	CPT-4	RB-2	P	P	P	P	
386	OFFICE/ FUTURE EXAM	OFFICE	CPT-4	RB-2	P	P	P	P	
C300	CIRCULATION	STAFF CORR	CPT-3	RB-2	P	P	P	P	
C310	CORRIDOR	OFFICE	CPT-4	RB-2	P	P	P	P	
C320	CORRIDOR	OFFICE	CPT-4	RB-2	P	P	P	P	
C330	CORRIDOR	(none)	RF-1 / CPT-1	RB-1	P	P	P	P	
C350	CIRCULATION	(none)	CPT-1 / CPT-2	RB-1	P	P	P	P	
C360	CORRIDOR	CORRIDOR	RF-1 / CPT-1	RB-1	P	P	P	P	
C380	CORRIDOR	OFFICE	CPT-4	RB-2	P	P	P	P	
E13	ELEV.	(none)	-	-	-	-	-	-	
E23	ELEV.	(none)	-	-	-	-	-	-	
L300	ELEV. LOBBY	(none)	CPT-1						
ST13	STAIR NO.1	(none)							
ST23	STAIR NO. 2	(none)							

Room Finish Schedule

NUMBER	ROOM NAME	Finish Style (Hide)	FLOOR	BASE MATL	WALLS N	WALLS S	WALLS E	WALLS W	NOTES
LEVEL 4									
400	PATHOLOGY LAB	(none)	RF-4A	RB-2	P	P	P	P	
401	OFFICE	(none)	RF-4	RB-2	P	P	P	P	
402	STAFF LOUNGE	(none)	RF-1 / RF-6	RB-2	P	P	P	P	GLASS TILE BACKSPLASH
403	INFUSION CENTER	NURSE	RF-1	RB-2	P	P	P	P	
404	OFFICE	NURSE	RF-1	RB-2	P	P	P	P	
404A	WORK	(none)							
406	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	PROVIDE NURSE CALL
407	JAN	UTILITY / JAN	RF-4	RB-3	EP	EP	EP	EP	FRP AT SINK WALLS TO 4'0" AFF
408	TLT	TOILET - STAFF	CT-1	CT-2	CT-2 / P	CT-2 / P	CT-2 / P	CT-2 / P	
409	LOCKER ROOM	(none)	RF-1	RB-2	P	P	P	P	P.LAM SHELF: ____
410	STOR.	(none)	RF-1	RB-1	P	P	P	P	
411	RECEPTION	LOBBY	CPT-1	RB-1	P	P	P	P	
412	WAITING	LOBBY	CPT-1	RB-1	P	P	P	P	
413	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	P.LAM WALL PANEL AT SINK- PROVIDE NURSE CALL
414	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	P.LAM WALL PANEL AT SINK- PROVIDE NURSE CALL
415	SNACKS	(none)	RF-1	RB-1	P	P	P	P	GLASS TILE BACKSPLASH
416	TELE	(none)	SC	RB-3	P	P	P	P	
420A	NURSE	NURSE	RF-1	RB-2	P	P	P	P	
420B	EQUIP ALCOVE	(none)	RF-1 / RF-3A&B	RB-2	P	-	P / WP	P	
420C	NURSE	NURSE	RF-1	RB-2	P	P	P	P	
421	TLT	TOILET - STAFF	CT-1	CT-2	CT-2 / P	CT-2 / P	CT-2 / P	CT-2 / P	
422	STAFF WORK RM	OFFICE	CPT-4	RB-2	P	P	P	P	
423	OFFICE	OFFICE	CPT-4	RB-2	P	P	P	P	
424	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	PROVIDE NURSE CALL
425	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
426	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
427	NURSE	NURSE	RF-1	RB-2	P	P	P	P	
428	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	PROVIDE NURSE CALL
429	NURSE	NURSE	RF-1	RB-2	P	P	P	P	
431	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
432	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
433	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
434	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
435	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
436	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
437	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
438	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
439	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
440	ELEC	(none)	SC	RB-3	P	P	P	P	
441	SUPPLY	(none)	RF-1	RB-2	P	P	P	P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
443	CONSULT RM	LOBBY	CPT-1	RB-1	P	P	P	P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
444	STOR	(none)	RF-1	RB-1	P	P	P	P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
445	NURSE	NURSE	RF-1	RB-2	P	P	P	P	
446	STOR.	(none)	RF-1	RB-2	P	P	P	P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
450	PROCEDURE	PROCEDURE	RF-5	RB-4	EP	EP	EP	EP	
451	PROCEDURE	PROCEDURE	RF-5	RB-4	EP	EP	EP	EP	
452	TOILET/ SHOWER	TOILET - STAFF	CT-1	CT-2	CT-2 / P	CT-2 / P	CT-2 / P	CT-2 / P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
453	CLEAN SUPPLY	(none)	RF-4A	RB-2	P	P	P	P	
454	JAN	(none)	RF-4A	RB-2	EP	EP	EP	EP	
455	SOILED UTILITY	(none)	RF-4A	RB-2	EP	EP	EP	EP	
456	TOILET/ SHOWER	TOILET - STAFF	CT-1	CT-2	CT-2 / P	CT-2 / P	CT-2 / P	CT-2 / P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
457	PROCEDURE	PROCEDURE	RF-5	RB-4	EP	EP	EP	EP	
458	PROCEDURE	PROCEDURE	RF-5	RB-4	EP	EP	EP	EP	
459	PROCEDURE	PROCEDURE	RF-5	RB-4	EP	EP	EP	EP	
460	SCOPE REPROCESS	PROCEDURE	RF-5	RB-4	EP	EP	EP	EP	
461	SCOPE STOR.	PROCEDURE	RF-5	RB-4	EP	EP	EP	EP	
462	SCOPE CLEAN	PROCEDURE	RF-5	RB-4	EP	EP	EP	EP	
463	PROCEDURE	PROCEDURE	RF-5	RB-4	EP	EP	EP	EP	
464	CART + SUPPLIES	(none)	RF-4A	RB-2	P	P	P	P	
480A	NURSE	NURSE	RF-1	RB-2	P	P	P	P	
480B	NURSE	NURSE	RF-1	RB-2	P	P	P	P	
480C	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
480D	EQUIP ALCOVE	(none)	RF-1 / RF-3A&B	RB-2	P / WP	P	-	P	
480E	NURSE	NURSE	RF-1	RB-2	P	P	P	P	
481	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
482	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
483	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	PROVIDE NURSE CALL
484	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
485	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
486	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
487	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
488	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
489	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
490	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
491	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
492	PREP/REC.	PREP/REC	RF-1 / RF-3A&B	RB-2	P	P	P	P	
493	TLT	TOILET - PATIENT	CT-1	CT-2	CT-2 / WC	CT-2 / WC	CT-2 / WC	CT-2 / WC	PROVIDE NURSE CALL
C400	CIRCULATION	(none)	CPT-1	RB-1	P	WC-3	P	P	
C410	CIRCULATION	LOBBY	CPT-1	RB-1	P	P	P	P	
C420	CIRCULATION	(none)	RF-1	RB-2	P	P	P	P	
C440	CIRCULATION	PATIENT CORR	RF-1	RB-2	P	P	P	P	PREP FLOOR AS REQUIRED FROM TILE DEMO W/ UNDERLAYMENT CEMENT FOR NEW FINISHES
C450	CORRIDOR	CLINICAL CORR		RB-2	P	P	P	P	
C480	CIRCULATION	(none)	RF-1	RB-2	P	P	P	P	
ST14	STAIR NO. 1	(none)							
ST24	STAIR NO. 2	(none)							

INTERIOR MATERIALS LEGEND

SECTION #	COMPONENT	FINISH CODE	COLOR /PATTERN	MANUFACTURER	MFG. NAME / NO.	COMMENTS
	ARCHITECTURAL WOODWORK					
	White Oak, Rift sawn screening	WD	Clear	ATLANTIC PLYWOOD or equal		CNC-cut shapes
	White Oak, Rift sawn baseboard	WD	Clear	ATLANTIC PLYWOOD or equal		
	ARCHITECTURAL MILLWORK					
	Cabinetry - Plastic Laminate (Custom Grade)	PLAM-1	340 Soft	ABET LAMINATI	Horizontal Grade	With 3mm PVC edgebanding
		PLAM-2	385 Sei Due	ABET LAMINATI	Horizontal Grade	With 3mm PVC edgebanding
		PLAM-3	Iconic Maple WM0047T	NEVAMAR	Horizontal Grade	With matching 3mm PVC edgebanding
	Wall Paneling - Toilet Rooms	PLAM-4	340 Soft	ABET LAMINATI	Horizontal Grade	With 3mm PVC edgebanding
	3mm PVC edgebanding	EB-1	Riviera Maple	CANPLAST INC.		Use with PLAM-1 and PLAM-2
	3mm PVA edgebanding	EB-2		CHARTER INDUSTRIES		Use with PLAM-3
	3mm PVC edgebanding - 1-5/16"	EB-3		DOELKEN/WOODTAPE		At Counter Top (CT-2)
	Cabinetry - Melamine Interiors		White	PANOLAM		at closed cabinets only
	Counter Top - Solid Surface	CT-1	Lar Sand G108	LG HAUSYS / HI-MACS	HI-MACS	See spec for color-matched sink
	Counter Top - Post-formed Plastic Laminate	CT-2				
	Counter Top - Post-formed Plastic Laminate	CT-3			Post formed Grade	
	Resin Panels at Check-in - 1/2"	RP-1	White	3FORM	CHROMA - Ghost / Sandstone finish	Vertical light box columns at check-in
	Resin Panels at Elevator Lobby - 1/2"	RP-2		3FORM		
	Resin Panels at Check-in desk fronts	RP-4	White	3FORM	CHROMA - White Out / Sandstone	
	Resin Panels at Nurse Stations - Pattern 1 - 3/8"	RP-5				[Nurse #457]
	Resin Panels at Nurse Stations - Pattern 2 - 3/8"	RP-6				[Nurse #481]
	Compact Laminate -					
09 65 13	**GLASS / GLAZING**					
	Glazing film			SOLYX		
Div 9	**FINISHES**					
09 51 00	**CEILINGS**					
	Ceiling Tile - 2x2 - Square Layin	[C1]	White	ARMSTRONG	ULTIMA #1910	with Exterior Hold-Down Clips at Vestibules.
	Ceiling Tile - 2x2 - High NRC - Tegular	[C2]	White	ARMSTRONG	ULTIMA Tegular - #1911	
	Ceiling Tile - 2x5 - High NRC - Tegular	[C3]	White	ARMSTRONG	ULTIMA Tegular - #	
	Exposed Suspension System		White	ARMSTRONG	Suprafine 9/16"	
09 65 13	**RESILIENT FLOORING**					
	Resilient Tile Plank - 9" x 48" - 20 mil	RF-1	62 Brined	JOHNSONITE	FREEDOM WOOD / Seasoned Oak	
	Resilient Tile Plank - 4-1/2" x 36" - 20 mil	RF-2	Sugar Maple - AROW8020	MANNINGTON / AMTICO	Signature Wood	at Lobby
	4B	RF-3A	Infinity Flare - ARO48420	MANNINGTON / AMTICO	ABSTRACT - Quantum - Square edge	[See pattern detail]
	Resilient Tile - 3" x 36"	RF-3B	Infinity Flare - ARO48420	MANNINGTON / AMTICO	ABSTRACT - Quantum - Square edge, Cross Grain	[See pattern detail]
	Resilient Tile - 12" x 12"	RF-3C	Infinity Flare - ARO48420	MANNINGTON / AMTICO	ABSTRACT - Quantum - Square edge, Cross Grain	[See pattern detail]
	Resilient Sheet Homogenious	RF-4A	NewGlacier 15364	MANNINGTON	BioSpec MD	[See pattern detail]
		RF-4B	Bright White 15246	MANNINGTON	BioSpec MD	[See pattern detail]
	Rubber roll goods with acoustic backing - 4.0mm	RF-5	Windflower	NORA	ENVIRONCARE - Acoustic	Heat welded seams; Dryfix Tape or NXT adhesive
	Resilient Tile Plank -	RF-6	[TBD]	ARMSTRONG	NATURAL CREATIONS / Mystix	
[redacted]	Sound Underlayment - Recycled Rubber		N/A	ECORE COMMERCIAL FLOORING	ECO SILENCE 5	used in conjunction with RF-2
						RF-1
09 65 13	**CERAMIC TILE**					
	Porcelain Tile - 12" x 24"	CT-1	Tobacco	BEST TILE	INDUS	with 3" x 24" bullnose trim
	Porcelain Tile - 2" x 1"	CT-2	[TBD]	DALTILE	KEYSTONES	Brickwork mosaic
	Wall tile -	CT-3	[TBD]	DALTILE	IDENTITY WALL	
	Glass Wall Tile	CT-4	[TBD]	ISLAND STONE	WAVELINE	
09 65 13	**RESILIENT BASE AND ACCESSORIES**					
	Resilient wall base - 4-1/4" inch sculpted	RB-1	179 Steel	JOHNSONITE	MILLWORKS - Reveal	
	Resilient wall base - 4"	RB-2		JOHNSONITE		
	Resilient wall base - 4"	RB-3		JOHNSONITE		
	Preformed sanitary rubber cove base	RB-4		NORA	Sanitary cove base - 6"	Heat-welded
09 68 00	**TILE CARPETING**					
	Carpet - 8" x 36"	CPT-1	Beech	INTERFACE	WALK THE PLANK	Herringbone Pattern
	Carpet - 9.85" x 39.4" - Accent	CPT-2	Gold Leaf CFP105	MILLIKEN	COLOR FIELDS - PAINTER	Ashlar Pattern
	Carpet - 24" x 24"	CPT-3	Noddle	BENTLEY	HIGH SCORE with NEXSTEP Cushion	Brick Pattern
	Carpet - 24" x 24"	CPT-4	Noddle	BENTLEY	MULTIPLAY with NEXSTEP Cushion	Monolithic Installation
09 91 00	**PAINTS AND COATINGS**					
	Paint - Walls - General Walls	P-1			Gloss Level: Eggshell or Satin	Matching door/window frames in Semi-gloss
	Paint - Walls - Accent	P-2			Gloss Level: Eggshell or Satin	Matching door/window frames in Semi-gloss
	Paint - Walls - Accent	P-3			Gloss Level: Eggshell or Satin	Matching door/window frames in Semi-gloss
	Paint - Walls - Accent	P-4			Gloss Level: Eggshell or Satin	Matching door/window frames in Semi-gloss
	Paint - Walls - Accent	P-5			Gloss Level: Eggshell or Satin	Matching door/window frames in Semi-gloss
	Paint - Walls - Accent	P-6			Gloss Level: Eggshell or Satin	Matching door/window frames in Semi-gloss
	Paint - Walls - Accent	P-7			Gloss Level: Eggshell or Satin	Matching door/window frames in Semi-gloss
	Epoxy Paint	EP				
	Sealed Concrete	SC		SHERWIN WILLIAMS	6	
	WALL COVERINGS					
	Vinyl Wallcovering - 20 oz	WC-1	Zinc	KOROSEAL	ARTE - Cordova	at plumbing wall
	Vinyl Wallcovering - 20 oz Type II - 54"W	WC-2	Shilling	D.L. COUCH	SOURCE ONE EXCL. / STREAMERS	
	Digital Vinyl Wallcovering	WC-3	[TBD]	DESIGNTEX	Type II - custom image with image royalty & printing	at Elevator Lobby
	Vinyl Wallcovering - 20 oz Type II - 54"W	WC-4				
	Vinyl Wallcovering - 20 oz Type II - 54"W	WC-5				
	WALL & DOOR PROTECTION					
	Corner Guards - 3"	CG-1		ACROVYN	SM-20 / 3000 Series	Full-Height - or as required
	Corner Guards - 2"	CG-2		ACROVYN	SSM-20 / 3000 Series	Full-Height - UND
	Corner Guards - 3" 135-degree	CG-3		ACROVYN	SM-20M / 3000 Series	Height as shown
	Corner Guards - 1-1/2" Stainless Steel	CG-4		IPC	Cement-on, Surface mount	Full Height
	Wall Protection - Rigid Sheet .060"	WP-1		ACROVYN	4000-series	To 4'-0"H - with top J-Trim, Inside corners, and Vertical Trim
	Wall Protection - Rigid Sheet .060"	WP-2		ACROVYN	4000-series	To 4'-0"H - with top J-Trim
	Wall Protection - Rigid Sheet .060"	WP-3		KOROSEAL	KOROGARD - Traffic Patterns	To 4'-0"H. At perimeter of Open Plan Work Area [123] - vertical seams to be centered on wall. Tight butt-joints, no vertical divider trim. All other locations, no vertical seams except at corners.
	Door Protection - .060"			ACROVYN	4000 - Series	See Door Schedule for Locations
	Wall Bumper	WB	933 Mission White	ACROVYN	SCR-50	With matching end caps
	Chair Rail	CR	933 Mission White	ACROVYN	FR-225	With matching end caps
Div. 10	**SPECIALTIES**					
	Track - Cubicle Curtain		White	INPRO CORP.	Optitrac Cubicle Track / Ball & Chain Carrier CE5038	
	Cubicle Curtains					
	Lockers		073 Champagne	PENCO	5-High Box, 12" wide x 15" deep	Include Sloped top, Z-Base, Combination lock & master key, Numbering
	Window Treatment		[TBD]	MECHOSHADE	Manual Shade - 1% and 5% light trans,ission. With valance	

ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

Reviewed for Code Compliance
Permits & Inspections Division
Approved with Conditions
Date: 05/03/16

COPYRIGHT 2016
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

PORTLAND GASTROENTEROLOGY CENTER

161 Marginal Way Portland, Maine

No.	Date	Description
		Revision Schedule

REGISTERED ARCHITECT
ANN M. FONTAINE-FISHER
NO. 4459
STATE OF MAINE

JOB NO.
14054

DRWN. CHK
Checker

SCALE:

ISSUE
PERMIT SET
03/18/16

TITLE
ROOM FINISH SCHEDULE

SHEET
A600

3/18/2016 5:32:09 PM