ELECTRICAL GENERAL NOTES

1. ALL GENERAL NOTES, SYMBOL LIST & DETAILS ARE TO BE CONSIDERED AS APPLICABLE TO ALL ELECTRICAL DRAWINGS FOR THIS PROJECT. SYMBOLS AND ABBREVIATIONS SHOWN ON THIS SHEET ARE FOR REFERENCE ONLY AND DO NOT INDICATE THEIR INCORPORATION IN THE DESIGN.
2. ALL WORK PERFORMED ON THIS CONTRACT SHALL BE DONE IN A NEAT AND WORKMANLIKE MANNER AND SHALL BE IN COMPLIANCE WITH NEC, NFPA, BOCA, OSHA, AND ALL APPLICABLE STATE AND LOCAL CODES AND ORDINANCES.
3. THESE DRAWINGS ARE, IN GENERAL, MADE TO SCALE BUT ALL MEASUREMENTS SHALL BE TAKEN FROM FIGURED DIMENSIONS, AND NOT BY SCALING.
4. THE ELECTRICAL CONTRACTOR SHALL CONFER WITH ALL OTHER TRADES RELATIVE TO THE LOCATION OF APPARATUS AND EQUIPMENT AND SELECT LOCATIONS SO AS NOT TO CONFLICT WITH WORK OF OTHER TRADES.
5. LIGHTING FIXTURE MANUFACTURERS NAME & MODEL NUMBER ARE USED FOR DESCRIPTIVE PURPOSES ONLY AND ARE INTENDED TO INDICATE THE STANDARD OF MATERIAL OR ARTICLES REQUIRED.
6. ALL EQUIPMENT SHOWN ON THESE DRAWINGS IS INTENDED TO BE GENERALLY REPRESENTATIVE OF THE EQUIPMENT WHICH WILL BE INSTALLED UNDER THIS CONTRACT. BUT IT SHALL NOT BE ASSUMED THAT THE DRAWINGS INDICATE THE SPECIFIC CONFIGURATION, ARRANGEMENT OR POINTS OF CONNECTION OF THE ACTUAL EQUIPMENT UNLESS NOTED OTHERWISE.
7. COORDINATE W/ CONTROLS CONTRACTOR TO PROVIDE POWER FOR ALL MISCELLANEOUS CONTROL OPERATORS AND PANELS.
8. CIRCUIT BREAKERS USED FOR LIGHTING CIRCUITS SHALL BE SWITCH DUTY RATED AND APPROVED FOR USE WITH H.I.D. FIXTURES. CIRCUIT BREAKERS USED FOR HVAC AND REFRIGERATION EQUIPMENT SHALL BE "HACR" RATED.
9. ALL HOME RUNS FOR LIGHTING OR POWER CIRCUITS LONGER THAN 150 FEET SHALL BE INCREASED ONE SIZE. (IE: #12 TO #10).
10. ALL BRANCH CIRCUIT AND FEEDER CONDUCTORS SHALL BE SIZED FOR THE O.C.D. RATING FOR THAT CIRCUIT ACCORDING TO NEC ART 310 UNLESS OTHERWISE INDICATED ON THESE DRAWINGS. IN NO CASE SHALL CONDUCTORS SMALLER THAN NO. 12 AWG BE USED FOR POWER OR LIGHTING CIRCUITS.
11. PROVIDE 3/8" NYLON ROPE IN ALL EMPTY SERVICE RACEWAYS.
12. ALL SLEEVES AND OTHER PENETRATIONS THRU FIRE RATED ASSEMBLIES SHALL BE SEALED AFTER CABLE INSTALLATION WITH A FIRE RETARDANT COMPOUND.
13. ALL FLUSH MOUNTED PANELBOARDS SHALL BE PROVIDED WITH (2) 1-1/4" EMPTY CONDUITS BETWEEN PANEL & SUSPENDED CEILING.
14. THE CONTRACTOR IS RESPONSIBLE FOR FIRESTOPPING AROUND ALL CONDUITS, CABLES AND ELECTRICAL EQUIPMENT AT ALL PARTITIONS PIERCED PER NEC 300-21 AND B.O.C.A.
15. THE CONTRACTOR IS RESPONSIBLE FOR MEETING ALL SEISMIC REQUIREMENTS FOR THE INSTALLATION OF ELECTRICAL EQUIPMENT UNDER B.O.C.A.
16. GROUNDING SHALL BE PER N.E.C. ARTICLE 250, INSTALL GROUNDING CONDUCTORS WITH ALL FEEDERS AND BRANCH CIRCUITS.
17. ALL WIRING SHALL BE IN CONDUIT.
18. REMOVE EQUIPMENT, FIXTURES AND DEVICES THAT ARE NOT BEING REUSED AND DISCARD. OWNER HAS THE OPTION TO KEEP ANY MATERIAL DESIRED. EXISTING FIXTURES SCHEDULED FOR REUSE SHALL BE CLEANED.

LIGHTING SYMBOLS

SYMBOLS	DESCRIPTIONS
	2'X2' RECESSED FLUORESCENT FIXTURE (NORMAL POWER)
	2'X2' RECESSED FLUORESCENT FIXTURE (LIFE SAFETY POWER)
	2'X4' RECESSED FLUORESCENT FIXTURE (NORMAL POWER)
	2'X4' RECESSED FLUORESCENT FIXTURE (LIFE SAFETY POWER)
	RECESSED DOWNLIGHT FIXTURE (NORMAL POWER)
	RECESSED DOWNLIGHT FIXTURE (LIFE SAFETY POWER)
	BARE LAMP FLUORESCENT STRIP - AS NOTED ON DRAWINGS.
	EMERGENCY EXIT SIGN, SEE LIGHTING FIXTURE SCHEDULE FOR SPECIFICATION.
	EMERGENCY LIGHTING FIXTURE BATTERY OPERATED. SEE LIGHTING FIXTURE SCHEDULE FOR SPECIFICATION.

GENERAL ABBREVIATIONS

ABBREVIATIONS	DESCRIPTIONS
ACU	AIR CONDITIONING UNIT
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AHU	AIR HANDLING UNIT
AIC	AMPERE INTERRUPTING CAPACITY
C	CONDUIT
CS	CONDUIT SLEEVE
CB	CIRCUIT BREAKER
℄	CENTER LINE
CR	CASEWORK RECESSED OUTLET
CLF	CURRENT LIMITING FUSE
CT	CURRENT TRANSFORMER
CTV	CABLE TELEVISION
CU	CONDENSING UNIT
CUH	CABINET UNIT HEATER
CWP	CONDENSER WATER PUMP
DT	DISTRIBUTION TRANSFORMER
DW	DISHWASHER
DWG	DRAWING
EBB	ELECTRIC BASEBOARD HEATER
EDH	ELECTRIC DUCT HEATER
EF	EXHAUST FAN
EUH	ELECTRIC UNIT HEATER
EWC	ELECTRIC WATER COOLER
EX	EXISTING EQUIPMENT (AS NOTED)
FACP	FIRE ALARM CONTROL PANEL
FBO	FURNISHED BY OWNER
FC	FAN COIL
GD	GARBAGE DISPOSER
GFCI	GROUND FAULT CIRCUIT INTERRUPTING
GND	GROUND
GRC	GALVANIZED RIGID STEEL CONDUIT
H	HUMIDIFIER
HD	HEAT DETECTOR
HH	HAND HOLE
HP	HORSEPOWER / HEAT PUMP
HPS	HIGH PRESSURE SODIUM
HRU	HEAT RECOVERY UNIT
HV	HIGH VOLTAGE
HWP	HOT WATER CIRC. PUMP
IG	ISOLATED GROUND
IR	INFRA-RED
KW	KILOWATT
KWH	KILOWATT HOUR
LIG	LONG/INSTANTANEOUS/GROUND FAULT
LTG	LIGHTING
MB	MAIN BREAKER
MC	METAL CLAD
MD	MAIN DISCONNECT
MDP	MAIN DISTRIBUTION PANEL
MH	MAN HOLE / METAL HALIDE
MI	MINERAL INSULATED
MLO	MAIN LUGS ONLY
MMC	MAINE MEDICAL CENTER
MTD	MOUNTED
MW	MICROWAVE
N/A	NOT APPLICABLE
NC	NORMALLY CLOSED
NEC	NATIONAL ELECTRICAL CODE (NFPA-70)
NF	NOT FUSED
NIC	NOT IN CONTRACT
NL	NIGHT LIGHT
NM	NON METALLIC
NO	NORMALLY OPEN
NTS	NOT TO SCALE
OC	OVER COUNTER OUTLET
OCD	OVERCURRENT DEVICE
PB	PULL BOX
PM	"PLUGMOLD" UTILIZED
PT	POTENTIAL TRANSFORMER
R	REMOVE
RECP	RECEPTACLE
REF	REFRIGERATOR
REQ'D	REQUIRED
RF	RETURN FAN
RGE	RANGE
RGS	RIGID GALVANIZED STEEL CONDUIT
RH	RANGE HOOD
SF	SUPPLY FAN
S/N	SOLID NEUTRAL
TBD	TO BE DETERMINED
TP	TAMPER PROOF
TV	TELEVISION
TYP	TYPICAL
UC	UNDER COUNTER
UNO	UNLESS NOTED OTHERWISE
WP	WEATHERPROOF
WM	INSTALL WITH "WIREMOLD"
XFMR	TRANSFORMER

PANEL & CIRCUIT SYMBOLS

SYMBOLS	DESCRIPTIONS DESCRIPTIONS
	PANELBOARD - FLUSH MOUNTED AT 6'-6" TO TOP.
	PANELBOARD - SURFACE MOUNTED AT 6'-6" TO TOP.
LP1-3 (PAR)	INDICATES PARTIAL CIRCUIT INDICATES CIRCUIT NUMBER INDICATES PANEL
	ELECTRICAL FEED TO EQUIPMENT; ARROW INDICATES HOMERUN TO PANELBOARD OR AS NOTED.
	INDICATES CIRCUIT IN CONDUIT RUN IN FLOOR OR UNDERGROUND.
	INDICATES CONTROL WIRING BY ELECTRICAL
T T	TRANSFORMER, SIZE & TYPE AS INDICATED
J C J C	JUNCTION BOX - SIZED IN ACCORDANCE WITH NEC - "C" INDICATES MOUNTING IN CEILING SPACE.
30NF	3 POLE, NON-FUSIBLE DISCONNECT SWITCH 30 = AMPACITY. VOLTAGE AS REQ'D.
40 60	3 POLE FUSIBLE DISCONNECT SWITCH 60 = CLIP SIZE, 40 = FUSE SIZE VOLTAGE AS REQ'D
3R	3 POLE WEATHERPROOF DISCONNECT SWITCH SIZE & CONFIGURATION AS NOTED ABOVE
MS	MANUAL STARTER - SIZE AS REQUIRED
	MOTOR, HP AS INDICATED COORDINATE W/ ACTUAL EQUIPMENT FURNISHED.
	COMBINATION MAGNETIC STARTER - NEMA SIZE AS REQUIRED (MINIMUM SIZE 1) PROVIDE W/ H-O-A SWITCH AND GREEN RUN LIGHT ON COVER.
	MAGNETIC STARTER - NEMA SIZE AS REQUIRED (MINIMUM SIZE 1) PROVIDE W/ H-O-A SWITCH AND GREEN RUN LIGHT ON COVER. . FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR. SIZE AS NOTED.
	MOTOR CONTROLLER - FURNISHED WITH MOTOR.
ATS	AUTOMATIC TRANSFER SWITCH
J	JUNCTION BOX IN ACCESSIBLE LOCATION WITH FLEXIBLE CONDUIT CONNECTION TO EQUIPMENT AS NOTED.

MISCELLANEOUS SYMBOLS

SYMBOLS	DESCRIPTIONS
	SWITCHES LOCATED IN THE SAME AREA SHALL BE GANGED UNDER COMMON PLATE WHENEVER PRACTICAL. GROUP SWITCHES, THERMOSTATS ETC. TOGETHER. SWITCHES SHALL BE LOCATED ON STRIKE SIDE OF DOOR. ADJUST TO MINIMIZE CUT OF BLOCK OR TILE. LOWERCASE LETTER IS SWITCH CONTROL GROUP.
S W	SPEAKER - CEILING MOUNT W - INDICATES WALL MOUNTED SPEAKER SM - INDICATES SOUND MASKING
	SECURITY CAMERA
AD DL	LINE VOLTAGE DOOR SWITCH. INSTALL IN HINGE SIDE OF DOOR JAMB WIRE TO JUNCTION BOX BEHIND EQUIPMENT IN ROOM
PP	DOOR PADDLE PUSHBUTTON
REC	RECORDER
SK	KEYPAD
ES	ELECTRONIC STRIKE
ES	PROVIDE 3/4" CONDUIT ROUTED CONCEALED TO ABOVE CEILING AND ASSOCIATED JUNCTION BOXES FOR FUTURE DOOR HARDWARE/ELECTRIC STRIKE
CR	CARD READER
CR	PROVIDE 3/4" CONDUIT ROUTED CONCEALED TO ABOVE CEILING AND ASSOCIATED JUNCTION BOXES FOR FUTURE CARD READERS WITH BLANK COVER, PROVIDE AS WEATHERPROOF WERE REQUIRED.
DOOR	DOOR CONTROLLER
PTE	EMERGENCY PUSH TO EXIT BUTTON
RTE	REQUEST TO EXIT SENSOR
ML	MAGNETIC LOCK
M	DOOR HOLD OPEN, RELEASE ON FIRE ALARM AND DAILY AT NIGHT EXACT TIME PROVIDED BY OWNER.

FIRE ALARM & LIFE SAFETY SYMBOLS

SYMBOLS	DESCRIPTIONS
F	FIRE ALARM PULL STATION MTD 48" A.F.F.
	SMOKE DETECTOR, CEILING MOUNTED. "I" DENOTES, TO BE USED FOR PRE-ALERT."E" DENOTES, TO BE CONNECTED TO ELEVATOR CONTROLLER."PR" DENOTES TO BE USED FOR PATIENT ROOM FOR PRE-ALERT TO NURSE STATIONS.
	DUCT MOUNTED SMOKE DETECTOR
RTS	REMOTE TEST STATION
HD 135° 200° I R	HEAT DETECTOR - TEMP. AS INDICATED, CEILING MOUNTED: F = FIXED TEMPERATURE, 135° UNLESS OTHERWISE NOTED R = RATE IF RISE R/F = COMBINATION RATE OF RISE AND FIXED TEMPERATURE
FS	VISUAL NOTIFICATION APPLIANCE MEETING A.D.A. REQUIREMENTS. MTD AT 6" BELOW CEILING OR +80" AFF, WHICHEVER IS LESS. (75 CANDELA)
HS	COMBINATION AUDIO/VISUAL NOTIFICATION APPLIANCE MEETING A.D.A. REQUIREMENTS. MTD AT 6" BELOW CEILING OR +80" AFF, WHICHEVER IS LESS. 75cd (CANDELA, OR AS NOTED. HORN/STROBE DEVICE.
D	FIRE ALARM SYSTEM MAGNETIC DOOR HOLDER, MATCH EXISTING, PROVIDE 120V FROM NEAREST NORMAL POWER PANEL IF REQUIRED.
DC	FIRE ALARM SYSTEM DOOR CLOSER
FACP	FIRE ALARM MAIN PANEL
FAAN	FIRE ALARM ANNUNCIATOR
F	4" RED SPRINKLER TROUBLE BELL MTD 80" AFF MOUNT 8' ABOVE GRADE
FS	SPRINKLER FLOW SWITCH. CONNECT TO FIRE ALARM SYSTEM
TS	SPRINKLER TAMPER SWITCH. CONNECT TO FIRE ALARM SYSTEM
PS	SPRINKLER PRESSURE SWITCH. CONNECT TO SPRINKLER TROUBLE BELL
F	MASTER BOX
MM	MONITOR MODULES
ZAM I	INITIATING RELAY MODULE. COORDINATE W/ OTHER TRADE ITEMS.
ZAM A	ZONE MONITOR DEVICE

DATA SYMBOLS

SYMBOLS	DESCRIPTIONS
	TELEPHONE OUTLET AT +18" OR AS NOTED. FURNISH (1) 3/4" CONDUIT FROM DEVICE DEVICE OUTLET BOX TO ACCESSIBLE SPACE ABOVE SUSPENDED CEILING PROVIDE TELEPHONE CABLE COMPLETE, TO TELEPHONE MOUNTING BOARD. WIRING TO BE CAT5. COLOR BY OWNER. W - INDICATES WALL MOUNT AT 48" W/POST TYPE PLATE.
	DUAL TELEPHONE/DATA OUTLET AT +18" OR AS NOTED. FURNISH (1) 1" CONDUIT FROM DEVICE OUTLET BOX TO ACCESSIBLE SPACE ABOVE SUSPENDED CEILING PROVIDE (1)TELEPHONE AND (2) DATA CABLE COMPLETE. TO NEW PATCH PANEL IN DATA CLOSET.
	DATA OUTLET AT +18" OR AS NOTED. FURNISH (1) 3/4" CONDUIT FROM DEVICE. OUTLET BOX TO ACCESSIBLE SPACE ABOVE SUSPENDED CEILING PROVIDE DATA CABLE COMPLETE, TO PATCH PANEL IN CLOSET.
AP	DATA OUTLET FOR WIRELESS ACCESS POINT MTD AT 6" BELOW CEILING OR ON CEILING AS NOTED. FURNISH (1) 3/4" CONDUIT FROM DEVICE OUTLET BOX TO ACCESSIBLE SPACE ABOVE SUSPENDED CEILING PROVIDE DATA CABLE COMPLETE, TO PATCH PANEL IN IT CLOSET.
AV	AUDIO VIDEO MTD AT +18" OR AS NOTED. FURNISH (1) 1-1/4" CONDUIT FROM DEVICE OUTLET BOX TO ACCESSIBLE SPACE ABOVE SUSPENDED CEILING OR TO FLOOR BOX AS SHOWN ON PLAN. PROVIDE COMPLETE WITH CABLE. INCLUDING BUT NOT LIMITED TO: VGA, HDMI, RCA, 3.5MM MINI JACK, AND CAT 6.
TV	TV OUTLET MTD ADJACENT TO RECEPTACLE AT +72" OR AS NOTED. . FURNISH (1) 3/4" CONDUIT FROM DEVICE OUTLET BOX TO ACCESSIBLE SPACE ABOVE SUSPENDED CEILING. PROVIDE COMPLETE WITH CABLE RG 6/U - 75 OHM, 18AWG SOLID CONDUCTOR, FFEP DIELECTRIC, FRPVC JACKET, CMP RATED WITH FOIL +63% TC BRAID. BELDEN OR EQUAL ROUTED TO CATV MOUNTING BOARD IN IT CLOSET.
D R	DATA CONNECTION/ QUANTITES AT FLOOR BOX WITH FURNITURE FEED. FURNISH (1) 1-1/2" CONDUIT FROM DEVICE OUTLET BOX TO ACCESSIBLE SPACE ABOVE SUSPENDED CEILING PROVIDE DATA CABLE COMPLETE, TO PATCH PANEL IN IT CLOSET.
TMB	3/4" PLYWOOD TELEPHONE TERMINAL BLOCK MOUNTING BOARD WITH #6 CU. GROUND AND DEDICATED DUPLEX CONVENIENCE OUTLET. PAINTED WITH 2 COATS OF FLAME RESISTANT GRAY PAINT. FURNISH IN ACCORDANCE WITH TELEPHONE Co. REQUIREMENTS. SIZE AS NOTED.

RECEPTACLE OUTLET SYMBOLS

SYMBOLS	DESCRIPTIONS
	LETTER IS CIRCUIT CONTROL GROUP. "42" INDICATES MOUNTED AT 42" A.F.F. "GFCI" / "GF" INDICATES GFI OUTLET (PROTECTS DOWNSTREAM RECEPTACLES ON SAME CIRCUIT.) "WM" INDICATES DEVICE MOUNTED IN "WIREMOLD" "E" INDICATES EXISTING "TP" INDICATES TAMPER PROOF "OC" INDICATES OVER COUNTER
	MOUNT WITH GROUND TERMINAL AT TOP. DEVICES SHALL BE HOSPITAL GRADE. SEE SPEC.
	SIMPLEX CONVENIENCE RECEPTACLE MOUNTED AT +18" OR AS NOTED.
	DUPLEX RECEPTACLE OUTLET NEMA 5-20R, HEAVY DUTY. MOUNTED AT +18" OR AS NOTED, SELF-ILLUMINATING, AND BACKPLATE. DEVICES SHALL BE RED WHEN CONNECTED TO CRITICAL OR EQUIPMENT PANELS.
	QUADRUPLEX RECEPTACLE OUTLET (DOUBLE DUPLEX) NEMA 5-20R, HEAVY DUTY. MOUNTED AT +18" OR AS NOTED, SELF-ILLUMINATING, AND BACKPLATE. DEVICES SHALL BE RED WHEN CONNECTED TO CRITICAL OR EQUIPMENT PANELS.
GF	GFCI DUPLEX RECEPTACLE OUTLET
R	RANGE OUTLET NEMA 14-50R ("D" INDICATES DRYER OUTLET NEMA 14-30R)
	SPECIAL PURPOSE CONNECTION.
	EUROPEAN 220V DUPLEX RECEPTACLE
	FLOOR SINGLE RECEPTACLE OUTLET W/ COVER. NEMA 5-20R
	FLOOR DUPLEX RECEPTACLE OUTLET W/ COVER. NEMA 5-20R
DW	FLOOR SPECIAL PURPOSE OUTLET LETTER(S) BESIDE SYMBOL INDICATES ACTUAL EQUIPMENT SERVED.

LIGHTING CONTROL SYMBOLS

SYMBOLSLS	DESCRIPTIONS
	SWITCHES LOCATED IN THE SAME AREA SHALL BE GANGED UNDER COMMON PLATE WHENEVER PRACTICAL. GROUP SWITCHES, THERMOSTATS ETC. TOGETHER. SWITCHES SHALL BE LOCATED ON STRIKE SIDE OF DOOR. ADJUST TO MINIMIZE CUT OF BLOCK OR TILE. LOWERCASE LETTER IS SWITCH CONTROL GROUP.
$	SINGLE POLE SWITCH MOUNTED AT +48" OR AS NOTED.
$3	THREE WAY SWITCH MOUNTED AT +48" OR AS NOTED.
$c	SLIDE CONTROL DIMMER AT +48" OR AS NOTED, PROVIDE SWITCH FOR FIXTURES ACTUALLY SERVED.
$P	SINGLE POLE SWITCH W/ PILOT LIGHT MOUNTED AT +48" OR AS NOTED.
$M	H.P. RATED MANUAL MOTOR STARTER (WEATHERPROOF WHERE OUTSIDE).
$OS OS2	OS - DUAL TECH. OCCUPANCY SENSOR WALL SWITCH - WATTSTOPPER DSW-100. OS2 - DUAL TECH. OCCUPANCY SENSOR TWO BUTTON/LOAD WALL SWITCH - WATTSTOPPER DSW-200 OR EQUAL
$x	LOW VOLTAGE SWITCH LIGHT MOUNTED AT +48" OR AS NOTED. THE LETTER INDICATES SWITCH GROUPING/RELAY #
OS	OCCUPANCY SENSOR (CEILING MOUNT) . COMPATIBLE WITH ROOM CONTROLLER/ SWITCHING SYSTEM OR/AND LIGHTING CONTROL PANEL. "H" DENOTES HIGH CEILING TYPE, "R" DENOTES HVAC RELAY.
H R 20A	ROOM CONTROLLER (ABOVE CEILING MOUNT) LRC - LOCAL RELAY CONTROL LDC - LOCAL DIMMING CONTROL NDC- NETWORK DIMMING CONTROL 924 - UL 924 LISTED DEVICE. THE # INDICATES NUMBER OF LOADS. ROOM CONTROLLERS: LRC - EQUALS EATON RC3; LDC - EQUALS EATON RC3D LDC WITH 924 - EQUALS EATON RC3DE NDC - EQUALS EATON RC3DE-PL-N AND RC-3TLB-OS1 OR RC-6TSB-PDR1 SWITCHES OR EQUAL. PROVIDE SYSTEM AS ROOM KITS.

NURSE CALL SYMBOLS

SYMBOLS	DESCRIPTIONS
PC	EMERGENCY/BATH STATION W/ PULL CORD MTD @ +44" AFF.
B	BEDSIDE STATION TO BE MOUNTED ON 3 GANG OUTLET BOX WITH 2 GANG PLASTER RING.
D	ROOM CORRIDOR LIGHT - CEILING MOUNTED OR WALL MOUNTED AT 78" AFF.
D Z	ZONE LIGHT - CEILING MOUNTED.
CC	CODE CALL PUSH BUTTON STATION MOUNTED @ 54" AFF
SA	NURSE CALL SYSTEM STAFF ASSIST STATION MOUNTED @ +54" AFF.
DS	NURSE CALL SYSTEM DUTY STATION MOUNTED @ +54" AFF
MAP	NURSE CALL ANNUNCIATOR PANEL, WALL MOUNTED
CE	NURSE CALL SYSTEM CENTRAL EQUIPMENT
TV	TELEVISION CONTROL WALL MOUNTED AT 90" AFF.
NC	NURSE CALL SYSTEM DESK CONSOLE

Stantec Consulting Services Inc.
482 Payne Road Scarborough Court
Scarborough, ME 04074-8929
Tel: (207) 883-3355 / Fax: (207) 883-3376
www.stantec.com

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/03/16

ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

COPYRIGHT 2016
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

PORTLAND GASTROENTEROLOGY CENTER

161 Marginal Way - Portland, Maine 04101

No.	Date	Description
Revision Schedule		

STATE OF MAINE
RICHARD A. NACCARATO
No. 10003
LICENSED
PROFESSIONAL ENGINEER
3/18/2016

JOB NO.
195210852

DRWN. MLC | CHK Checker

SCALE:

ISSUE
PERMIT SET
3/18/2016

TITLE
ELECTRICAL LEGEND AND GENERAL NOTES

SHEET
E001