Color profile: Generic CMYK printer profile
Composite Default screen

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 11/23/16

89.8 SQ FT

INTERNALLY ILLUMINATED (WHITE LED) LETTERS AND LOGO ON FABRICATED ALUMINUM RACEWAYS; PAINT RACEWAYS AKZO [408D1] TO MATCH MOUNTING SURFACE

LETTERS: 3/16" THICK TRANSLUCENT WHITE FACES; 1" BLUE TRIM CAP & RETURNS

LOGO: 3/16" THICK TRANSLUCENT WHITE FACES; GSP TRANS DELFT BLUE [230-97] VINYL ON FACE; 1" WHITE TRIM CAP & RETURNS

POWER SUPPLIES IN RACEWAYS; OWNER TO SUPPLY PRIMARY ELECTRICAL TO SIGN LOCATION

10134.2: INT. ILLUM. LETTERS ON RACEWAYS AND LOGO

SCALE: 3/8"=1'-0" **(2) SETS REQUIRED**

LOK-BOLT™ ANCHORING SYSTEM AS MFG BY POWERS FASTENERS, NEW ROCHELLE, NY OR EQUAL:

A PRE-ASSEMBLED SINGLE UNIT SLEEVE ANCHOR FOR ANCHORING INTO SOLID AND HOLLOW CONCRETE AND MASONRY SUBSTRATES

PATENTED COMPRESSION RING PULLS FIXTURE FLUSH TO THE WORK SURFACE

AVAILABLE IN CARBON STEEL AND TYPE 304 STAINLESS STEEL; SEVERAL HEAD STYLES

SIZE RANGE: ¼" DIA. x 5/8" TO ¾" DIA. x 7 ½"

SLEEVE-ANCHOR MOUNTING DETAIL

NOT TO SCALE

(2) ANCHORS EVERY 4' OF RACEWAY

STAINLESS STEEL, NON-CORROSIVE/NON-GALVANIC ACTING ANCHORS

ANCHORS SET INTO MORTAR JOINTS, NOT INTO MASONRY FACES

DRILL HOLES NO DEEPER THAN 3¼"

SEAL ALL PENETRATIONS WITH SILICONE ADHESIVE

LETTERS MOUNTING

SCALE: 1½"=1'-0"

Neokraft Signs Inc.
686 Main Street
Lewiston, Maine 04240
Telephone: 207.782.9654
Facsimile: 207.782.0009
1.800.339.2258
http://www.neokraft.com

Custom Sign Fabrication

These plans are the exclusive property of Neokraft Signs, Inc. and are the result of the original work of its employees. They are submitted to Neokraft's client for the sole purpose of consideration of whether to purchase these plans or to purchase from Neokraft a sign manufactured according to these plans.

Distribution or exhibition of these plans to anyone other than employees of said client, or use of these plans to construct a sign similar to the one embodied herein, is expressly forbidden. In the event that such exhibition or construction occurs, Neokraft expects to be reimbursed $1500 in compensation for time and effort entailed in creating these plans.

PERMIT

MAINE EYE CENTER
10134.X

LOCATION: 161 MARGINAL WAY
PORTLAND, ME
DRAWING NO.: 1 OF 3
DRAWN BY: DS REP.: PM
DATE: 09.26.2016
REVISED 10.05.2016
QUOTE: @1787
GEN REF.:

G:\DESIGN\10134.2 Maine Eye Center - il rw PRES 10-05-2016.cdr
Wednesday, October 05, 2016 7:59:21 AM

© COPYRIGHT 2016, BY NEOKRAFT SIGNS, INC.