



WALL LEGEND

	= WALLS, ELEMENTS OR FINISHES TO BE CAREFULLY DEMOD.
	= EXISTING WALLS, ELEMENTS OR FINISHES TO REMAIN & BE PROTECTED FROM DAMAGE

- SECOND FLOOR DEMOLITION NOTES:**
- 1) DEMO ALL EXISTING FINISH FLOORING IN ALL AREAS
 - 2) ALL EXISTING CEILING LIGHT FIXTURES TO REMAIN
 - 3) NO STRUCTURAL ELEMENTS ARE TO BE DEMOD.
 - 4) DEMO WORK SHALL BE PERFORMED IN A MANNER TO LIMIT DUST, DEBRIS & NOISE
 - 5) THIS BUILDING SHALL REMAIN OPEN FOR BUSINESS DURING CONSTRUCTION
 - 6) CUT OPENINGS IN WALLS @ LOCKER ROOMS AS INDICATED ON SHEET D.2, PATCH, REPAIR & PAINT WALLS TO REMAIN AS REQD.
 - 7) ALL EXISTING SINKS & COUNTER TOPS SHALL BE REMOVED & REPLACED
 - 8) ALL EXISTING TOILETS & URINALS SHALL BE TEMPORARILY REMOVED TO ALLOW FOR NEW WALL TILE WORK. REPLACE EXISTING TOILETS & URINALS ONCE WORK IS COMPLETE OR AS REQD.
 - 9) REMOVE ALL EXISTING TOILET PARTITION WALLS & DOORS & REPLACE W/ NEW AS REQD.
 - 10) ALL EXISTING SHOWER STALLS IN WOMEN'S LOCKER ROOM SHALL BE REMOVED
 - 11) ALL SHOWER PARTITION WALLS IN WOMEN'S LOCKER ROOM SHALL BE DEMOD. ALONG W/ ALL ASSOCIATED FIXTURES & CONTROLS
 - 12) ALL EXISTING LOCKER UNITS SHALL BE REMOVED & REPLACED W/ NEW UNITS AS REQD.
 - 13) ALL EXISTING LOCKER ROOM BENCHES SHALL BE REMOVED & REPLACED AS REQD.
 - 14) ALL AREAS AROUND DEMOD. ELEMENTS SHALL BE PATCHED, REPAIRED & PAINTED AS REQD. PER SCOPE OF WORK.
 - 14) ALL EXG. MECHANICAL CHASES SHALL REMAIN
 - 15) ALL SHOWER STALLS, ASSOCIATED FIXTURES, CONTROLS & FINISHES IN MEN'S LOCKER ROOM SHALL REMAIN

No.	Description	Date
A	Landlord Response	05.24.17
	Revision Schedule	

Project Info:
Planet Fitness Portland
 145 Marginal Way
 Portland, ME

Sheet Status:
 Latest Release: 05.24.17 - Rev. A
 Issued For: For Construction
 Org. Issue Date: April 12th, 2017

JOB NO:
 DRAFTED: MLN
 CHECKED: JMT

SCALE: 3/16" = 1'-0"

Sheet Title:
Second Floor Demolition Plan

Sheet Number:
D.2

① SECOND FLOOR DEMOLITION PLAN
 3/16" = 1'-0"