

Done



S0



LINTELS

1. THE FOLLOWING LINTELS SHALL BE USED FOR MASONRY OPENINGS, U.N.O. ON DRAWINGS:

MASONRY OPENING

LINTEL SIZE

UP TO 3'-0"

L 3 1/2 x 3 1/2 x 5/16

3'-1" TO 4'-6"

L 4 x 3 1/2 x 5/16 (LLV)

4'-7" TO 6'-0"

L 5 x 3 1/2 x 5/16 (LLV)

6'-1" TO 8'-0"

L 6 x 3 1/2 x 5/16 (LLV)

- 2. PROVIDE ONE ANGLE FOR EACH 4" WALL THICKNESS. FOR 6" WALL THICKNESS, PROVIDE WT OR BUILT-UP SECTION WITH PROPERTIES EQUAL TO OR GREATER THAN 1 1/2 TIMES THE ANGLES PROPERTIES FOR A 4" WALL THICKNESS.
- 3. PROVIDE 8" OF BEARING AT EACH END OF ALL LINTELS.
- 4. ALL EXTERIOR LINTELS SHALL BE HOT-DIPPED GALVANIZED.

Let me know if you need anything else.

Matt Gagnon, LEED A.P.

Project Manager

o/ 207.730.5566

d/ 207.303.3108

c/ 207.219.0015

cid:image003.jpg@01D2E367.678BAF70

160 Pleasant Hill Road, Scarborough, Maine 04074
landryfrench.com

On Nov 16, 2017, at 9:56 AM, Jeanie Bourke <jmb@portlandmaine.gov> wrote:

Hi Matt,

Do you have a new header detail for the new double door opening that you could send me?

Thanks,
Jeanie

Jeanie Bourke
Code Enforcement Officer/Plan Reviewer
Team Leader

City of Portland
Permitting and Inspections Department
389 Congress St. Rm 315
Portland, ME 04101
jmb@portlandmaine.gov
(207)874-8715

On Wed, Nov 15, 2017 at 3:29 PM, Matthew Gagnon <mgagnon@landryfrenchconstruction.com> wrote:

Jeanie,