

SECTION 09265

GYPSUM BOARD SHAFT-WALL ASSEMBLIES

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following:
1. Shaft enclosures.

1.2 DEFINITIONS

- A. Gypsum Board Construction Terminology: Refer to ASTM C 11 for definitions of terms for gypsum board construction not defined in this Section or in other referenced standards.

1.3 PERFORMANCE REQUIREMENTS

- A. Structural Performance:
1. Provide gypsum board shaft-wall assemblies capable of withstanding the full air-pressure loads indicated for maximum heights of partitions without failing and while maintaining an airtight and smoke-tight seal. Evidence of failure includes deflections exceeding limits indicated, bending stresses causing studs to break or to distort, and end-reaction shear causing track (runners) to bend or to shear and studs to become crippled.
 2. Provide gypsum board shaft-wall assemblies for horizontal duct enclosures capable of spanning distances indicated within deflection limits indicated.
 3. Air-pressure loads and deflection limits are specified in "Gypsum Board Shaft Wall" Article in Part 2.

1.4 SUBMITTALS

- A. Product Data: For each gypsum board shaft-wall assembly indicated.
- B. Fire-Test-Response Reports: From a qualified independent testing and inspecting agency substantiating each gypsum board shaft-wall assembly's required fire-resistance rating.
1. Include data substantiating that elevator entrances and other items that penetrate each gypsum board shaft-wall assembly do not negate fire-resistance rating.
- C. Research/Evaluation Reports: Evidence of compliance with building code in effect for Project, from a model code organization acceptable to authorities having jurisdiction that substantiate required fire-resistance rating for each gypsum board shaft-wall assembly.
- D. Acoustical-Test-Response Reports: From a qualified independent testing agency substantiating required STC rating for each gypsum board shaft-wall assembly.

1.5 QUALITY ASSURANCE

- A. Fire-Resistance-Rated Assemblies: Provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing and inspecting agency acceptable to authorities having jurisdiction.
 - 1. Fire-Resistance-Rated Assemblies: Indicated by design designations from FM's "Approval Guide, Building Products." and UL's "Fire Resistance Directory." [GA-600, "Fire Resistance Design Manual."
- B. STC-Rated Assemblies: For gypsum board shaft-wall assemblies indicated to have STC ratings, provide assembly materials and construction complying with requirements of assemblies whose STC ratings were determined according to ASTM E 90 and classified according to ASTM E 413 by a qualified independent testing agency.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials in original packages, containers, and bundles bearing brand name and identification of manufacturer or supplier.
- B. Store materials inside under cover and keep them dry and protected against damage from weather, direct sunlight, surface contamination, corrosion, construction traffic, and other causes. Stack gypsum panels flat on leveled supports off the ground to prevent sagging.

1.7 PROJECT CONDITIONS

- A. Comply with requirements for environmental conditions, room temperatures, and ventilation specified in Division 9 Section "Gypsum Board Assemblies."

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. American Gypsum Co.
 - 2. G-P Gypsum Corp.
 - 3. National Gypsum Company.
 - 4. United States Gypsum Co.

2.2 ASSEMBLY MATERIALS

- A. General: Provide materials and components complying with requirements of fire-resistance-rated assemblies indicated.
 - 1. Provide panels in maximum lengths available to eliminate or minimize end-to-end butt joints.
 - 2. Provide auxiliary materials complying with gypsum board shaft-wall assembly manufacturer's written recommendations.

- B. Steel Framing: ASTM C 645.
 - 1. Protective Coating: ASTM A 653/A 653M, G40 (Z120), hot-dip galvanized coating.
- C. Gypsum Liner Panels: Manufacturer's proprietary liner panels in 1-inch (25.4-mm) thickness and with moisture-resistant paper faces.
- D. Gypsum Wallboard: ASTM C 36, core type as required by fire-resistance-rated assembly indicated.
 - 1. Edges: Tapered.
- E. Accessories: Cornerbead, edge trim, and control joints of material and shapes specified in Division 9 Section "Gypsum Board Assemblies" that comply with gypsum board shaft-wall assembly manufacturer's written recommendations for application indicated.
- F. Gypsum Wallboard Joint-Treatment Materials: ASTM C 475 and as specified in Division 9 Section "Gypsum Board Assemblies."
- G. Steel Drill Screws: ASTM C 1002, unless otherwise indicated.
 - 1. Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch (0.84 to 2.84 mm) thick.
- H. Acoustical Sealant: As specified in Division 9 Section "Gypsum Board Assemblies."
- I. Sound Attenuation Blankets: ASTM C 665 for Type I, unfaced mineral-fiber-blanket insulation produced by combining thermosetting resins with mineral fibers manufactured from slag or rock wool.

2.3 GYPSUM BOARD SHAFT WALL

- A. Basis-of-Design Product: As indicated on Drawings by design designation of a qualified testing and inspecting agency.
- B. Sustained Air-Pressure Loads: 5 lbf/sq. ft. (0.24 kPa).
- C. Deflection Limit: $L/240$.
- D. Studs: Manufacturer's standard profile for repetitive members and corner and end members and for fire-resistance-rated assembly indicated.
 - 1. Depth: 2-1/2 inches (63.5 mm), unless noted otherwise.
 - 2. Minimum Base Metal Thickness: Manufacturer's standard thicknesses that comply with structural performance requirements for stud depth indicated.
- E. Track (Runner): Manufacturer's standard J-profile track with long-leg length as standard with manufacturer, but at least 2 inches (51 mm), in depth matching studs.
 - 1. Minimum Base Metal Thickness: Manufacturer's standard thicknesses that comply with structural performance requirements for stud depth indicated.
- F. Room-Side Finish: Gypsum board.

- G. Shaft-Side Finish: As indicated by fire-resistance-rated assembly design designation.
- H. Cavity Insulation: Sound attenuation blankets.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates to which gypsum board shaft-wall assemblies attach or abut, with Installer present, including hollow-metal frames, elevator hoistway door frames, cast-in anchors, and structural framing. Examine for compliance with requirements for installation tolerances and other conditions affecting performance. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. General: Install gypsum board shaft-wall assemblies to comply with requirements of fire-resistance-rated assemblies indicated, manufacturer's written installation instructions, and the following:
 - 1. ASTM C 754 for installing steel framing.
 - 2. Division 9 Section "Gypsum Board Assemblies" for applying and finishing panels.
- B. Do not bridge building expansion joints with shaft-wall assemblies; frame both sides of joints with furring and other support.
- C. Install supplementary framing in gypsum board shaft-wall assemblies around openings and as required for blocking, bracing, and support of gravity and pullout loads of fixtures, equipment, services, heavy trim, furnishings, and similar items that cannot be supported directly by shaft-wall assembly framing.
- D. At penetrations in shaft wall, maintain fire-resistance rating of shaft-wall assembly by installing supplementary steel framing around perimeter of penetration and fire protection behind boxes containing wiring devices, elevator call buttons, elevator floor indicators, and similar items.
- E. Isolate gypsum finish panels from building structure to prevent cracking of finish panels while maintaining continuity of fire-rated construction.
- F. Install control joints to maintain fire-resistance rating of assemblies.
- G. Seal gypsum board shaft walls with acoustical sealant at perimeter of each assembly where it abuts other work and at joints and penetrations within each assembly. Install acoustical sealant to withstand dislocation by air-pressure differential between shaft and external spaces; maintain an airtight and smoke-tight seal; and comply with manufacturer's written instructions or ASTM C 919, whichever is more stringent.

END OF SECTION