

ROOM FINISH SCHEDULE PUBLIC SPACES & TYPICAL UNIT										
NUMBER	ROOM NAME	FLOOR	BASE MATL	WALLS				CEILING	Height	NOTES
				N	S	E	W			
000	PARKING	ASPHALT	-		*	*		OPEN		*PAINT 3 WALLS SURROUNDING STAIR S1; PAINT PARTIAL EAST WALL TO TRASH [006] AND CORR [004] ACCENT COLORS
001	STORAGE	CONC	VINYL	PAINT	PAINT	PAINT	PAINT	OPEN		
002	ELEC	CONC	-	PAINT	PAINT	PAINT	PAINT	OPEN		
003	MECH	CONC	-	PAINT	PAINT	PAINT	PAINT	OPEN		
004	CORR	VCT(1)	VINYL	PAINT	PAINT	PAINT	PAINT	C1 / VANDAL CLIPS	8' - 0"	(1) FLOOR PATTERN
005	ELEV MACH		CONC							
006	TRASH	CONC	VINYL	PAINT	PAINT	PAINT	PAINT	OPEN		
007	PARKING	ASPHALT	-			*		OPEN		*PAINT 3 WALLS SURROUNDING STAIR S3 ACCENT COLOR
008	METERING	CONC	-					OPEN		
009	STORAGE (ASPHALT)	-		PAINT	PAINT	PAINT	PAINT	OPEN		
100A	CORR	VCT(1)	VINYL	PAINT	PAINT	PAINT	PAINT	C1	8' - 0"	(1) FLOOR PATTERN
100B	CORR	VCT(1)	VINYL	PAINT	PAINT	PAINT	PAINT	C1	8' - 0"	(1) FLOOR PATTERN
100C	BATHRM	SHEET VINYL - 2	VINYL	PAINT	PAINT	PAINT	PAINT 2	C2	8' - 0"	
100D	JAN.	VCT	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
100E	LAUNDRY	SLIP-RESISTANT VCT	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
100F	CUSTODIAN	VCT	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
100G	COMMUNITY	VCT(1)	VINYL	PAINT 2	PAINT	PAINT	VINYL WC	C2	8' - 0"	(1) FLOOR PATTERN
100H	KITCHEN	VCT(1)	VINYL	PAINT 2	PAINT	PAINT	VINYL WC	C2	8' - 0"	(1) FLOOR PATTERN
100K	VEST	WALK OFF MAT TILES	VINYL	PAINT	PAINT	PAINT	PAINT	OPEN		
100L	CORR	VCT(1)	VINYL	PAINT	PAINT	PAINT	PAINT	C1	8' - 0"	(1) FLOOR PATTERN
100M	T/D	VCT	VINYL	PAINT	PAINT	PAINT	PAINT			
100N	TEL/DATA	VCT	VINYL	PAINT	PAINT	PAINT	PAINT			
101A	KITCHEN	SHEET VINYL - 1	VINYL	PAINT	PAINT 2	PAINT 2	PAINT	C2	8' - 0"	ACCENT PAINT COLOR 2 WALLS BEHIND CABINETS
101B	BATH	SHEET VINYL - 2	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101C	BATH	SHEET VINYL - 2	SHEET VINYL - 2	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	FLASH COVE BASE
101D	BEDRM 2	CARPET 2	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101E	CLST	CARPET 2	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101F	CLST	CARPET 2	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101G	BEDRM 1	CARPET 2	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101H	BEDRM 3	CARPET 2	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101J	CLST	CARPET 2	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101K	STOR.	SHEET VINYL - 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101L	LINEN	SHEET VINYL - 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101M	LIVING	SHEET VINYL - 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101N	CLST	SHEET VINYL - 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
101P	CORR	SHEET VINYL - 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
102A	KITCHEN	SHEET VINYL - 1	VINYL	PAINT	PAINT 2	PAINT 2	PAINT	C2	8' - 0"	ACCENT PAINT COLOR 2 WALLS BEHIND CABINETS
102B	CLST	SHEET VINYL - 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
102C	LINEN	SHEET VINYL - 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
102D	BATHRM	SHEET VINYL - 2	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
102E	CLST	CARPET 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
102F	BEDRM 1	CARPET 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
102G	LIVING	SHEET VINYL - 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	
102H	CORR	SHEET VINYL - 1	VINYL	PAINT	PAINT	PAINT	PAINT	C2	8' - 0"	

ROOM FINISH SCHEDULE STAIRS										
NUMBER	ROOM NAME	FLOOR	BASE MATL	WALLS				CEILING	Height	NOTES
				N	S	E	W			
S1	STAIR	RUBBER TREAD / RISER / LANDINGS U.N.O	VINYL	PAINT	PAINT	PAINT	PAINT	C2		WALK-OFF TILE MATS AT GROUND LANDINGS
S2	STAIR	RUBBER TREAD / RISER / LANDINGS U.N.O	VINYL	PAINT	PAINT	PAINT	PAINT	C2		WALK-OFF TILE MATS AT GROUND LANDINGS
S3	STAIR	RUBBER TREAD / RISER / LANDINGS U.N.O	VINYL	PAINT	PAINT	PAINT	PAINT	C2		WALK-OFF TILE MATS AT GROUND LANDINGS

GENERAL NOTES:

- ALL KITCHENS IN UNITS ARE TO BE ADAPTABLE, UNO AS ACCESSIBLE. THEREFOR, ALL SURFACES THAT MAY EVENTUALLY BE EXPOSED SHALL BE COMPLETELY FINISHED (PAINT, BASE, PIPING INSULATION KITS, FLOORING) PRIOR TO INSTALLATION OF CABINETRY.
- ALL TOILETS WITHIN UNITS ARE TO BE ADAPTABLE, UNO AS ACCESSIBLE. THEREFOR, ALL SURFACES THAT MAY EVENTUALLY BE EXPOSED SHALL BE COMPLETELY FINISHED (PAINT, BASE, PIPING INSULATION KITS, FLOORING) PRIOR TO INSTALLATION OF CABINETRY.
- ALL SINKS IN KITCHEN AND TOILETS WITHIN UNITS SHALL BE EQUIPPED WITH PIPING INSULATION KITS.
- PAINT 1, 2, 3 ETC. ARE MEANT TO DESIGNATE CHANGE IN WALL COLOR. THE PROJECT COULD CONSIST OF UP TO 25 PAINT COLORS FOR BOTH INTERIOR AND EXTERIOR COATINGS. A COLOR SCHEDULE WILL BE PROVIDED ONCE CONTRACT IS AWARDED.
- AT STAIR S2, ACOUSTICAL WALL PANELS ARE TO BE PAINTED UNTILIZING UP TO 5 COLORS. IN A RANDOMIZED PATTERN.
- ELEVATOR FLOOR SHALL BE RUBBER TILE - SEE SPEC.




48 DARTMOUTH STREET
 PORTLAND, MAINE 04101
 207-775-1059
 www.pdtarchts.com

COPYRIGHT
 PDT Architects
 Reuse or reproduction of the
 contents of this document is not
 permitted without written
 permission of PDT Architects.



307 CLIMBERLAND AVENUE
 PORTLAND, MAINE 04101
 www.avestahousing.org

Pearl Place 2
 184 Pearl Street



JOB NO.
10020

DRWN. CHK
Checker

SCALE:

ISSUE
08/03/11

TITLE
ROOM FINISH
SCHEDULE

SHEET
A602