

SECTION 095113 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes acoustical panels and exposed suspension systems for ceilings.

1.3 DEFINITIONS

- A. AC: Articulation Class.
- B. CAC: Ceiling Attenuation Class.
- C. LR: Light Reflectance coefficient.
- D. NRC: Noise Reduction Coefficient.

1.4 COORDINATION

- A. Coordinate layout and installation of acoustical panels and suspension system with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, fire-suppression system, and partition assemblies.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. LEED Submittals: Follow submittal requirements of Division 01 Section "Submittal Requirements" and provide product data on the LEED Materials Documentation Cover Sheet attached as an Appendix to Division 01 Section "Sustainable Design and LEED Requirements."
- C. Samples for Verification: For each component indicated and for each exposed finish required, prepared on Samples of size indicated below.
  - 1. Acoustical Panel: Set of 6-inch- square Samples of each type, color, pattern, and texture.
  - 2. Exposed Suspension System Members, Moldings, and Trim: Set of 12-inch- long Samples of each type, finish, and color.

## PEARL PLACE 2

### 1.6 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for each acoustical panel ceiling.

### 1.7 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For finishes to include in maintenance manuals.

### 1.8 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Acoustical Ceiling Panels: Full-size panels equal to 2.0 percent of quantity installed.
  - 2. Suspension System Components: Quantity of each exposed component equal to 2.0 percent of quantity installed.
  - 3. Hold-Down Clips: Equal to 2.0 percent of quantity installed.

### 1.9 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Qualified according to NVLAP for testing indicated.

### 1.10 DELIVERY, STORAGE, AND HANDLING

- A. Deliver acoustical panels, suspension system components, and accessories to Project site in original, unopened packages and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.
- B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.
- C. Handle acoustical panels carefully to avoid chipping edges or damaging units in any way.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Acoustical ceiling shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
- B. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - 1. Flame-Spread Index: Comply with ASTM E 1264 for Class A materials.

2. Smoke-Developed Index: 50 or less.
- C. Fire-Resistance Ratings: Comply with ASTM E 119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  1. Indicate design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.

## 2.2 ACOUSTICAL PANELS, GENERAL

- A. Meet requirements of LEED for Homes Mid-Rise 2010 Credit MR 2.2 as defined in Division 01 Section "Sustainable Design and LEED Requirements" for this type of material.
- B. Source Limitations:
  1. Acoustical Ceiling Panel: Obtain each type through one source from a single manufacturer.
  2. Suspension System: Obtain each type through one source from a single manufacturer.
- C. Acoustical Panel Standard: Provide manufacturer's standard panels of configuration indicated that comply with ASTM E 1264 classifications as designated by types, patterns, acoustical ratings, and light reflectances, unless otherwise indicated.
  1. Mounting Method for Measuring NRC: Type E-400; plenum mounting in which face of test specimen is 15-3/4 inches away from test surface per ASTM E 795.
- D. Acoustical Panel Colors and Patterns: Match appearance characteristics indicated for each product type.
  1. Where appearance characteristics of acoustical panels are indicated by referencing pattern designations in ASTM E 1264 and not manufacturers' proprietary product designations, provide products selected by Architect from each manufacturer's full range that comply with requirements indicated for type, pattern, color, light reflectance, acoustical performance, edge detail, and size.
- E. Broad Spectrum Antimicrobial Fungicide and Bactericide Treatment: Where indicated, provide acoustical panels treated with manufacturer's standard antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested according to ASTM D 3273 and evaluated according to ASTM D 3274 or ASTM G 21.

## 2.3 ACOUSTICAL PANELS FOR ACOUSTICAL PANEL CEILING

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
  1. Armstrong World Industries, Inc.; Fine Fissured No. 1732.
  2. BPB USA; HHF-154.
  3. USG Interiors, Inc.; Radar ClimaPlus No. 2220.

## PEARL PLACE 2

- B. Classification: Provide panels complying with ASTM E 1264 for type, form, and pattern as follows:
  - 1. Type and Form: Type III, mineral base with painted finish; Form 1, nodular or 2, water felted.
  - 2. Pattern: CE (perforated, small holes and lightly textured) and I (embossed).
- C. Color: White.
- D. LR: Not less than 0.80.
- E. NRC: Not less than 0.55.
- F. CAC: Not less than 35.
- G. Edge/Joint Detail: Beveled tegular.
- H. Thickness: 5/8 inch.
- I. Modular Size: 24 by 24 inches.
- J. Antimicrobial Treatment: Broad spectrum fungicide and bactericide based.

### 2.4 METAL SUSPENSION SYSTEMS, GENERAL

- A. Metal Suspension System Standard: Provide manufacturer's standard direct-hung metal suspension systems of types, structural classifications, and finishes indicated that comply with applicable requirements in ASTM C 635.
- B. Finishes and Colors, General: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes. Provide manufacturer's standard factory-applied finish for type of system indicated.
  - 1. High-Humidity Finish: Comply with ASTM C 635 requirements for "Coating Classification for Severe Environment Performance" where high-humidity finishes are indicated.
- C. Attachment Devices: Size for five times the design load indicated in ASTM C 635, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.
- D. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
  - 1. Zinc-Coated, Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
  - 2. Size: Select wire diameter so its stress at 3 times hanger design load (ASTM C 635, Table 1, "Direct Hung") will be less than yield stress of wire, but provide not less than 0.106-inch- diameter wire.
- E. Hanger Rods or Flat Hangers: Mild steel, zinc coated or protected with rust-inhibitive paint.

- F. Angle Hangers: Angles with legs not less than 7/8 inch wide; formed with 0.04-inch- thick, galvanized steel sheet complying with ASTM A 653/A 653M, G90 coating designation; with bolted connections and 5/16-inch- diameter bolts.
- G. Seismic Stabilizer Bars: Manufacturer's standard perimeter stabilizers designed to accommodate seismic forces.
- H. Seismic Struts: Manufacturer's standard compression struts designed to accommodate seismic forces.
- I. Seismic Clips: Manufacturer's standard seismic clips designed and spaced to secure acoustical panels in-place.
- J. Hold-Down Clips: Where indicated, provide manufacturer's standard hold-down clips spaced 24 inches o.c. on all cross tees.
  - 1. Available Products: UHDC by Armstrong or L15 by USG.

2.5 METAL SUSPENSION SYSTEM FOR ACOUSTICAL PANEL CEILING Insert drawing designation

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Prelude 15/16" Exposed Tee System (7300 Series); Armstrong World Industries, Inc.
  - 2. S11 System; Celotex Corporation.
  - 3. 1200 System; Chicago Metallic Corporation.
  - 4. DX 24 System; USG Interiors, Inc.
- B. Wide-Face, Capped, Double-Web, Steel Suspension System: Main and cross runners roll formed from cold-rolled steel sheet, prepainted, electrolytically zinc coated, or hot-dip galvanized according to ASTM A 653/A 653M, not less than G30 coating designation, with prefinished 15/16-inch- wide metal caps on flanges.
  - 1. Structural Classification: Intermediate-duty system.
  - 2. End Condition of Cross Runners: Override (stepped) or butt-edge type, as standard with manufacturer.
  - 3. Face Design: Flat, flush.
  - 4. Cap Material: Steel cold-rolled sheet.
  - 5. Cap Finish: Painted white.

2.6 METAL EDGE MOLDINGS AND TRIM

- A. Roll-Formed, Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that comply with seismic design requirements; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension system runners.

1. Provide manufacturer's standard edge moldings that fit acoustical panel edge details and suspension systems indicated and that match width and configuration of exposed runners, unless otherwise indicated.
2. For circular penetrations of ceiling, provide edge moldings fabricated to diameter required to fit penetration exactly.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.

1. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 PREPARATION

- A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders, and comply with layout shown on reflected ceiling plans.

#### 3.3 INSTALLATION

- A. General: Install acoustical panel ceilings to comply with ASTM C 636/C 636M and seismic design requirements indicated, according to manufacturer's written instructions and CISCA's "Ceiling Systems Handbook."

- B. Suspend ceiling hangers from building's structural members and as follows:

1. Hangers shall be single lengths of wire without splices; coordinate lengths in deep ceiling cavities.
2. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
3. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
4. Splay hangers only where required and, if permitted with fire-resistance-rated ceilings, to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
5. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.
6. Secure wire hangers to ceiling suspension members and to supports above with a minimum of three tight turns. Connect hangers directly either to structures or to inserts,

- eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
7. Secure flat, angle, channel, and rod hangers to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices that are secure and appropriate for both structure to which hangers are attached and type of hanger involved. Install hangers in a manner that will not cause them to deteriorate or fail due to age, corrosion, or elevated temperatures.
  8. Do not support ceilings directly from permanent metal forms or floor deck. Fasten hangers to cast-in-place hanger inserts, postinstalled mechanical or adhesive anchors, or power-actuated fasteners that extend through forms into concrete.
  9. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
  10. Do not attach hangers to steel deck tabs.
  11. Do not attach hangers to steel roof deck. Attach hangers to structural members.
  12. Space hangers not more than 48 inches o.c. along each member supported directly from hangers, unless otherwise indicated; provide hangers not more than 8 inches from ends of each member.
  13. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.
- C. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or postinstalled anchors.
- D. Suspension system shall be reinforced to support diffusers, light fixtures and any additional members. Install hanger wires to grid at each corner of light fixtures. Coordinate location with electrical and other trades.
1. Each individual fixture and attachment with combined weight of 56 pounds or less shall have two 12-gage wire hangers attached at diagonal corners of the fixture. These wires shall be slack. Fixtures and attachments with a combined weight of greater than 56 pounds shall be independently supported from the structure at all four corners.
- E. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
1. Screw attach moldings to substrate at intervals not more than 16 inches o.c. and not more than 3 inches from ends, leveling with ceiling suspension system to a tolerance of 1/8 inch in 12 feet. Miter corners accurately and connect securely.
  2. Do not use exposed fasteners, including pop rivets, on moldings and trim.
- F. Install suspension system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- G. Install acoustical panels with undamaged edges and fit accurately into suspension system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide a neat, precise fit.
1. Arrange directionally patterned acoustical panels as follows:

- a. As indicated on reflected ceiling plans.
  - b. Install panels with pattern running in one direction parallel to long axis of space.
2. For reveal-edged panels on suspension system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.
  3. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.
  4. Install hold-down clips in areas within 10 feet of exterior doors or vestibule doors; space as recommended by panel manufacturer's written instructions, unless otherwise indicated or required.

### 3.4 FIELD QUALITY CONTROL

- A. Above-Ceiling Observation: Before Contractor installs acoustical panel ceilings, conduct an above-ceiling observation and report deficiencies in the Work observed. Do not proceed with installation of acoustical panels until deficiencies have been corrected.
  1. Complete the following in areas to receive gypsum board ceilings:
    - a. Installation of 80 percent of lighting fixtures, powered for operation.
    - b. Installation, insulation, and leak and pressure testing of water piping systems.
    - c. Installation of air-duct systems.
    - d. Installation of air devices.
    - e. Installation of mechanical system control-air tubing.
    - f. Installation of penetration firestopping.

### 3.5 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 095113